

# **DocBook to LaTeX Publishing**

---

## **User Manual**

Ref A1 Ed. 09

## COLLABORATORS

|               |   |              |                              |
|---------------|---|--------------|------------------------------|
|               | <i>TITLE :</i><br>DocBook to LaTeX Publishing |              | <i>REFERENCE :</i><br>Ref A1 |
| <i>ACTION</i> | <i>NAME</i>                                   | <i>DATE</i>  | <i>SIGNATURE</i>             |
| WRITTEN BY    | Benoît Guillon                                | 20 July 2016 |                              |
| REVIEWED BY   | Andreas Hoenen                                | 20 July 2016 |                              |

## REVISION HISTORY

| NUMBER | DATE       | DESCRIPTION   | NAME       |
|--------|------------|---|------------|
| 01     | 2009/05/05 | The manual does not include the change history anymore. The change history is now in the release note. The XSL Parameters are now described as reference entries. | B. Guillon |
| 02     | 2009/06/21 | Add a section about the new <code>set</code> support, and a section about how to extend the verbatim rendering.   | B. Guillon |
| 03     | 2011/07/03 | Add a section about the new HTML table support, and a section about the PyPI distribution.  | B. Guillon |
| 04     | 2012/04/10 | Update documentation for release 0.3.3.   | B. Guillon |
| 05     | 2012/06/03 | Update documentation for release 0.3.4.   | B. Guillon |
| 06     | 2014/05/26 | Update documentation for release 0.3.5.   | B. Guillon |
| 07     | 2015/05/15 | Update documentation for release 0.3.6: add the ability to use a <code>texpost python</code> plugin, and new index capabilities.                                  | B. Guillon |
| 08     | 2015/08/06 | Update documentation for release 0.3.7: add section Section <a href="#">4.5</a> .   | B. Guillon |

---

**REVISION HISTORY**

---

| NUMBER | DATE       | DESCRIPTION  | NAME                         |
|--------|------------|--|------------------------------|
| 09     | 2016/07/20 | Update documentation for release 0.3.8: add appendix Appendix <a href="#">B</a> , and sections Section <a href="#">5.7.1</a> , Section <a href="#">4.9</a> . | B. Guillon / Karl O.<br>Pinc |

---

# Contents

|          |  |          |
|----------|--|----------|
| <b>1</b> | <b>Documentation</b>                         | <b>1</b> |
| 1.1      | Reference . . . . .                          | 1        |
| <b>2</b> | <b>Introduction</b>                          | <b>2</b> |
| 2.1      | What about DB2LaTeX? . . . . .               | 2        |
| 2.2      | Features . . . . .                           | 2        |
| 2.3      | Version . . . . .                            | 3        |
| 2.4      | Change History . . . . .                     | 3        |
| 2.5      | Publishing Principles . . . . .              | 3        |
| 2.5.1    | Backend Drivers . . . . .                    | 4        |
| 2.5.2    | XSL Stylesheets . . . . .                    | 4        |
| 2.5.3    | Python Post Processing . . . . .             | 4        |
| 2.5.4    | LaTeX Style Package . . . . .                | 4        |
| <b>3</b> | <b>Installing the Package</b>                | <b>5</b> |
| 3.1      | Content . . . . .                            | 5        |
| 3.2      | Installing on Unix like Systems . . . . .    | 5        |
| 3.2.1    | Dblatex Packages . . . . .                   | 5        |
| 3.2.2    | Dependencies . . . . .                       | 6        |
| 3.2.3    | Installation . . . . .                       | 6        |
| 3.2.3.1  | Installing the dependencies . . . . .        | 6        |
| 3.2.3.2  | Installing from the source tarball . . . . . | 6        |
| 3.2.3.3  | Installing from the Python Egg . . . . .     | 7        |
| 3.3      | Installing on Windows . . . . .              | 7        |
| 3.3.1    | Dependencies . . . . .                       | 7        |
| 3.3.2    | Installation . . . . .                       | 7        |
| 3.3.2.1  | Installing xsltproc . . . . .                | 7        |
| 3.3.2.2  | Installing MiKTeX . . . . .                  | 7        |
| 3.3.2.3  | Installing dblatex . . . . .                 | 8        |

---

|          |  |          |
|----------|--|----------|
| <b>4</b> | <b>Using dblatex</b>   | <b>9</b> |
| 4.1      | Reference . . . . .  | 9        |
|          | <code>dblatex</code> . . . . .   | 9        |
| 4.2      | Output Formatting Style . . . . .  | 12       |
|          | 4.2.1 How it works . . . . .   | 12       |
|          | 4.2.2 Adding a New Formatting Style . . . . .                            | 13       |
| 4.3      | Publishing Outputs . . . . .   | 14       |
|          | 4.3.1 Publishing a single document . . . . .                             | 14       |
|          | 4.3.2 Publishing a Set of Books . . . . .                                | 14       |
| 4.4      | Global Page Setup . . . . .  | 15       |
| 4.5      | Chapter and Section numbering . . . . .                                  | 16       |
|          | 4.5.1 Depth of Section numbering and Table Of Content . . . . .          | 16       |
|          | 4.5.2 Using the <code>latex</code> style for section numbering . . . . . | 17       |
|          | 4.5.3 Using the <code>label</code> attribute . . . . .                   | 18       |
| 4.6      | Figure Inclusion . . . . .   | 18       |
|          | 4.6.1 Presentation . . . . .   | 18       |
|          | 4.6.2 Converting on the fly . . . . .                                    | 19       |
|          | 4.6.3 Paths Lookup . . . . .   | 19       |
| 4.7      | Creating Tables . . . . .  | 20       |
|          | 4.7.1 Limitations . . . . .  | 20       |
|          | 4.7.2 Table Width . . . . .  | 20       |
|          | 4.7.3 Tables without <code>colwidth</code> . . . . .                     | 21       |
|          | 4.7.4 Tables with mixed <code>colspec</code> . . . . .                   | 21       |
|          | 4.7.5 Tables with proportional and fixed <code>colwidth</code> . . . . . | 21       |
|          | 4.7.6 Tables with fixed <code>colwidths</code> . . . . .                 | 22       |
|          | 4.7.7 Automatic Column Width . . . . .                                   | 22       |
|          | 4.7.7.1 Global Setting . . . . .   | 22       |
|          | 4.7.7.2 Local Setting . . . . .  | 23       |
|          | 4.7.8 Informal Table LaTeX Styles . . . . .                              | 24       |
|          | 4.7.9 Tables with <code>morerows</code> . . . . .                        | 25       |
|          | 4.7.10 Landscape tables . . . . .  | 25       |
|          | 4.7.11 Smaller tables . . . . .  | 27       |
|          | 4.7.12 Coloured tables . . . . .   | 27       |
|          | 4.7.13 HTML Tables . . . . .   | 28       |
| 4.8      | Writing Mathematics . . . . .  | 30       |
|          | 4.8.1 Writing LaTeX Mathematical Equations . . . . .                     | 30       |
|          | 4.8.1.1 Presentation . . . . .   | 30       |
|          | 4.8.1.2 Implementation choice . . . . .                                  | 30       |
|          | 4.8.1.3 Mathematical Delimiters . . . . .                                | 30       |

---

|            |   |    |
|------------|---|----|
| 4.8.1.4    | Compatibility                             | 31 |
| 4.8.1.5    | Examples                                  | 31 |
| 4.8.2      | Writing MathML equations                  | 32 |
| 4.9        | Musical Notation                          | 33 |
| 4.10       | Extending the Verbatim Rendering          | 33 |
| 4.10.1     | Dblatex Specific Options                  | 33 |
| 4.10.2     | Scaling Feature                           | 33 |
| 4.10.3     | Formatting embedded elements              | 34 |
| 4.10.4     | Creating a new Verbatim Environment       | 35 |
| 4.11       | Creating an Index                         | 36 |
| 4.11.1     | Internationalized Indexes                 | 36 |
| 4.11.1.1   | Indexing Tools                            | 36 |
| 4.11.1.2   | Index Sorting                             | 36 |
| 4.12       | Writing a Bibliography                    | 37 |
| 4.12.1     | Using Bibliography Entries                | 37 |
| 4.12.2     | Using BibTeX Databases                    | 38 |
| 4.12.3     | Natbib Citations                          | 39 |
| 4.13       | Document Revisions                        | 39 |
| 4.14       | Locale Support                            | 39 |
| 4.14.1     | Document Encoding                         | 39 |
| 4.14.2     | Babel Languages                           | 40 |
| 4.14.3     | CJK Languages                             | 40 |
| 4.14.3.1   | Korean Support                            | 40 |
| 4.14.4     | Mixing the languages                      | 40 |
| 4.15       | Using XRefsyle and Olinks                 | 40 |
| 4.15.1     | Specific xrefstyle for <code>ulink</code> | 41 |
| 4.16       | Footnotes                                 | 41 |
| 4.16.1     | Footnote Numbering Scope                  | 41 |
| 4.16.2     | End Notes                                 | 41 |
| 4.16.2.1   | Writing a document with endnotes          | 41 |
| 4.16.2.2   | Setup Properties                          | 42 |
| 4.16.2.3   | Endnotes Setup from scratch               | 42 |
| 4.16.2.4   | Grouping Endnotes                         | 43 |
| 4.16.2.4.1 | Adding new Groups                         | 43 |
| 4.16.2.4.2 | Formatting the Headings text              | 43 |
| 4.16.2.4.3 | LaTeX Command to make the Headings        | 43 |
| 4.16.2.4.4 | Endnotes Counter Scope                    | 44 |

|          |  |           |
|----------|--|-----------|
| <b>5</b> | <b>Customization</b>                                 | <b>45</b> |
| 5.1      | Using XSL Parameters                                 | 45        |
| 5.2      | Setting Command line Parameters                      | 45        |
| 5.3      | Using Processing Instructions                        | 45        |
| 5.4      | XSL User Stylesheet                                  | 46        |
| 5.4.1    | Changing the XSL parameter values                    | 46        |
| 5.4.2    | Overriding some templates                            | 47        |
| 5.5      | Customized LaTeX style                               | 48        |
| 5.5.1    | Reusing an existing LaTeX style                      | 48        |
| 5.5.2    | Package options                                      | 49        |
| 5.5.3    | Needed packages                                      | 49        |
| 5.5.4    | DocBook interface                                    | 49        |
| 5.5.5    | Debugging your Style                                 | 50        |
| 5.6      | Latex post process script                            | 51        |
| 5.6.1    | Post latex compilations                              | 51        |
| 5.6.2    | Post processing with a Python Plugin                 | 51        |
| 5.7      | Dblatex Configuration File                           | 52        |
| 5.7.1    | XML Configuration File Format                        | 52        |
| 5.7.1.1  | <config>   | 53        |
| 5.7.1.2  | <latex>  | 53        |
| 5.7.1.3  | <xslt>   | 54        |
| 5.7.1.4  | <imagedata>  | 54        |
| 5.7.1.5  | <converter>  | 54        |
| 5.7.1.6  | <command>  | 55        |
| 5.7.1.7  | <options>  | 55        |
| 5.7.2    | Deprecated Text Configuration File Format            | 55        |
| 5.7.3    | Configuration Paths                                  | 56        |
| 5.8      | Customization Precedence                             | 56        |
| <b>6</b> | <b>FAQ</b>   | <b>58</b> |
| 6.1      | My images are too big. What can I do?                | 58        |
| 6.2      | How can I have the PDF fit to height by default?     | 58        |
| 6.3      | How can I have all the PDF hyperlinks in blue color? | 58        |
| 6.4      | How can I remove that stupid float rules?            | 59        |
| 6.5      | My long tables don't split in several pages. Why?    | 59        |
| 6.6      | I cannot put a table in an example.                  | 59        |
| 6.7      | I cannot compile my cyrillic document. Why?          | 59        |

---

|          |  |           |
|----------|--|-----------|
| <b>7</b> | <b>Thanks</b>                          | <b>60</b> |
| 7.1      | Sponsors . . . . .                     | 60        |
| 7.2      | Contributors . . . . .                 | 60        |
| 7.3      | Pioners . . . . .                      | 60        |
| <b>A</b> | <b>Dblatex XSL Parameter Reference</b> | <b>61</b> |
| A.1      | Admonitions . . . . .                  | 61        |
|          | figure.caution . . . . .               | 61        |
|          | figure.important . . . . .             | 61        |
|          | figure.note . . . . .                  | 62        |
|          | figure.tip . . . . .                   | 62        |
|          | figure.warning . . . . .               | 62        |
| A.2      | Callouts . . . . .                     | 62        |
|          | callout.linkends.hot . . . . .         | 62        |
|          | calloutlist.style . . . . .            | 63        |
|          | callout.markup.circled . . . . .       | 63        |
|          | co.linkends.show . . . . .             | 63        |
|          | imageobjectco.hide . . . . .           | 63        |
| A.3      | ToC/LoT/Index Generation . . . . .     | 64        |
|          | doc.lot.show . . . . .                 | 64        |
|          | doc.toc.show . . . . .                 | 64        |
|          | titleabbrev.in.toc . . . . .           | 64        |
|          | toc.section.depth . . . . .            | 65        |
|          | bibliography.tocdepth . . . . .        | 65        |
|          | colophon.tocdepth . . . . .            | 65        |
|          | dedication.tocdepth . . . . .          | 66        |
|          | preface.tocdepth . . . . .             | 66        |
|          | glossary.tocdepth . . . . .            | 66        |
|          | index.tocdepth . . . . .               | 67        |
|          | latex.index.tool . . . . .             | 67        |
|          | latex.index.language . . . . .         | 68        |
|          | refentry.tocdepth . . . . .            | 68        |
| A.4      | Processor Extensions . . . . .         | 68        |
|          | alt.use . . . . .                      | 68        |
|          | tex.math.in.alt . . . . .              | 69        |
| A.5      | Automatic labelling . . . . .          | 69        |
|          | bibliography.numbered . . . . .        | 69        |
|          | glossary.numbered . . . . .            | 69        |
|          | index.numbered . . . . .               | 70        |

---



|                                       |    |
|---------------------------------------|----|
| refentry.numbered . . . . .           | 70 |
| A.6 Meta/*Info . . . . .              | 71 |
| doc.pdfcreator.show . . . . .         | 71 |
| make.single.year.ranges . . . . .     | 71 |
| make.year.ranges . . . . .            | 71 |
| A.7 Reference Pages . . . . .         | 72 |
| funcsynopsis.decoration . . . . .     | 72 |
| funcsynopsis.style . . . . .          | 72 |
| function.parens . . . . .             | 72 |
| refclass.suppress . . . . .           | 72 |
| refentry.generate.name . . . . .      | 73 |
| refentry.xref.manvolnum . . . . .     | 73 |
| A.8 Tables . . . . .                  | 73 |
| newtbl.autowidth . . . . .            | 73 |
| newtbl.bgcolor.thead . . . . .        | 74 |
| newtbl.default.colsep . . . . .       | 74 |
| newtbl.default.rowsep . . . . .       | 75 |
| newtbl.format.tbody . . . . .         | 75 |
| newtbl.format.tfoot . . . . .         | 75 |
| newtbl.format.thead . . . . .         | 75 |
| newtbl.use.hhline . . . . .           | 76 |
| table.continue.caption . . . . .      | 76 |
| table.default.position . . . . .      | 76 |
| table.default.tabstyle . . . . .      | 76 |
| table.in.float . . . . .              | 77 |
| table.title.top . . . . .             | 77 |
| default.table.rules . . . . .         | 78 |
| default.table.width . . . . .         | 78 |
| A.9 Linking . . . . .                 | 79 |
| latex.hyperparam . . . . .            | 79 |
| Olink Parameters . . . . .            | 79 |
| A.10 Cross References . . . . .       | 80 |
| insert.xref.page.number . . . . .     | 80 |
| xref.hypermarkup . . . . .            | 81 |
| A.11 Lists . . . . .                  | 81 |
| term.breakline . . . . .              | 81 |
| variablelist.term.separator . . . . . | 81 |
| A.12 QAndASet . . . . .               | 82 |
| qanda.defaultlabel . . . . .          | 82 |

|                                      |    |
|--------------------------------------|----|
| A.13 Bibliography . . . . .          | 82 |
| biblioentry.item.separator . . . . . | 82 |
| biblioentry.numbered . . . . .       | 82 |
| citation.default.style . . . . .     | 83 |
| citation.natbib.options . . . . .    | 83 |
| citation.natbib.use . . . . .        | 83 |
| latex.bibfiles . . . . .             | 84 |
| latex.biblio.output . . . . .        | 84 |
| latex.biblio.style . . . . .         | 84 |
| latex.bibwidelabel . . . . .         | 85 |
| A.14 Glossary . . . . .              | 85 |
| glossterm.auto.link . . . . .        | 85 |
| A.15 Miscellaneous . . . . .         | 85 |
| annotation.support . . . . .         | 85 |
| beginpage.as.pagebreak . . . . .     | 86 |
| doc.section.depth . . . . .          | 86 |
| endnotes.heading.command . . . . .   | 86 |
| endnotes.heading.groups . . . . .    | 87 |
| endnotes.heading.style . . . . .     | 87 |
| endnotes.properties . . . . .        | 87 |
| equation.default.position . . . . .  | 88 |
| example.default.position . . . . .   | 88 |
| example.float.type . . . . .         | 89 |
| figure.anchor.top . . . . .          | 89 |
| figure.default.position . . . . .    | 90 |
| figure.title.top . . . . .           | 90 |
| filename.as.url . . . . .            | 90 |
| footnote.as.endnote . . . . .        | 90 |
| hyphenation.format . . . . .         | 91 |
| linenumbering.scope . . . . .        | 91 |
| linenumbering.default . . . . .      | 92 |
| linenumbering.everyNth . . . . .     | 92 |
| literal.layout.options . . . . .     | 92 |
| literal.lines.showall . . . . .      | 93 |
| literal.width.ignore . . . . .       | 93 |
| literal.class . . . . .              | 93 |
| literal.role . . . . .               | 93 |
| literal.environment . . . . .        | 94 |
| literal.extensions . . . . .         | 94 |

|  |     |
|--|-----|
| mediaobject.caption.style . . . . .          | 95  |
| monoseq.hyphenation . . . . .                | 95  |
| monoseq.small . . . . .                      | 95  |
| pdf.annot.options . . . . .                  | 96  |
| segmentedlist.as.table . . . . .             | 96  |
| seg.item.separator . . . . .                 | 97  |
| show.comments . . . . .                      | 97  |
| texlive.version . . . . .                    | 97  |
| ulink.footnotes . . . . .                    | 98  |
| ulink.show . . . . .                         | 98  |
| xref.with.number.and.title . . . . .         | 99  |
| A.16 Graphics . . . . .                      | 99  |
| imagedata.boxed . . . . .                    | 99  |
| imagedata.default.scale . . . . .            | 99  |
| imagedata.file.check . . . . .               | 100 |
| keep.relative.image.uris . . . . .           | 100 |
| A.17 Chunning . . . . .                      | 100 |
| set.book.num . . . . .                       | 100 |
| use.id.as.filename . . . . .                 | 101 |
| A.18 Pagination and General Styles . . . . . | 101 |
| page.height . . . . .                        | 101 |
| page.margin.bottom . . . . .                 | 101 |
| page.margin.inner . . . . .                  | 102 |
| page.margin.outer . . . . .                  | 102 |
| page.margin.top . . . . .                    | 102 |
| page.width . . . . .                         | 103 |
| paper.type . . . . .                         | 103 |
| geometry.options . . . . .                   | 103 |
| doc.alignment . . . . .                      | 104 |
| doc.collab.show . . . . .                    | 104 |
| doc.layout . . . . .                         | 104 |
| doc.publisher.show . . . . .                 | 104 |
| draft.mode . . . . .                         | 105 |
| draft.watermark . . . . .                    | 105 |
| latex.engine.options . . . . .               | 105 |
| latex.class.article . . . . .                | 106 |
| latex.class.book . . . . .                   | 106 |
| latex.class.options . . . . .                | 106 |
| latex.encoding . . . . .                     | 107 |

---

|   |            |
|---|------------|
| <code>latex.unicode.use</code>                    | 107        |
| <code>latex.output.revhistory</code>              | 107        |
| A.19 Font Families                                | 107        |
| <code>body.font.family</code>                     | 107        |
| <code>cjk.font</code>                             | 108        |
| <code>monospace.font.family</code>                | 108        |
| <code>sans.font.family</code>                     | 108        |
| <code>xetex.font</code>                           | 109        |
| A.20 Localization                                 | 109        |
| <code>korean.package</code>                       | 109        |
| <code>latex.babel.language</code>                 | 110        |
| <code>latex.babel.use</code>                      | 110        |
| A.21 Prepress                                     | 110        |
| <code>crop.marks</code>                           | 110        |
| <code>crop.paper.type</code>                      | 110        |
| <code>crop.page.width</code>                      | 111        |
| <code>crop.page.height</code>                     | 111        |
| <code>crop.mode</code>                            | 112        |
| <code>crop.options</code>                         | 112        |
| <b>B Dblatex Processing Instruction Reference</b> | <b>113</b> |
| B.1 Bibliography                                  | 113        |
| <code>bibtex</code>                               | 113        |
| <code>dblatex citestyle</code>                    | 114        |
| B.2 LaTeX   | 114        |
| <code>latex</code>                                | 114        |
| B.3 Miscellaneous                                 | 115        |
| <code>dblatex angle</code>                        | 115        |
| <code>texmath delimiters</code>                   | 116        |
| B.4 Tables  | 116        |
| <code>dblatex bgcolor</code>                      | 116        |
| <code>dblatex table-width</code>                  | 117        |
| B.5 Lists   | 118        |
| <code>dblatex autowidth</code>                    | 118        |
| <code>dblatex colwidth</code>                     | 119        |
| <code>dblatex list-presentation</code>            | 120        |
| <b>8 Index</b>                                    | <b>121</b> |

# List of Figures

|   |    |
|---|----|
| 2.1 Transforming Process . . . . .                  | 3  |
| 4.1 Parameter Lengths used for Page Setup . . . . . | 16 |

# List of Tables

4.1 [An HTML Table](#) . . . . . 29

# List of Examples

|      |   |    |
|------|---|----|
| 4.1  | Choosing the DB2LaTeX style . . . . .                         | 12 |
| 4.2  | Figure inclusion . . . . .                                    | 19 |
| 4.3  | Figure conversion . . . . .                                   | 19 |
| 4.4  | Figures lookup . . . . .                                      | 19 |
| 4.5  | Equation taken from TDG . . . . .                             | 30 |
| 4.6  | Equation with user delimiters . . . . .                       | 31 |
| 4.7  | Inlined Equation . . . . .                                    | 31 |
| 4.8  | Equation in a block . . . . .                                 | 31 |
| 4.9  | Equation in a float . . . . .                                 | 32 |
| 4.10 | Equation without a title . . . . .                            | 32 |
| 4.11 | Index Entry . . . . .   | 36 |
| 4.12 | XSL Index Language Setup . . . . .                            | 37 |
| 4.13 | A Bibliography . . . . .                                      | 37 |
| 4.14 | Bibliography using BibTeX databases . . . . .                 | 38 |
| 4.15 | Writing a document with endnotes . . . . .                    | 41 |
| 5.1  | Table width specified with a Processing Instruction . . . . . | 46 |
| 5.2  | Overriding templates . . . . .                                | 48 |
| 5.3  | Reused LaTeX style . . . . .                                  | 49 |
| 5.4  | Texpost Python Plugin Example . . . . .                       | 51 |
| 5.5  | User Manual Configuration File . . . . .                      | 52 |
| 5.6  | Customization Precedence . . . . .                            | 57 |
| A.1  | Configuring with latex.hyperparam . . . . .                   | 79 |

# Chapter 1

## Documentation

### 1.1 Reference

[TDG] Norman Walsh and Leonard Muellner, *DocBook: The Definitive Guide*, Copyright © 1999, 2000, 2001 O'Reilly & Associates, Inc., 156592-580-7, O'Reilly.



## Chapter 2

# Introduction

### 2.1 What about DB2LaTeX?

**Dblatex** started as a **DB2LaTeX** clone, but since then many things have changed and new features have been added or (hopefully) improved. Now, the portion of shared code is small if any, and the **dbl**atex purpose is different from **DB2LaTeX** on these points:

- The project is end-user oriented, that is, it tries to hide as much as possible the latex compiling stuff by providing a single clean script to produce directly DVI, PostScript and PDF output.
- The actual output rendering is done not only by the XSL stylesheets transformation, but also by a dedicated LaTeX package. The goal is to allow a deep LaTeX customisation without changing the XSL stylesheets.
- Post-processing is done by Python, to make publication faster, convert the images if needed, and do the whole compilation.

### 2.2 Features

With **dbl**atex you can:

- transform a DocBook XML/SGML book or article to pure LaTeX,
  - compile the temporary LaTeX file with **latex**, **pdflatex**, or **xelatex** to produce DVI, PostScript and PDF files,
  - publish a set of books,
  - convert on the fly the figures included in the document,
  - have cross references with hot links,
  - olink to other documents built with **dbl**atex,
  - write complex tables,
  - write several bibliographies,
  - reuse BibTeX bibliographies,
  - use callouts on program listings or on images,
  - create an index with **makeindex** or **xindy**,
  - write mathematical equations in LaTeX,
  - write mathematical equations in MathML,
-

- have revision bars,
- customise the output rendering with an XSL configuration file,
- use your own LaTeX style package.

## 2.3 Version

This manual is for dblatex version 0.3.8.

## 2.4 Change History

See the [Release Notes](#) in *Release Notes for dblatex* to have the dblatex change history.

## 2.5 Publishing Principles

Dblatex transforms a DocBook XML/SGML document to LaTeX. Once transformed into LaTeX, standard LaTeX tools are used to produce DVI, Postscript or PDF files.

Figure 2.1 explains the process applied. It shows the tools used and the steps. The emphasized tools are provided by the package.




Figure 2.1: Transforming Process

### 2.5.1 Backend Drivers

The main script supports the following LaTeX backend drivers:

#### **dvips**

The driver calls **latex**, and produces DVI, Postscript and at the end PDF files. Latex natively accepts only EPS graphics. The drawback is that converting to PDF can take a while.

#### **pdftex**

The driver calls **pdflatex**, to directly produce PDF files. The conversion is fast, the file size is smaller. Pdflatex natively accepts PDF, PNG, JPEG, and TIFF graphics.

#### **xetex**

The driver calls **xelatex**, to directly produce PDF files through the **XeTeX** engine. This engine natively supports UTF-8 which improves multilingual support.

### 2.5.2 XSL Stylesheets

The XSL stylesheets located under `xsl/` are used to transform from XML to “raw” LaTeX. The main file is `latex_book_fast.xsl`, that includes the other stylesheets of the directory.

### 2.5.3 Python Post Processing

Actually the XSL stylesheets does not produce valid LaTeX. The reason is that some DocBook processing is too complex or too time-consuming for XSL transforming. Besides, some extra actions need sometimes to be done such like figure conversion. Here are the main actions done by Python Post processing:

- Transform the entities to valid LaTeX characters (e.g. `&nbsp;` is transformed to `'~'`). Python is suited and performant for this task.
- Convert the figures to be compatible with the backend driver. See Section 4.6 for more detail.
- Force some hyphenation in tables or for typed words.
- Do the whole LaTeX compilation sequence thanks to the **rubber** compilation engine.

### 2.5.4 LaTeX Style Package

Once valid LaTeX is available, the LaTeX style package (`docbook.sty`) under `latex/style/` is used to customize the output rendering. It includes the other files of the directory. You can also provide your own LaTeX style (cf. Chapter 5).

## Chapter 3

# Installing the Package

### 3.1 Content

The package contains the following:

**docs/**

Contains the files of this document.

**latex/**

Contains all the latex stuff: LaTeX style files, logos, and scripts to compile the LaTeX output.

**scripts/**

Several scripts, including the main script of the package.

**xsl/**

XSL stylesheets.

**tests/**

Test files.

### 3.2 Installing on Unix like Systems

#### 3.2.1 Dblatex Packages

Dblatex is packaged for these Systems or Distributions:

- [Linux Debian, Ubuntu](#),
- [Linux OpenSUSE \(RPM\), Linux Fedora \(RPM\)](#),
- [FreeBSD, NetBSD](#),
- [Mac OS X \(Fink\)](#).

If you are installing on one of these distributions, follow their recommended way of installation, and you can safely ignore the next sections that give details for installing dblatex from the source tarball.

### 3.2.2 Dependencies

To work, the following items must be available:

- An XSLT. `xsltproc` is the default XSLT used, but one can also use `4suite` or `saxon`.
- The XML DocBook DTD.
- A recent LaTeX distribution. The configure script checks that the needed latex packages are available.
- Python  $\geq 2.4$ .

### 3.2.3 Installation

#### 3.2.3.1 Installing the dependencies

To use the package, install properly the dependencies:

1. Install Python if necessary.
2. Install LaTeX.
3. Install the XSLT. By default `xsltproc` is used.
4. Install the XML DocBook DTD.
5. Create a catalog file, that defines where to find the DTD. Here is an example:

```
PUBLIC "-//OASIS//DTD DocBook XML V4.1.2//EN"
    "file:///usr/local/share/xml/docbook/dtd/4.1.2/docbookx.dtd"
```

If the XML Gnome tools are available, it's a good idea to create an XML catalog by using `xmlcatalog` such like this:

```
% xmlcatalog --noout --create mycatalog
% xmlcatalog --noout --add 'public' '-//OASIS//DTD DocBook XML V4.1.2//EN' \
    'file://path/to/4.1.2/docbookx.dtd' mycatalog
```

6. Add the catalog path to the `SGML_CATALOG_FILES` variable:

```
export SGML_CATALOG_FILES=$SGML_CATALOG_FILES:/path/to/mycatalog
```

You can skip this step if you configure the `dblatex` installation with the `--catalogs` option.

#### 3.2.3.2 Installing from the source tarball

The steps to follow are the following:

1. Untar the ball. For a bziped release, do as follow:

```
% tar xvfj dblatex-x.x.x.tar.bz2
```

For a gzipped release, do as follow:

```
% tar xvfz dblatex-x.x.x.tar.gz
```

2. Install the package. The installation script preliminary checks the dependencies. In the example, the `dblatex` script is installed under `/usr/local/bin` and the other files are installed under `/usr/local/share/dblatex`. Besides, the `--catalogs` option tells where to find the catalogs.

```
% cd dblatex-x.x.x
% python ./setup.py install --prefix=/usr/local --catalogs=/path/to/mycatalog
```

### 3.2.3.3 Installing from the Python Egg

Since version 0.3.2 dblatex is distributed as a Python Egg in the [Python Package Index \(PyPI\)](#). It requires to have `easy_install` installed.

The procedure to follow is:

1. Call simply `easy_install`:

```
% easy_install dblatex
Searching for dblatex
Reading http://pypi.python.org/simple/dblatex/
Reading http://dblatex.sf.net
Best match: dblatex 0.3.1.1
Downloading http://pypi.python.org/packages/2.5/d/dblatex/dblatex-0.3.1.1-py2.5.egg#md5 ←
=8520d596e473ff544eb9dc5175d7ae
Processing dblatex-0.3.1.1-py2.5.egg
creating /path/to/dblatex-0.3.1.1-py2.5.egg
Extracting dblatex-0.3.1.1-py2.5.egg to /path/to
Adding dblatex 0.3.1.1 to easy-install.pth file
Installing dblatex script to /path/to

Installed /path/to/dblatex-0.3.1.1-py2.5.egg
```

That's it!

## 3.3 Installing on Windows

The following packages to install and the procedure is for a native Windows installation. If you want to use dblatex via Cygwin instead, you should consider it like a unix like install.

### 3.3.1 Dependencies

The following applications are required:

- An XSLT. `xsltproc` is the default XSLT used, but one can also use [4suite](#).
- The XML DocBook DTD.
- [MiKTeX](#) > 2.5.
- [Python](#) >= 2.4.

### 3.3.2 Installation

#### 3.3.2.1 Installing xsltproc

You can download the binaries and getting the installation instructions from: <http://www.zlatkovic.com/libxml.en.html>.

#### 3.3.2.2 Installing MiKTeX

Install the minimal distribution, and add the following packages: `changebar`, `colortbl`, `fancybox`, `fancyhdr`, `fancyvrb`, `listings`, `overpics`, `rotating`, `subfigure`, `titlesec`, `bibtopic`, `enumitem`, `eepic`, `lm`, `lastpage`, `helvetic`, `times`, `symbol`, `courier`, `footmisc`, `ifxetex`, `pdfpages`, `wasysym`.

---

### 3.3.2.3 Installing dblatex

From the unpacked package directory just type:

```
python setup.py install
```

If the Python directory is C:\Python25 you can now try **dbl**atex by typing:

```
python C:\Python25\Scripts\dbl
```

atex file.xml

---

## Chapter 4

# Using dblatex

### 4.1 Reference

#### dblatex

dblatex — convert DocBook to LaTeX, DVI, PostScript, and PDF

#### Synopsis

```
dblatex [options] {file|-}
```

#### Description

**dblatex** is a program that transforms your SGML/XML DocBook documents to DVI, PostScript or PDF by translating them into pure LaTeX as a first process. MathML 2.0 markups are supported, too.

#### Options

A summary of options is included below.

**-h, --help**

Show a help message and exit.

**-b backend, --backend=backend**

Backend driver to use: *pdftex* (default), *dvips*, or *xetex*. See also Section 2.5.1.

**-B, --no-batch**

All the tex output is printed.

**-c config, -S config, --config=config**

Configuration file. A configuration file can be used to group all the options and customizations to apply. See Section 5.7.

**-d, --debug**

Debug mode: Keep the temporary directory in which dblatex actually works. Section 5.5.5 explains how you can use it.

**-D, --dump**

Dump the error stack when an error occurs (debug purpose).

**-e indexstyle, --indexstyle indexstyle**

Index style file to pass to **makeindex** instead of the dblatex default index style.

---



- f *figure\_format*, --fig-format=*figure\_format***  
Input figure format: *fig*, *eps*. Used when not deduced from figure file extension. See also Section 4.6.2.
  - F *input\_format*, --input-format=*input\_format***  
Input file format: *sgml*, *xml* (default).
  - i *texinputs*, --texinputs *texinputs***  
Path added to TEXINPUTS
  - I *figure\_path*, --fig-path=*figure\_path***  
Additional lookup path of the figures. See Section 4.6.3.
  - l *bst\_path*, --bst-path=*bst\_path***  
Additional lookup path of the BibTeX styles. See Section 4.12.2.
  - L *bib\_path*, --bib-path=*bib\_path***  
Additional lookup path of the BibTeX databases. See Section 4.12.2.
  - m *xslt*, --xslt=*xslt***  
XSLT engine to use. The available engines are: xsltproc (default), 4xslt, saxon.
  - o *output*, --output=*output***  
Output filename. When not specified, the input filename is used, with the suffix of the output format. The option is ignored if several books are chunked from a set. In this case the -O option is applied instead.
  - O *output\_dir*, --output-dir=*output\_dir***  
Output directory of the books built from a set. When not specified, the current working directory is used instead. The option is ignored if a single document is outputted, and the -o is taken into account.
  - p *xsl\_user*, --xsl-user=*xsl\_user***  
An XSL user stylesheet to use. Several user stylesheets can be specified, but the option order is meaningful: a user stylesheet takes precedence over previously defined user stylesheets. See Section 5.1.
  - P *param=value*, --param=*param=value***  
Set an XSL parameter from command line. See Section 5.2.
  - q, --quiet**  
Less verbose, showing only TeX output messages and error messages.
  - r [*plugin:*] *script*, --texpost=[*plugin:*] *script***  
Script called at the very end of the tex compilation. Its role is to modify the tex file or one of the compilation files before the last round. The *script* can be a python plugin. In this case add the prefix term 'plugin:'. See Section 5.6.
  - s *latex\_style*, --texstyle=*latex\_style***  
Latex style to apply. It can be a package name, or directly a latex package path. A package name must be without a directory path and without the '.sty' extension. On the contrary, a full latex package path can contain a directory path, but must ends with the '.sty' extension. See Section 5.5.
  - t *format*, --type=*format***  
Output format. Available formats: *tex*, *dvi*, *ps*, *pdf* (default).
  - dvi**  
DVI output. Equivalent to -tdvi.
  - pdf**  
PDF output. Equivalent to -tpdf.
  - ps**  
PostScript output. Equivalent to -tps.
  - T *style*, --style=*style***  
Output style, predefined are: *db2latex*, *simple*, *native* (default). See Section 4.2.
-

**-v, --version**

Display the dblatex version.

**-V, --verbose**

Verbose mode, showing the running commands

**-x *xslt\_options*, --xslt-opts=*xslt\_options***

Arguments directly passed to the XSLT engine

**-X, --no-external**

Disable the external text file support. This support is needed for callouts on external files referenced by `textdata` or `imagedata`, but it can be disabled if the document does not contain such callouts. Disabling this support can improve the processing performance for big documents.

**Files and Directories****`$HOME/.dblatex/`**

User configuration directory.

**`/etc/dblatex/`**

System-wide configuration directory.

The predefined output styles are located in the installed package directory.

**Environment Variables****`DBLATEX_CONFIG_FILES`**

Extra configuration directories that may contain some dblatex configuration files.

**Examples**

To produce `myfile.pdf` from `myfile.xml`:

```
dblatex myfile.xml
```

To set some XSL parameters from the command line:

```
dblatex -P latex.babel.language=de myfile.xml
```

To use your XSL stylesheet:

```
dblatex -p myconfig.xsl myfile.xml
```

To use the `db2latex` output style:

```
dblatex -T db2latex myfile.xml
```

To apply your own latex style:

```
dblatex -s mystyle myfile.xml  
dblatex -s /path/to/mystyle.sty myfile.xml
```

To pass extra arguments to the XSLT engine:

```
dblatex -x "--path /path/to/load/entity" myfile.xml
```

To use **dblatex** and profiling:

---

```
xsltproc --param profile.attribute "'output'" \
  --param profile.value "'pdf'" \
  /path/to/profiling/profile.xsl \
  myfile.xml | dblatex -o myfile.pdf -
```

To build a set of books:

```
dblatch -O /path/to/chunk/dir -Pset.book.num=all myfile.xml
```

## 4.2 Output Formatting Style

The output rendering done by **dblatch** can be widely customized like explained in Chapter 5. By default several rendering styles are provided, that one can choose by using the option `-T` (see Example 4.1). The available styles are:

### native

The rendering uses the default LaTeX stylesheets. It is the style used by default if **dblatch** has been configured without using the option `--style`.

### simple

The rendering is very close to original latex rendering. The wrapper around the default latex packages is very thin.

### db2latex

The rendering tries to be as close as possible to the **DB2LaTeX** formatting.

---

#### Example 4.1 Choosing the DB2LaTeX style

---

```
dblatch -T db2latex file.xml
```

---

### 4.2.1 How it works

The rendering style stuff is under the `latex/` directory. You can see the XSL stylesheets under `xsl/` as the way to produce latex with as little as possible docbook specific things (even if a large amount of latex packages are used to do the work). Then, it's up to LaTeX stylesheets to format the document as you wish.

The organization under `latex/` is as follow:

#### contrib

Contains the non-default available LaTeX stylesheets (simple and db2latex).

#### graphics

Default graphics used in the admonitions (e.g. warning). These graphics are used by the default output formatting.

#### scripts

Scripts used to compile with **latex** or **pdflatex**.

#### specs

Contains all the configuration files describing the available styles. A specification file must have the extension `.specs`, `.conf`, or `.xml` to be detected as a style description, and its basename is the name of the style. For example the style **db2latex** is described by the configuration file `db2latex.xml`.

When **dblatch** is executed with no parameter, the usage is displayed. In particular, the list of the available styles is given, like this:

---

```
$ dblatex
dblathex [options] file.{sgml|xml}
Options:
-t {pdf|ps|dvi|tex|xml}: output format
...
-T style                : available latex styles (db2latex, native, simple)
```

The list is built by scanning the specs files found under `specs/`. The spec file syntax is described in Section 5.7.

## style

Default LaTeX stylesheets.

### 4.2.2 Adding a New Formatting Style

To add a new formatting style, do the following steps:

1. Let's create the style directories that will contain all the specific data. We choose to put them under the default **dblathex** user configuration directory.

```
$ mkdir -p $HOME/.dblathex/mystyle/latex
$ mkdir -p $HOME/.dblathex/mystyle/xsl
```

Note that you could choose another configuration directory (see Section 5.7.3 for more details).

2. Create the latex stylesheets you need. It must define the expected DocBook interface and include some core definitions from the default latex stylesheets (cf. Section 5.5). Create also your XSL stylesheet if necessary.
3. Put these files under the appropriate directories:

```
$ mv mytexstyle.sty $HOME/.dblathex/mystyle/latex/.
$ mv param.xsl $HOME/.dblathex/mystyle/xsl/.
```

4. Create a configuration file under the directory `$HOME/.dblathex`. The configuration file must point to the new latex stylesheet, and give the specific parameters. Example:

```
$ cat $HOME/.dblathex/mystyle.conf
<?xml version="1.0" encoding="utf-8"?>
<!-- =====
      Dblathex config file for my new style.
      Note that the directories are relative to mystyle.conf
      ===== -->
<config xmlns="http://dblathex.sourceforge.net/config">
  <latex>
    <texinputs>mystyle/latex//</texinputs>
    <texstyle use="mytexstyle"/>
  </latex>
  <xslt>
    <stylesheet fileref="mystyle/xsl/param.xsl"/>
  </xslt>
  <options>-f fig</options>
</config>
```

5. That's it. Try to compile your document with your style, and check the output.

```
$ dblathex -T mystyle file.xml
```

## 4.3 Publishing Outputs

### 4.3.1 Publishing a single document

The default publishing document units are: `article` and `book`. The output file name is optionnaly specified by the `-o` option.

You can also publish an article or book subset, i.e. you can run `dblatex` on an XML input whose root element is a `chapter`, a `section`, or anything else. In this case, `dblatex` wraps the root element in an `article` or in a `book` and print out a warning. The output subset does not contain any front matter data found in an article or in a book (cover page, revision history, etc.), but it can contain some back matter materials like an index.

```
$ dblatex subset.xml
Build the book set list...
Build the listings...
XSLT stylesheets DocBook - LaTeX 2e (0.2.11)
=====
Warning: the root element is not an article nor a book
Warning: element section(sec-subset) wrapped with article
Build subset.pdf
...
```

### 4.3.2 Publishing a Set of Books

When the document root element is a `set`, and when `set.book.num` is set to 'all', `dblatex` outputs a file per book contained in the set (and in the nested sets). In this case the `-o` option is ignored, and only the `-O` option is taken into account to specify the output directory that will contain the generated files.

Instead of building all the books, the user can publish a single book from the set, by setting the `set.book.num` parameter to the absolute position of the book in the set(s). By default `set.book.num` is set to 1 to publish only the first book.

The output file names are the book identifiers when `use.id.as.filename` is non zero, and when an identifier exists. If one of the two conditions are not met, the filename pattern is "book<position in set>".

Example: given the following set:

```
<?xml version="1.0" encoding="UTF-8"?>

<!-- setfile.xml. An example of set. All the books have an @id except one -->

<!DOCTYPE set PUBLIC "-//OASIS//DTD DocBook XML V4.4//EN"
"http://www.oasis-open.org/docbook/xml/4.4/docbookx.dtd">
<set lang="en" id="a_set" xmlns:xi="http://www.w3.org/2001/XInclude">
<title>Set Title</title>
  <set>
    <xi:include href="book1.xml"/> <!-- book #1 -->
    <xi:include href="book2.xml"/> <!-- book #2 -->
    <xi:include href="book3.xml"/> <!-- book #3 -->
  </set>
  <set>
    <set>
      <xi:include href="bookA.xml"/> <!-- book #4 -->
      <xi:include href="bookB.xml"/> <!-- book #5 -->
    </set>
    <set>
      <xi:include href="bookC.xml"/> <!-- book #6 -->
    </set>
  </set>
  <set>
    <xi:include href="book4.xml"/> <!-- book #7 -->
    <!-- The following book, at 8th position in the sets, has no @id -->
```

```

    <xi:include href="book5.xml"/>    <!-- book #8 -->
    <xi:include href="book6.xml"/>    <!-- book #9 -->
  </set>
</set>

```

Publishing this set produces 9 books in the `pdfdir` directory:

```

$ dblatex -O./pdfdir -Pset.book.num=all -Puse.id.as.filename=1 setfile.xml
Build the book set list...
Build the listings...
XSLT stylesheets DocBook - LaTeX 2e (0.2.11)
=====
Output all the books from the set
Writing sec1-mybook.rtex for book(sec1-mybook)
Writing sec2-mybook.rtex for book(sec2-mybook)
Writing sec3-mybook.rtex for book(sec3-mybook)
Writing secA-mybook.rtex for book(secA-mybook)
Writing book8.rtex for book
Writing secC-mybook.rtex for book(secC-mybook)
Writing sec4-mybook.rtex for book(sec4-mybook)
Writing sec5-mybook.rtex for book(sec5-mybook)
Writing sec6-mybook.rtex for book(sec6-mybook)
...
Files successfully built in '/path/to/set/pdfdir':
sec1-mybook.pdf
sec2-mybook.pdf
sec3-mybook.pdf
sec4-mybook.pdf
book8.pdf
sec6-mybook.pdf
secA-mybook.pdf
secB-mybook.pdf
secC-mybook.pdf

```

## 4.4 Global Page Setup

Since version 0.3.3 the user can specify to **dblatex** the global page layout to apply, through some XSL parameters (see Section A.18). It is also possible to produce pre-press layouts with physical pages having some crops (see Section A.21).

Figure 4.1 shows the meaning of each parameter length. Of course the example is a page with crops, only to be able to display the crop lengths with the other lengths.




Figure 4.1: Parameter Lengths used for Page Setup

**Warning**

The native dlatex style still contains some hard-coded lengths to format the `revhistory` table. You should then disable the revision history display.

## 4.5 Chapter and Section numbering

### 4.5.1 Depth of Section numbering and Table Of Content

**Dblatex** relies on latex to automatically compute the chapter and section numbers. It also relies on latex to produce the headings with these numbers, and to produce the Table Of Content containing these entries.

Some specific sections like `preface`, `colophon`, or `dedication` are not numbered because they are displayed in front and back matters, but they can be listed in the TOC if the related parameters are set (`dedication.tocdepth`, `preface.tocdepth`, `colophon.tocdepth`).

More generally you can configure the depth of the chapter and section numbering with the parameter `doc.section.depth`, and the depth of the entries in the TOC with the parameter `toc.section.depth`.

Note however that an unnumbered section becomes an informal component, and therefore you can only link to such a section by using a specific xrefstyle because their label built with the automatic number does not exist anymore. The other drawback is that all the sections included in an unnumbered section or chapter are unnumbered.

## 4.5.2 Using the latex style for section numbering

A well customized latex style can be a powerful yet versatile alternative to the use of section and/or TOC depth parameter. With some latex packages you can easily format the headings to remove the numbers, or transform them. See Section 5.5 to know how to use your own latex style with **dbl**atex.

The benefit of this method is that you can fully control how the titles must be displayed, you do not have to play with latex counters to have the right depth, and the sections do not lost their formal number label.

The following example shows how you can customize the chapter title by using the latex package `titlesec`, and shows how to remove the chapter label in the Table Of Content with the package `titletoc`. Look in particular in the listing where text is emphasized.

```
\usepackage{titlesec}

%% Example 1: Redefines the heading to remove the chapter label
%% The 2nd parameter only contains \filcenter without any label
\titleformat{\chapter}[block]
{\filcenter\huge}{\bfseries}{20pt}{\Huge}

%% Example 2: Put the chapter number in word
%% The title of the first chapter is then displayed like this:
%% "Chapter One <chapter title>"
\newcommand\makeletterof[1]{%
\ifthenelse{\equal{#1}{1}}{ONE}{%
\ifthenelse{\equal{#1}{2}}{TWO}{%
\ifthenelse{\equal{#1}{3}}{THREE}{%
\ifthenelse{\equal{#1}{4}}{FOUR}{%
\ifthenelse{\equal{#1}{5}}{FIVE}{%
\ifthenelse{\equal{#1}{6}}{SIX}{%
\ifthenelse{\equal{#1}{7}}{SEVEN}{%
\ifthenelse{\equal{#1}{8}}{EIGHT}{%
\ifthenelse{\equal{#1}{9}}{NINE}{%
\ifthenelse{\equal{#1}{10}}{TEN}{%
\ifthenelse{\equal{#1}{11}}{ELEVEN}{%
\ifthenelse{\equal{#1}{12}}{TWELVE}{%
#1}}}}}}}}}}}}}}

\titleformat{\chapter}[block]
{\filcenter\ttfamily\huge}%
{\bfseries\MakeUppercase{\chaptertitlename} \makeletterof{\thechapter}}{20pt}{\Huge}

%% Make TOC entries for chapters without label
\usepackage{titletoc}

\titlecontents{chapter} %
[1.5em] %
{\addvspace{1em plus 0pt}\bfseries} %
{\hspace{-1.3em}} % no number, remove room reserved for it
{\hspace{-1.3em}} %
```



```
{\hfill \contentspage} %
[\addvspace {0pt}]
```

### 4.5.3 Using the label attribute

If you need to mix numbered and not numbered chapters, the numbering depth parameters will not help. The latex style will not easily detect that for some chapters the number should be displayed and for others it should not.

To mix numbered and unnumbered chapters you can use a label with an empty string for the chapters that must not be numbered, as shown by the example below.

```
<chapter id="intro" label=""><title>Introduction</title>
  <!-- This chapter must be displayed with no number, like a preface -->
</chapter>
<chapter id="before" label=""><title>Pre-requisite</title>
  <!-- This chapter must be displayed with no number, like a preface -->
</chapter>
<chapter id="chap1"><title>First chapter</title>
  <!-- First numbered chapter -->
</chapter>
...
<chapter id="after" label=""><title>Conclusion</title>
  <!-- This chapter must be displayed with no number, like a colophon -->
</chapter>
...
```

You can also set a label to a specific integer to force a section counter. In this case there is no more automatic numbering. The automatic numbering then applies to the following sections that increment the counter set for this section if there is no label.

```
<chapter id="intro" label="2"><title>Introduction</title>
  <!-- This chapter is forced to have number 2 (it should be 1) -->
  <section id="s1" label="3"><title>Section 2.3</title>
    <!-- This section is forced to have number 3 (it should be 1) -->
    <section id="s11" label="4"><title>Section 2.3.4</title>
      <!-- This section is forced to have number 4 (it should be 1) -->
    </section>
  </section>
</chapter>
```

## 4.6 Figure Inclusion

### 4.6.1 Presentation

The expected format of the included figures depends on the backend driver used:

**dvips:**

EPS format is required.

**pdftex:**

PDF or PNG format is required.

In order to be able to use both backends, it is wise to not write the suffix of the file that references the figure. The suffix will be deduced from the backend used.

The figures must either already exist in the expected format, or must be able to be converted on the fly.

**Example 4.2** Figure inclusion

```
<figure id="fig-exemple1">
  <title>Components</title>
  <mediaobject>
    <imageobject>
      <imagedata fileref="path/figure1" align="center" scale="70">
    </imageobject>
  </mediaobject>
</figure>
```

**4.6.2 Converting on the fly**

When it is needed dblatex tries to automatically convert the figures to the expected format (i.e. EPS or PDF). The principle is to detect the original figure format from the suffix of the fileref attribute. If no suffix is given, the tool checks if a file whose basename is conformant with the fileref attribute and with one of the predefined suffixes exists (that is, ".eps", ".fig", ".pdf", or ".png"). If such a file exists, conversion is done from the original format found.

The option `-f fig_format` allows to specify the default included figures format (*fig\_format*), that will be used when automatic format scanning gives no result. Then, the tool converts the figures from the specified format to the expected one.

If the specified format is unknown, no conversion is done. The supported formats are:

**fig:**

native format of the figures produced by XFig.

**eps:**

Encapsulated PostScript format. This format shall be specified only when using the pdftex backend.

**Example 4.3** Figure conversion

The following command compiles a document that contains figures produced with XFig.

```
% dblatex -f fig mydoc.sgml
```

**4.6.3 Paths Lookup**

You can use and cumulate the option `-I path` to specify where the figures are. The given paths can be absolute or relative. The paths are added to the document root path.

**Example 4.4** Figures lookup

This example shows how figure lookup is done. Let's consider this document source:

```
<figure id="fig-example1">
  <title>Composants</title>
  <mediaobject>
    <imageobject>
      <imagedata fileref="rep1/rep2/figure1" align="center" scale="70">
    </imageobject>
  </mediaobject>
</figure>
```

And the document is compiled like this:

```
% dblatex -I /another/path -I /last/case /initial/path/document.sgml
```

The figure1 lookup is done in the following directories, in respect of the order:

- `/initial/path/rep1/rep2` ;
  - `/another/path/rep1/rep2` ;
  - `/last/case/rep1/rep2`.
- 

## 4.7 Creating Tables

DocBook tables can be quite complex, but **dblatex** should be able to drive most of cases thanks to the excellent `newtbl` implementation by David Hedley completely written in XSL.

Here is what is supported:

- Columns without specified widths (`colspec` without `colwidth` attribute) have the same size.
- A table width is always equal to the page width, if at least one column doesn't contain a fixed width attribute (e.g. `colwidth="12cm"`).
- Fixed column widths are supported (e.g. `colwidth="10cm"`). The unit can be whatever is understood by latex (e.g. `cm`, `em`, `in`, `pt`).
- Proportional column widths are supported (e.g. `colwidth="5*"`). Combination of fixed and proportional width is supported too (e.g. `colwidth="5*+10cm"`).
- The `morerows` attribute of a table entry (`entry` element) is supported.
- The `namest` and `nameend` attributes of a table entry (`entry` element) are supported. It is possible to have a cell spanned on several columns.
- The `orient` table attribute is supported (portrait and landscape).
- It is possible to have missing cell entries in a table.

### 4.7.1 Limitations

Currently the following things are known to fail with tables:

- Program listings and screens cannot be embedded in tables. Some other verbatim environments like `litterallayout` are allowed.
- Footnotes in table cells can fail, especially if the footnote contains several paragraphs. Moreover they are lost if a float like a table.

### 4.7.2 Table Width

A table width is explicit when all the columns have a fixed size. In this case it is the sum of the column widths. In the other cases (columns with no `colwidth` or proportional columns widths) the total table width is deduced by `dblatex` as follow: it looks for the Processing Instruction `<?dblatex table-width="width" ?>` first, then the `@width` attribute, the `default.table.width` parameter, and finally use the page width.

A table width can be expressed as:

- A valid length (e.g. `15cm`),
- A percentage of the page width (e.g. `75%`),
- A keyword telling to apply an automatic column width (e.g. `autowidth.all`).

The automatic column width setup is detailed in Section [4.7.7](#).

---

### 4.7.3 Tables without colwidth

When none of the `colspec` elements contains the `colwidth` attribute, all the columns have the same size, and the table width is fixed to the maximum available size. Several examples of these tables are given.

| Column 1                                     |
|--|
| left aligned                                 |
| no specified width, so it takes all the page |

| Column 1           | Column 2      |
|--------------------|---------------|
| left aligned       | centered cell |
| no specified width | idem          |

| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

### 4.7.4 Tables with mixed colspec

A table can have `colspec` elements containing `colwidth` attribute mixed with `colspec` elements without `colwidth`. Here is an XML source example:

```
<informaltable>
  <tgroup cols="5" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/>
    <colspec align="left" colwidth="4cm"/>
    <colspec align="right" colwidth="5cm"/>
    <colspec align="center"/>
    <colspec align="center" colwidth="3cm"/>
    <tbody>
      ...
    </tbody>
  </tgroup>
</informaltable>
```

It is rendered like this:

| Column 1                          | Column 2          | Column 3          | Column 4         | Column 5          |
|-----------------------------------|-------------------|-------------------|------------------|-------------------|
| left aligned<br>(tgroup<br>order) | left aligned      | right aligned     | centered<br>cell | in the centre     |
| no specified<br>width             | 4 cm column width | 5 cm column width | no width         | 3 cm column width |

### 4.7.5 Tables with proportional and fixed colwidth

Proportional column widths are supported. Here is an example:

```
<informaltable>
  <tgroup cols="5" colsep="1" rowsep="1" align="left">
    <colspec colname="c1" colwidth="*"/>
    <colspec align="left" colwidth="2*"/>
    <colspec align="right" colwidth="3*"/>
    <colspec align="center"/>
    <colspec align="center" colwidth="3cm"/>
  </tgroup>
</informaltable>
```

```

<tbody>
...
</tbody>
</tgroup>
</informaltable>

```

It gives this table:

| Column 1                       | Column 2                 | Column 3                 | Column 4           | Column 5          |
|--------------------------------|--------------------------|--------------------------|--------------------|-------------------|
| left aligned<br>(tgroup level) | left aligned             | right aligned            | centered cell      | in the centre     |
| proportional column (*)        | proportional column (2*) | proportional column (3*) | no specified width | 3 cm column width |

#### 4.7.6 Tables with fixed colwidths

All the columns can have fixed size, like this:

```

<informaltable>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1" colwidth="2cm"/>
    <colspec align="left" colwidth="2.5cm"/>
    <colspec align="right" colwidth="5cm"/>
    <colspec align="center" colwidth="3cm"/>
    <tbody>
      ...
    </tbody>
  </tgroup>
</informaltable>

```

It gives the following table:

| Column 1                       | Column 2            | Column 3          | Column 4          |
|--------------------------------|---------------------|-------------------|-------------------|
| left aligned<br>(tgroup level) | left aligned        | right aligned     | centered cell     |
| 2 cm column width              | 2,5 cm column width | 5 cm column width | 4 cm column width |

#### 4.7.7 Automatic Column Width

##### 4.7.7.1 Global Setting

In the previous sections the columns widths are computed from a proportional basis, when no `colwidth` is specified or when the `colwidths` contain a star ("\*"). Of course, a `colwidth` containing a fixed width incidently sets the column width with this size.

It is possible to change this sizing policy of not-fixed-width columns by playing with the `newtbl.autowidth` parameter. The parameter can take the following values:

##### default

The automatic width (that is, latex is in charge to size the column width) is applied only to columns not having a specified `colspec` `colwidth`. It includes both undefined `colspec`, and `colspec` without the `colwidth` attribute.

##### all

the automatic width is applied to any column, whether a `colspec` is provided or not.

By default the parameter is unset, and no automatic width is applied. Using automatic width is handy in some situations but there is no more control if the tables fit in the page or not, since in this case the column is as wide as its content, with no more paragraph breaking. The parameter is global for all the tables in the document.

You can also perform the same thing by setting the `default.table.width` parameter to `autowidth.default` or `autowidth.all` instead of using `newtbl.autowidth`.

#### 4.7.7.2 Local Setting

If you want to apply an automatic width only to some specific tables you can put the Processing Instruction `<?dblatex table-width="autowidth.scope" ?>` in the related tables. The PI has precedence over the `newtbl.autowidth` parameter.

The `scope` can take the same values and have the same effects than for the `newtbl.autowidth` parameter (default or all).

In addition to these keywords, `table.width` can also take for its value keywords of the form `autowidth.column:N ...`, where `N` is the number of the column (counting from 1) which is to have its width automatically sized.

See the following example:

```
<informaltable><?dblatex table-width="autowidth.column: 1 3"?>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/>                                <!-- automatic width is applied to column #1 -->
    <colspec align="left" colwidth="*/>
    <colspec align="right" colwidth="5cm"/> <!-- automatic width is applied to column #3 -->
    <colspec align="center" colwidth="3cm"/>
    ...
  </informaltable>
```

Here are two other examples with the all and default scopes:

The following table has columns 1 and 2 sized by latex with `autowidth.all`:

| Column 1        | Column 2                | Column 3                                      | Column 4                       |
|-----------------|-------------------------|---|--------------------------------|
| cell on 4 lines | simple cell             | cell on 2 lines                               | cell without morerow attribute |
|                 | cell in column 2        |   | cell on 2 lines                |
|                 | left aligned on 2 lines | cell in line 3, column 3<br>4 cm column width | last cell in column 4          |

It is written as follow:

```
<informaltable><?dblatex table-width="autowidth.all"?>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/> <!-- 'default' and 'all' apply on this column -->
    <colspec align="left" colwidth="*/> <!-- only 'all' applies on this column -->
    <colspec align="right" colwidth="5cm"/>
    <colspec align="center" colwidth="3cm"/>
    ...
  </informaltable>
```

The following table has only columns 1 sized by latex with `autowidth.default`:

| Column 1        | Column 2                | Column 3                                      | Column 4                       |
|-----------------|-------------------------|---|--------------------------------|
| cell on 4 lines | simple cell             | cell on 2 lines                               | cell without morerow attribute |
|                 | cell in column 2        |   | cell on 2 lines                |
|                 | left aligned on 2 lines | cell in line 3, column 3<br>4 cm column width | last cell in column 4          |

The only difference is that the PI attribute value is `autowidth.default`:

```
<informaltable><?dblatex table-width="autowidth.default"?>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/> <!-- 'default' and 'all' apply on this column -->
    <colspec align="left" colwidth="*/> <!-- only 'all' applies on this column -->
    <colspec align="right" colwidth="5cm"/>
    <colspec align="center" colwidth="3cm"/>
    ...
  </tgroup>
</informaltable>
```

#### 4.7.8 Informal Table LaTeX Styles

By default **dblatex** translates an informal table to the LaTeX environment specified by the `table.default.tabstyle` parameter (usually `longtable`), but you can specify which LaTeX tabular environment to use, globally through the parameter, or per table through the `tabstyle` attribute. Of course the `tabstyle` attribute value is specific to `dblatex`. The supported values are:

##### **longtable**

The default table type used by `dblatex` when `table.default.tabstyle` is empty, in order to be able to split over several pages.

##### **tabular**

The most usual table type. Such table can only be on a single page.

##### **tabularx**

An advanced table type that allows to stretch column widths to the available remained page width. Such table can only be on a single page like for "tabular".

The two following examples show how `tabular` and `tabularx` rendering differ when the automatic width feature is used. Here is the XML source code:

```
<informaltable tabstyle="tabular">
  <?dblatex table-width="autowidth.column: 1 3"?>
  <tgroup cols="5" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/>
    <colspec align="left"/>
    <colspec align="right"/>
    <colspec align="center"/>
    ...
  </tgroup>
</informaltable>

<informaltable tabstyle="tabularx">
  <?dblatex table-width="autowidth.column: 1 3"?>
  <tgroup cols="5" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/>
    <colspec align="left"/>
    <colspec align="right"/>
    <colspec align="center"/>
    ...
  </tgroup>
</informaltable>
```

It is rendered as follow:

| C1 | Column 2     | Column 3      | Column 4      | Column 5 |
|----|--------------|---------------|---------------|----------|
| A  | left aligned | right aligned | centered cell | centered |
| B  | idem         | idem          | idem          | idem     |

| C1 | Column 2     | Column 3      | Column 4      | Column 5 |
|----|--------------|---------------|---------------|----------|
| A  | left aligned | right aligned | centered cell | centered |
| B  | idem         | idem          | idem          | idem     |

4.7.9 Tables with morerows

A table can contain entries that cover several lines. The following XML source contains an entry covering 4 lines:

```
<informaltable>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1" colwidth="*"/>
    ...
    <tbody>
      <entry morerows="3">it covers 4 lines</entry>
      ...
    </tbody>
  </tgroup>
</informaltable>
```

Here is an example of table containing several entries with morerows attribute:

| Column 1        | Column 2                | Column 3                 | Column 4                       |
|-----------------|-------------------------|--------------------------|--------------------------------|
| cell on 4 lines | simple cell             | cell on 2 lines          | cell without morerow attribute |
|                 | cell in column 2        |                          | cell on 2 lines                |
|                 | left aligned on 2 lines | cell in line 3, column 3 |                                |
|                 |                         | 4 cm column width        | last cell in column 4          |

4.7.10 Landscape tables

A table can be displayed in a lanscape format by using the orient attribute. Here is an XML source example:

```
<informaltable orient="land">
  <tgroup cols="5" colsep="1" rowsep="1" align="left">
    <colspec colname="c1" colwidth="*"/>
    ...
    <tbody>
      ...
    </tbody>
  </tgroup>
</informaltable>
```

Here is how it is displayed.



| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

### 4.7.11 Smaller tables

For big tables it can be usefull to have smaller text, so that the table is not too large or too long and it can be displayed within a page. It is possible to specify smaller table text by using the `role` attribute of the elements `table` or `informaltable`.

The values and the “role” dedicated to this attribute are specific to `dblatex`, but it is compliant with the DocBook specification because in general the `role` attribute purpose is never defined.

The available text size definitions supported by `role` are directly taken from LaTeX:

- `small`,
- `footnotesize`,
- `scriptsize`,
- `tiny`.

Here are examples for each size.

| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

| Column 1           | Column 2     | Column 3      | Column 4      | Column 5 |
|--------------------|--------------|---------------|---------------|----------|
| left aligned       | left aligned | right aligned | centered cell | centered |
| no specified width | idem         | idem          | idem          | idem     |

### 4.7.12 Coloured tables

You can color all the table by setting its `bicolor` attribute.

You can also color only some cells by using the Processing Instruction `<?dblatex bgcolor="color">`. The PI can apply to columns when put in a `colspec`, to rows when put at the beginning of a row, or to cells when put in a entry.

The entry colour has precedence over the row colour, that has precedence over the column colour, that has precedence over the table colour.

The color can be expressed in hexadecimal notation like for HTML (e.g. `#C0C0C0`) or in a syntax understood by the `colortbl` latex package.

Here is an example.

| Column 1 | Column 2     | Column 3 | Column 4 |
|----------|--------------|----------|----------|
| yellow   | green column | yellow   | yellow   |
| blue row | red cell     | blue row | blue row |
| yellow   | green column | yellow   | gray     |

This table is coded like this:

```
<informaltable id="tbl-color" bgcolor="{yellow}">
<tgroup cols="4" colsep="1" rowsep="1" align="left">
```

```

<colspec colname="c1" colwidth="2cm"/>
<colspec align="left" colwidth="2.5cm"><?dblatex bgcolor="#00FF00"?></colspec>
<colspec align="right" colwidth="5cm"/>
<colspec align="center" colwidth="3cm"/>
<thead>
  <row>
    <entry>Column 1</entry><entry>Column 2</entry>
    <entry>Column 3</entry><entry>Column 4</entry>
  </row>
</thead>
<tbody>
<row>
  <entry>yellow</entry><entry>green column</entry>
  <entry>yellow</entry><entry>yellow</entry>
</row>
<row>
<?dblatex bgcolor="{blue}"?>
  <entry>blue row</entry>
  <entry><?dblatex bgcolor="{red}"?>red cell</entry>
  <entry>blue row</entry><entry>blue row</entry>
</row>
<row>
  <entry>yellow</entry><entry>green column</entry>
  <entry>yellow</entry>
  <entry><?dblatex bgcolor="[gray]{0.8}"?>gray</entry>
</row>
</tbody>
</tgroup>
</informaltable>

```

### 4.7.13 HTML Tables

Since version 0.3.2 dblatex supports HTML tables. Some features are handled differently from CALS tables as illustrated by the following HTML table source example:

```

<table border="1" width="100%" rules="all"❶>
  <caption>An HTML Table</caption>❷
  <colgroup span="2" valign="top" align="right"/>
    <?dblatex bgcolor="red"?>❸
  </colgroup>
  <colgroup valign="bottom" align="left" width="5%"❹>
    <col align="right" span="2"/>
    <col valign="top"/>
  </colgroup>
  <colgroup bgcolor="yellow" width="0*"❺><?dblatex bgcolor="yellow"?></colgroup>
  <colgroup valign="bottom" align="left" width="15%"/>
  <colgroup valign="bottom" align="left" width="10%"/>
  <thead>
    <tr> <td width="10%">Head A1</td><td>Head B1</td><td>Head C1</td> </tr>
  </thead>
  <tfoot>
    <tr> <td width="10%">Foot A1</td><td>Foot B1</td><td>Foot C1</td> </tr>
  </tfoot>

  <tr>
    <td width="10%">A1</td><td>B1</td><td>C1</td>
  </tr>
  <tr>
    <td>A2</td><td bgcolor="yellow">B2</td><td colspan="3" rowspan="3">C-E2</td><td>F2</td>
  </tr>

```

```

<tr>
  <td>A3</td><td width="25.3"❹>B3</td><td>F3</td><td rowspan="2">G3</td><td rowspan="3"> ←
    H3</td>
</tr>
<tr>
  <td>A4</td><td>B4</td><td>F4</td><td>G4</td>
</tr>
<tr>
  <td>A5</td><td>B5</td><td width="5%">C5</td><td>D5</td>
</tr>
<tr bgcolor="blue"❷>
  <td>A6</td><td>B6</td><td>C6</td><td>D6</td><td>E6</td><td bgcolor="green"❸>F6</td>
</tr>
</table>

```

- ❶ The cell borders are specified through the `table rules` attribute, and not by any `rowsep` and `colsep` attributes. Therefore it is not possible to set the borders of an individual cell. If no `rules` attribute is provided the default setup defined by `default.table.rules` parameter is used.
- ❷ The title of a formal HTML table is set through the `caption` element, because the `title` element is not available.
- ❸ The cell background colors can be set directly with the `bgcolor` attribute in `row` (for an entire row color setting), `th`, or `td`, but the `dblatex bgcolor` Processing Instruction is required in `colgroup` or `col` to set a column color.
- ❹ The relative widths can be expressed as a percentage. The proportional syntax (e.g. "3\*") is still available in `colgroups`.
- ❺ To specify that a column must be as wide as its content, there is no need to use the `dblatex autowidth` Processing Instruction. You just need to set the related `colgroup width` attribute to "0\*".
- ❻ The fixed widths must be expressed as numbers, and the implicit unit is the point ("pt"). You cannot set a width expressed in a unit like inches ("in"), centimeters ("cm") and so on.
- ❼ The closest enclosing element attribute has precedence over ancestor attributes. This applies to background color too.

This source example is rendered as follow:

| Head A1 | Head B1 | Head C1 |    |    |    |    |    |    |
|---------|---------|---------|----|----|----|----|----|----|
| A1      | B1      | C1      |    |    |    |    |    |    |
| A2      | B2      |         |    |    | F2 |    |    |    |
| A3      | B3      |         |    |    | F3 |    |    |    |
| A4      | B4      | C-E2    |    |    | F4 | G3 |    | G4 |
| A5      | B5      | C5      | D5 |    |    |    | H3 |    |
| A6      | B6      | C6      | D6 | E6 | F6 |    |    |    |
| Foot A1 | Foot B1 | Foot C1 |    |    |    |    |    |    |

Table 4.1: An HTML Table

## 4.8 Writing Mathematics

### 4.8.1 Writing LaTeX Mathematical Equations

#### 4.8.1.1 Presentation

DocBook doesn't define elements for writing mathematical equations. Only few elements exist that tell how equation should be displayed (inlined, block):

- `inlineequation` tells that the equation is inlined,
- `informalequation` tells that the equation is displayed as a block, without a title.
- `equation` tells that the equation is displayed as a block, with or without a title.

These tags include a `graphic` (or `mediaobject`) or an alternative text equation, as shown by the example.

---

#### Example 4.5 Equation taken from TDG

---

```
<equation><title>Last Theorem of Fermat</title>
  <alt>x^n + y^n &ne; z^n &forall; n &ne; 2</alt>
  <graphic fileref="figures/fermat"></graphic>
</equation>
```

---

#### 4.8.1.2 Implementation choice

The principle is to use only the `alt` element. If initially `alt` contains actually the text to print, it is chosen to use this element to embed LaTeX mathematical equations. This choice has the following advantages:

- The translation done by `dblatex` is really easy, since the equation is already written in LaTeX.
- LaTeX is one of the best word processor to render mathematical formulas.
- One doesn't need to write the equations in MathML.
- This method isn't specific to this tool (see the following section).

#### 4.8.1.3 Mathematical Delimiters

The `dblatex` implementation is as light as possible. This is why it is up to the writer to properly use the mathematical delimiters (`$`, `\(`, `\)`, `\[`, `\]`). By this way the writer fully controls how he writes equations.

By default **dblatex** checks that consistent mathematical delimiters or environment are used in `alt` and it inserts the default math mode delimiters if `dblatex` thinks they are missing, but you can ask `dblatex` to write directly the `alt` content without any action. To do this, use the `texmath` Processing Instruction with `delimiters` set to 'user'.

For example, Example 4.6 has user specific delimiters:

**Example 4.6** Equation with user delimiters

$$S = \left\lfloor \frac{N \bmod 65536}{32768} \right\rfloor$$

$$E = \left\lfloor \frac{N \bmod 32768}{1024} \right\rfloor$$

$$M = N \bmod 1024.$$

EQUATION 4.1: Equation block with align tabs

In the XML source this equation uses a specific `align*` environment and the `texmath` PI to let the equation as is:

```
<?xml version="1.0" encoding="iso-8859-1"?>
<!DOCTYPE para PUBLIC "-//OASIS//DTD DocBook XML V4.4//EN"
"http://www.oasis-open.org/docbook/xml/4.4/docbookx.dtd">
<equation>
  <title>Equation block with align tabs</title>
  <alt><?texmath delimiters="user"?><![CDATA[\begin{align*}
S &= \left\lfloor \frac{N \bmod 65536}{32768} \right\rfloor \\
E &= \left\lfloor \frac{N \bmod 32768}{1024} \right\rfloor \\
M &= N \bmod 1024. \\
\end{align*}]]></alt>
</equation>
```

**4.8.1.4 Compatibility**

This implementation is not contradictory nor specific. In particular, the **DBTeXMath** proposal to extend the DSSSL stylesheets used by jade follows the same approach, and is integrated in the Norman Walsh XSL stylesheets.

**4.8.1.5 Examples**

The following examples show how to write the equations.

**Example 4.7** Inlined Equation

The formula  $C = \alpha + \beta Y^\gamma + \varepsilon$  is inlined in the paragraph. Its XML source is:

```
<para>The formula
  <inlineequation id="eg-inlineequation">
    <alt>$C = \alpha + \beta Y^{\gamma} + \epsilon$</alt>
    <graphic fileref="figures/eq1"/>
  </inlineequation>
  is inlined in the paragraph. Its XML source is:</para>
```

**Example 4.8** Equation in a block

The following formula:

$$C = \alpha + \beta Y^\gamma + \varepsilon$$

is displayed in a separate block. The XML source is:

```
<para>The following formula:
  <informalequation>
    <alt>\[C = \alpha + \beta Y^{\gamma} + \epsilon\]</alt>
    <graphic fileref="figures/eq1"/>
  </informalequation>
is displayed in a separate block. The XML source is:</para>
```

---

**Example 4.9** Equation in a float

The formula Equation 4.2 below:

$$C = \alpha + \beta Y^{\gamma} + \epsilon$$

EQUATION 4.2: Simple Formula

is displayed in a block with a title. Its XML source is:

```
<?xml version="1.0" encoding="iso-8859-1"?>
<!DOCTYPE para PUBLIC "-//OASIS//DTD DocBook XML V4.4//EN"
"http://www.oasis-open.org/docbook/xml/4.4/docbookx.dtd">
<para>The formula <xref linkend="eq-with-title"/> below:
  <equation id="eq-with-title">
    <title>Simple Formula</title>
    <alt>\[C = \alpha + \beta Y^{\gamma} + \epsilon\]</alt>
    <graphic fileref="figures/eq1"/>
  </equation>
is displayed in a block with a title. Its XML source is:</para>
```

---

**Example 4.10** Equation without a title

The formula 4.1 below:

$$C = \alpha + \beta Y^{\gamma} + \epsilon \tag{4.1}$$

is displayed as a latex equation with its own equation numbering. Its XML source is:

```
<?xml version="1.0" encoding="iso-8859-1"?>
<!DOCTYPE para PUBLIC "-//OASIS//DTD DocBook XML V4.4//EN"
"http://www.oasis-open.org/docbook/xml/4.4/docbookx.dtd">
<para>The formula <xref linkend="eq-with-no-title"/> below:
  <equation id="eq-with-no-title">
    <alt>C = \alpha + \beta Y^{\gamma} + \epsilon</alt>
    <graphic fileref="figures/eq4"/>
  </equation>
is displayed as a latex equation with its own equation numbering.
Its XML source is:</para>
```

## 4.8.2 Writing MathML equations

You can write MathML equations in a DocBook based document, by using the [MathML Module for DocBook XML](#) instead of the DocBook DTD.

---

dblatex now translates the MathML equations to latex by using the excellent stylesheets of the [XSLT MathML Library](#) by Vasil Yaroshevich. A large amount of tests from the [W3C MathML Test Suite 2.0](#) is supported (657 of 712 tests). The test file used to validate the MathML stylesheets is provided in the package.

## 4.9 Musical Notation

Dblatex does not itself present musical notation. Of course, images of musical scores can be incorporated into dblatex output as can any other sort of images. For a more comprehensive solution which better integrates the typesetting of text with musical notation the LilyPond project (<http://www.lilypond.org/>) provides a facility for including musical notation within DocBook documents. LilyPond provides a program, **lilypond-book**, that pre-processes DocBook documents containing LilyPond musical notation and which can automatically invoke **dblatex** to produce PDFs integrating musical notation with text.

Information regards **lilypond-book** is, at present, found in LilyPond's "Usage" manual, the "Running lilypond-book" chapter, the "Integrating music and text" section.

## 4.10 Extending the Verbatim Rendering

### 4.10.1 Dblatex Specific Options

There are few attributes or options specific to **dblatex** to render verbatim blocks:

- The `role` attribute of `screen`, `programlisting`, and `literallayout` can take the following special values:

#### **wrap**

The verbatim lines can break and wrap when they are longer than the available width. It is the default behaviour.

#### **overflow**

The verbatim lines never break and go into the margin when they are too long.

#### **scale**

The verbatim block is automatically scaled so that the longest line or specified column count fits in the available page width. See Section [4.10.2](#).

- The parameter `literal.role` can be used to set the default role to apply. By default the value is an empty string.
- The parameter `literal.class` can be used to set the default `literallayout` class when no class attribute is given. By default the value is `monospaced`.

### 4.10.2 Scaling Feature

The user can scale the verbatim block so that the longest line fits in the available page width, or so that the page contains at least a specified width expressed in columns.

The scaling feature is enabled when the parameter `literal.extensions` is set as follow:

#### **scale**

The scaling is performed only when the `role` attribute is set to "scale", or when the `role` attribute is not set and the parameter `literal.role` is set to "scale".

#### **scale.by.width**

The scaling is performed when the `role` attribute or `literal.role` is properly set, or when the attribute `width` is set. When `width` is set the block is scaled so that the specified width fits in the page width.

Here are some listing examples with several attribute combinations producing or not the scaling. In these examples the parameter `literal.extensions` is set to "scale.by.width".



```
<programlisting width="110">  
The listing is scaled and lines are wrapped after 110 characters. Check yourself:  
  
123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789  
    9 123456789  
0          1          2          3          4          5          6          7          8          9          10 ←  
        11  
  
</programlisting>
```

```
<programlisting width="110" role="overflow">
There is no scaling because the role has precedence over the width attribute:

123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789
0          1          2          3          4          5          6          7          8          9
11

</programlisting>
```

```
<programlisting role="scale">
The listing is scaled to display the longest line with no break:

123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 1234567 9 123456789
0          1          2          3          4          5          6          7          8          9          10         11

</programlisting>
```

```
<programlisting width="110" role="scale">
The listing is scaled to fit up to 110 columns, and the lines are wrapped. In this case role is redundant ←
  because @width automatically produces scaling.

123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 123456789 ←
   9 123456789
0      1      2      3      4      5      6      7      8      9      10 ←
      11

</programlisting>
```

### 4.10.3 Formatting embedded elements

The programlisting and screen environments are supported by dblatex, but the implementation is rather conservative, that is, most of the elements embedded in such environments are not rendered like in normal environment (e.g. bold, emphasis, etc.). Only the contained text is printed out. For the elements whose rendering is lost, **dbl**atex prints out a warning message.

For example, let's compile the following programlisting fragment:

```
<programlisting>
zone <replaceable>zone_name</replaceable>
<optional><replaceable>class</replaceable></optional> {
    type delegation-only;
};
</programlisting>
```

**dblatex** warns that the `optional` and `replaceable` elements are not supported (i.e. not rendered) in the programlisting:

```
$ dblatex progfrag.xml
Build the book set list...
Build the listings...
XSLT stylesheets DocBook - LaTeX 2e (devel)
=====
Warning: the root element is not an article nor a book
Warning: programlisting wrapped with article
replaceable not supported in programlisting or screen
optional not supported in programlisting or screen
replaceable not supported in programlisting or screen
```

```
replaceable not supported in programlisting or screen
optional not supported in programlisting or screen
replaceable not supported in programlisting or screen
...
```

If you want those elements be formatted in bold, or italic you need to override the templates used in `latex.programlisting` mode, as follow:

```
<xsl:template match="replaceable|optional" mode="latex.programlisting">
  <xsl:param name="co-tagin" select="'&lt;:'" /> ❶
  <xsl:param name="rnode" select="/" />          ❷
  <xsl:param name="probe" select="0" />           ❸

  <xsl:call-template name="verbatim.boldseq"> ❹
    <xsl:with-param name="co-tagin" select="$co-tagin" />
    <xsl:with-param name="rnode" select="$rnode" />
    <xsl:with-param name="probe" select="$probe" />
  </xsl:call-template>
</xsl:template>
```

❶, ❷, ❸ These parameters are required in `latex.programlisting` mode.

❹ The predefined template makes bold the verbatim text of the element.

If formatting setup is not enough, you can also render these elements as if they were in a normal environment. To do this, you need to override the templates used in `latex.programlisting` mode, as follow:

```
<xsl:template match="replaceable|optional" mode="latex.programlisting">
  <xsl:param name="co-tagin" select="'&lt;:'" />
  <xsl:param name="rnode" select="/" />
  <xsl:param name="probe" select="0" />

  <xsl:call-template name="verbatim.embed"> ❶
    <xsl:with-param name="co-tagin" select="$co-tagin" />
    <xsl:with-param name="rnode" select="$rnode" />
    <xsl:with-param name="probe" select="$probe" />
  </xsl:call-template>
</xsl:template>
```

❶ To enable the normal mode rendering within a verbatim environment, call the `verbatim.embed` template, and pass the mandatory parameters.

#### 4.10.4 Creating a new Verbatim Environment

**dblatex** heavily relies upon the listing `latex` package to display the `screen`, `programlisting`, and `literallayout` blocks.

The global listing setup can be overwritten with `literal.layout.options` but the user can also provide its own listing environment to use instead of the default environment, by using the following procedure:

1. Create the new listing environment in a customized latex style, like the following example. It is required that the environment name starts with the string `"lst"`. If not, **dblatex** raises an error because it cannot recognize it as a special verbatim environment.

```
%%
%% This style is derivated from the db2latex one
%%
\NeedsTeXFormat{LaTeX2e}
```

```
\ProvidesPackage{mystyle}[2012/02/03 My DocBook Style]

%% Just use the original package and pass the options
\RequirePackageWithOptions{db2latex}

%% New listing environment doing what I want
\lstnewenvironment{lstblock}[1][{}]{
  {\lstset{numbers=left,numberstyle=\tiny,float,#1}}
  {}
}
```

2. Specify to **dblatex** the listing environment name through the *literal.environment* parameter, either on the command line or with a user XSL stylesheet.

```
$ dblatex -s mystyle.sty -P literal.environment=lstblock file.xml
```

## 4.11 Creating an Index

An index is automatically generated if some index entries (`indexterm`), telling the terms to put in the index, are written in the document. The `keyword` elements are not printed but are also added to the index.

---

### Example 4.11 Index Entry

---

```
<para>In this paragraph is described the function
<function>strcpy</function><indexterm><primary>strcpy</primary></indexterm>.
</para>
```

---

The index is put at the end of the document. It is not possible to put it somewhere else.

### 4.11.1 Internationalized Indexes

#### 4.11.1.1 Indexing Tools

**Makeindex** is used by default to build the index. It works fine for latin charset but it is not suited for other charsets and UTF-8 encoding. Moreover its sorting rule is not suited for many languages.

Therefore **dblatex** gives the possibility to use **xindy** that allows internationalized indexing. When **xindy** is used, the sorting language used is deduced from the Docbook document `lang`. If the document `lang` has no correspondance for **xindy**, or if you want to force the use of a specific sorting language, you can specify the sorting language to use. With **Xindy** you can also provide your own sort rules, but see the official **Xindy** documentation for more details.

A parameter is provided to use **xindy** instead of **makeindex**:

- *latex.index.tool*=xindy tells **dblatex** to use **xindy** instead of **makeindex** (default).

A typical use is then:

```
dblatex -P latex.index.tool=xindy file.xml
```

#### 4.11.1.2 Index Sorting

**Makeindex** has very few methods to change its index sorting rules, except the `-g` and `-L` options which are not very helpful in a DocBook context. On the contrary **xindy** can sort the index according to a specific language.

When **xindy** is used as index tool, **dblatex** passes to **xindy** through the **xindy** `-L` option the language name corresponding to the `lang` attribute of the document. If the document has no language or if **xindy** does not support the document language, the default sorting is applied. In this case you can use the following parameter:

---

- `latex.index.language` specifies the language used to sort the indexes. Currently this parameter is relevant only for xindy. The language set must be known by xindy (see the xindy documentation). When not set (or empty) the sorting language to apply is deduced from the document lang.

The parameter can be used like any other like this:

```
dblatex -P latex.index.language=german-din file.xml
```

But it can also be used through an XSL configuration file to provide new mapping rules between ISO lang codes and known xindy languages, or override the current mapping done by dblatex as shown in Example 4.12.

---

#### Example 4.12 XSL Index Language Setup

By default dblatex maps the de lang code to the language named `german-din`, and has no correspondance to map `cy` (Welsh) or `eu` (Basque). The following setup provides a mapping for these cases:

```
<xsl:param name="latex.index.tool">xindy</xsl:param>

<xsl:param name="latex.index.language">
  <xsl:variable name="lang">
    <xsl:call-template name="l10n.language">
      <xsl:with-param name="target" select="(/set|/book|/article) [1]" />
      <xsl:with-param name="xref-context" select="true()" />
    </xsl:call-template>
  </xsl:variable>

  <!-- Define Xindy lang to use in specific cases -->
  <xsl:choose>
    <xsl:when test="$lang='de'">german-duden</xsl:when>
    <xsl:when test="$lang='cy'">english</xsl:when>
    <xsl:when test="$lang='eu'">french</xsl:when>
  </xsl:choose>
</xsl:param>
```

## 4.12 Writing a Bibliography

A bibliography (bibliography) can be written and put anywhere in the document. It appears as a chapter or a section and is composed by several divisions (bibliodiv) displayed as sections or subsections.

### 4.12.1 Using Bibliography Entries

The writer selects information that describes each bibliography entry (biblioentry), and chooses the presentation order. The titles and authors are displayed first.

---

#### Example 4.13 A Bibliography

```
<bibliography><title>Bibliography Example</title>
  <bibliodiv><title>References</title>
    <biblioentry>
      <title>Document title</title>
      <author><firstname>J.</firstname><surname>Doe</surname></author>
      <pubsnumber>DEX000567325</pubsnumber>
    </biblioentry>
  </bibliodiv>
  <bibliodiv><title>White papers</title>
    <biblioentry>
      <title>Technical notes</title>
      <authorgroup>
```

```

    <author><firstname>J.</firstname><surname>Doe</surname></author>
    <author><firstname>R.</firstname><surname>Marion</surname></author>
  </authorgroup>
  <pubsnumber>DEX000704520</pubsnumber>
</biblioentry>
</bibliodiv>
</bibliography>

```

## 4.12.2 Using BibTeX Databases

Instead of writing the bibliographic materials in DocBook you can reuse some already available BibTeX databases. Of course, this feature is specific to **dblatex**, that will automatically call **bibtex** if some bibtex databases are used.

To do so, write a `bibliodiv` containing an empty `bibliomixed` element having a `bibtex` processing instruction specifying the databases to use and the style to apply.

More precisely here are the attributes supported by the `bibtex` PI:

### **bibfiles**

This attribute is mandatory and specifies the databases to use. The databases are separated by commas, and must not contain the file suffix (`.bib`). The bibfiles paths must be absolute or relative to the base directory of the document. You can also add some bibfile paths by using the `-L` option.

### **bibstyle**

Optional attribute specifying the bibliographic style to apply for rendering the databases. You can also change globally the style to apply with the `latex.biblio.style`.

The actual style file used by **bibtex** is searched in the default paths, but some extra paths can be added by using the `-l` option.

### **mode**

Optional print mode. The available values are:

#### **all**

Print all the entries contained in the databases.

#### **cited**

Print only the entries cited in the document.

#### **notcited**

Print only the entries *not* cited in the document.

When the attribute is not used, the `latex.biblio.output` parameter is used as print mode. By default the print mode is set to 'all'.

Some `bibliodivs` embedding bibliographic entries can be mixed with some `bibliodivs` using BibTeX databases, as shown by Example 4.14.

---

### Example 4.14 Bibliography using BibTeX databases

---

```

<bibliography><title>Bibliography Example</title>
  <bibliodiv><title>References</title>
    <biblioentry>
      <title>Document Title</title>
      <author><firstname>J.</firstname><surname>Doe</surname></author>
      <pubsnumber>DEX000567325</pubsnumber>
    </biblioentry>
  </bibliodiv>
  <bibliodiv><title>Bibtex References</title>
    <bibliomixed><?bibtex bibfiles="bib/latex-bib" bibstyle="alpha"?></bibliomixed>
  </bibliodiv>

```

---

```
<bibliodiv><title>Cited Bibtex References</title>
  <bibliomixed><?bibtex bibfiles="bib/database1,bib/database2"
    bibstyle="plain"
    mode="cited"?></bibliomixed>

</bibliodiv>
</bibliography>
```

### 4.12.3 Natbib Citations

You can apply natbib citation styles by playing with the citation role attribute, or with a dblatex processing instruction. The natbib use is enabled only when the `citation.natbib.use` parameter is set to 1; if not (default) the role attribute or PI are not taken into account even if present. The natbib package can be loaded with user specific options by setting the `citation.natbib.options` parameter.

When using the role attribute, simply type the natbib citation command to apply. When using the dblatex PI, put the natbib command in the `citestyle` attribute.

If you need to put some square brackets "[ ]" in the citation texts, enclose the whole text with "{ }" to protect them (as you would do in latex).

Here are some examples:

```
<para>
<citation role="\citep[see][chap. #2]">texbook</citation>
<citation role="\citep[see][{}[chap. #2]]">texbook</citation>
<citation><?dblatex citestyle="\citep[see][chap. #2]">texbook</citation>
<citation>texbook</citation>
</para>
```

You can use a global natib citation style with the `citation.default.style` parameter. By default the parameter is empty, and therefor is not used.

## 4.13 Document Revisions

The attribute `revisionflag` is usefull to identify the changes between two revisions of a document. This information is managed by dblatex, that adds revision bars in the margin of the paragraphs changed, such like in this paragraph.

Adding the revision flags can be manual, but its is tedious and error prone. The `diffmk` tool by Norman Walsh can do the work for you. See <http://www.sagehill.net/docbookxsl/Changebars.html> for more details about how to use it.

---

#### Note

With old changebar packages the revision bars only appear when using the "dvips" driver. This limitation has been fixed with changebar greater or equal to v3.5c.

---

## 4.14 Locale Support

### 4.14.1 Document Encoding

By default the latex document produced by **dblatex** is encoded in latin1, that fits well for roman-characters. This said, a real international support involves some kind of Unicode (UTF8) support.

In dblatex, the Unicode support is done by two methods that can be selected by some parameters:

---

- `latex.unicode.use=1` asks for including the unicode package (initially provided by Passivetex) in order to handle many of the unicode characters in a latin1 encoded document.
- `latex.encoding=utf8` produces a document encoded in UTF8, that is compiled in UTF8. It requires to have the `ucs` package installed.

In some languages like Chinese, Japanese or Korean, the latex document must be in UTF8. Therefore, the UTF8 encoding is forced for these languages whatever the parameter values are.

### 4.14.2 Babel Languages

Dblatex should be able to handle most of the languages supported by the babel package. Just set the `lang=lang` attribute in the root document element and dblatex will load the appropriate babel language.

### 4.14.3 CJK Languages

Dblatex can handle the CJK languages thanks to the CJK package. The CJK package must be installed to have this support available.

As said in Section 4.14.1 the latex file is encoded in UTF8. Moreover, the Cyberbit fonts are then used.

The install of the CJK package and Cyberbit fonts are well described at: <http://kile.sourceforge.net/Documentation/html/cjk.html>.

#### 4.14.3.1 Korean Support

Dblatex does not use the HLatex package to drive Korean documents. It does not use the **hmakeindex** nor the **hbibtex** tool. Currently, Korean is handled like Chinese and Japanese with the CJK package.

### 4.14.4 Mixing the languages

Dblatex cannot handle correctly a document containing several elements with different `lang` values. In particular, if the main document lang is not one of the CJK language, a portion of text written in CJK will not be handled correctly and it can result in a compilation crash.

Even if the langs mixed do not end to a compilation failure, only the main document lang will be taken into account.

## 4.15 Using XRefsyle and Olinks

Since version 0.2.7 you can use the `xrefstyle` attribute like you would do with the DocBook Project stylesheets for HTML output.

Furthermore, you can also use `olinks`. Note that Olinking is used in the PDF version of this manual, in Section 2.4.

Actually, the common DocBook Project stylesheets version 1.72 are now used by dblatex to handle all of these features.

These features are fully described in the [DocBook XSL: The Complete Guide](#) book by Bob Stayton. In particular, the following sections cover these topics:

- <http://www.sagehill.net/docbookxsl/CustomXrefs.html> explains how to use `xrefstyle`.
  - <http://www.sagehill.net/docbookxsl/Olinking.html> explains how to use `olinks`.
-

### 4.15.1 Specific xrefstyle for ulink

Dblatex defines a template that can be applied through the `xrefstyle` attribute to format an `ulink`. The template has the following general form: `url[. {show|hide}][. {after|infoot}]`

The principle is that the `show` and `hide` parts override locally for this `ulink` the `ulink.show` parameter, and the `after` and `infoot` parts override locally the `ulink.footnotes` parameter.

When only one part is defined, only one setup is overridden, and the other setup depends on the corresponding global parameter.

See `ulink.show` to have several examples of use of the `ulink xrefstyle` template.

## 4.16 Footnotes

### 4.16.1 Footnote Numbering Scope

The footnotes are well handled by latex. Dblatex just takes care about special cases like footnotes in headings or in tables. Therefore the default latex behaviour is applied for footnote numbering.

By default the footnote numbers are reset for each new chapter. If you want to change the numbering scope, you can use the latex package `chngcntr` either in a customized latex style (see Chapter 5) or in the parameter `latex.begindocument`. The following example makes the footnote numbers document wide.

```
<xsl:param name="latex.begindocument">
  <xsl:text>
% Want document wide footnotes
\usepackage{chngcntr}
\counterwithout{footnote}{chapter}
\begin{document}
  </xsl:text>
</xsl:param>
```

### 4.16.2 End Notes

You can configure **dblatex** to manage the footnotes as endnotes. In this case the notes are expected to be displayed in a dedicated section. The following sections tell how to do this.

#### 4.16.2.1 Writing a document with endnotes

To have footnotes behaving as endnotes, you just need to set the `footnote.as.endnote` to 1, and to put in your document an empty `index` element with the attribute `type` set to 'endnotes'. This index is supposed to be included in a section dedicated to contain the notes, and therefore it does not display any heading by itself. The section containing the endnotes index can also contain any other materials.

---

#### Example 4.15 Writing a document with endnotes

---

The following document contains some footnotes and a section for the End Notes:

```
<book>
  <chapter><title>A Chapter</title>
  <para>Bla bla<footnote id="fn1">First note</footnote> bla
  bla<footnote id="fn2">Second note</footnote> ...</para>
</chapter>

  <chapter><title>Another Chapter</title>
  <para>Bla bla<footnote id="fn3">Third note</footnote> bla
  bla<footnote id="fn4">Fourth note</footnote> ...</para>
</chapter>
```

---



```
<chapter><title>End Notes</title>
<para>This chapter contains all the notes of the book.</para>

<index type="endnotes"/>
</chapter>
</book>
```

**dblatex** is called with:

```
$ dblatex -P footnote.as.endnote=1 file.xml
```

#### 4.16.2.2 Setup Properties

Currently the endnotes are handled by the latex package `endnotes`. You can customize its use with the `endnotes.properties` attribute set. This attribute set is filled by default with the values given by the internal attribute set `endnotes.properties.default`, and you can override the following attributes:

##### **package**

Recall the latex package in charge to handle the endnotes. Attribute provided for provision since currently there is no real alternative with well established packages.

##### **heading**

Macros to render the heading of the endnotes to display.

##### **font-size**

Macro specifying the font size to apply for each endnote. The package default is `\footnotesize`. The `dblatex` default is `\normalsize`.

##### **note-format**

Macros specifying how to render an end note. The package default is the same formatting that footnotes. The `dblatex` default is to print out endnotes like a numbered list.

The default setup:

```
<xsl:attribute-set name="endnotes.properties.default">
  <xsl:attribute name="package">endnotes</xsl:attribute>

  <!-- No header: endnotes are embedded in another section -->
  <xsl:attribute name="heading">\mbox{}\par</xsl:attribute>

  <!-- Show end notes as a numbered list -->
  <xsl:attribute name="font-size">\normalsize</xsl:attribute>
  <xsl:attribute name="note-format">%
    \leftskip=1.8em\noindent
    \makebox[0pt][r]{\theenmark.\rule{0pt}{\baselineskip}}\ignorespaces
  </xsl:attribute>
</xsl:attribute-set>

<xsl:attribute-set name="endnotes.properties"
  use-attribute-sets="endnotes.properties.default"/>
```

#### 4.16.2.3 Endnotes Setup from scratch

If you want to fully control the endnotes setup, add some other macros, you can directly override the template `endnotes.setup`, as shown by the example below. If the endnote setup is already defined in your latex style you can override the template to make it empty in order to avoid some conflict between the latex style definition and the default one done by `dblatex`.

```
<!-- Use the default endnotes package setup and change the heading -->
<xsl:template name="endnotes.setup">
  <xsl:text>\usepackage{endnotes}&#10;</xsl:text>
  <xsl:text>\def\enoteheading{\paragraph*{List Of Notes}%
    \mbox{} \par \vskip-\baselineskip}&#10;</xsl:text>
</xsl:template>
```

#### 4.16.2.4 Grouping Endnotes

By default the endnotes are displayed for the whole document as a global list. You can configure dblatex to show the endnotes grouped per part or per chapter. A heading is put before each group of notes to recall the component (part, chapter, or another section) that contains these notes. The purpose is to make the research of the notes at the end of the document easier for the reader.

To group the endnotes according to the granularity you wish, you just need to set the `endnotes.heading.groups` with the expected section types separated by a space. For example, the following setup displays notes per part and per chapter:

```
<xsl:param name="footnote.as.endnote" select="1"/>
<xsl:param name="endnotes.heading.groups" select="'part chapter'"/>
```

##### 4.16.2.4.1 Adding new Groups

By default dblatex can group the notes per chapter and/or per part, provided that the section type is declared in `endnotes.heading.groups` as explained previously. If you want to add another section type you need to override the template called in mode `endnotes`, and to add this type to the declared groups. Usually the `endnotes` mode template only calls the `endnotes.add.header` template. The example below makes a new group for preface.

```
<xsl:param name="endnotes.heading.groups" select="'part chapter preface'"/>

<xsl:template match="preface" mode="endnotes">
  <xsl:call-template name="endnotes.add.header">
    <xsl:with-param name="reset-counter" select="1"/>
  </xsl:call-template>
</xsl:template>
```

##### 4.16.2.4.2 Formatting the Headings text

You can use the parameter `endnotes.heading.style` to format the headings of the groups with the same syntax than `xrefs` type does. The example below gives a template where the title and the page of the chapter containing the notes are displayed.

```
<xsl:param name="endnotes.heading.style">
  <xsl:text>template:Notes of the chapter "%t", page %p</xsl:text>
</xsl:param>
```

##### 4.16.2.4.3 LaTeX Command to make the Headings

By default **dblatex** creates the headings of the groups with a section command whose level is just below the level of the endnotes section. For example, if the endnotes section is a chapter, the headings are created by using a `\section*` latex command. If the endnotes section is a section, the headings are done by using `\subsection*`, and so on.

If this behaviour does not fit your needs you can specify the command to use with the parameter `endnotes.heading.command`. It can be usefull if you want to format these heading in a specific way. The heading markup produced following the `endnotes.heading.style` template is passed as an argument of the specified command. The example below uses the command `\enoteheader*` to create the headings. It assumes that this macro is defined somewhere else (e.g. in a user latex style).

```
<xsl:param name="endnotes.heading.command" select="'\enoteheader*'"/>
```

#### 4.16.2.4.4 Endnotes Counter Scope

By default the endnotes counter restarts from one in each chapter or part when they are grouped. You can change this behaviour by overriding the `endnotes.counter.resetby` parameter that lists the section types where the counter is reset. If you want a global counter running for the whole document, just set the parameter empty.

## Chapter 5

# Customization

The transformation process (and thus the output rendering) can be heavily customized by:

- using some [configuration parameters](#) either in a [configuration stylesheet](#) or directly from the [command line](#),
- using [Processing Instructions](#) to create some instructions very specific to dblatex,
- using some [customized stylesheets](#),
- using a [customized LaTeX style package](#).
- using a [LaTeX post process script or plugin](#).

All these customization methods can be used independently and in exceptional cases, but it can also be combined and registered in a master configuration file, called a specification file (cf. Section 5.7) to create a new tool dedicated to your needs.

### 5.1 Using XSL Parameters

The PDF rendering can be customised by using some XSL configuration parameters. Appendix A contains the reference documentation of the available user-configurable parameters.

### 5.2 Setting Command line Parameters

You can set some XSL parameters directly from the command line without creating a configuration parameter stylesheet, with the `-P parameter=value` option.

The following example set the `latex.hyperparam` parameter value:

```
dblatex -P latex.hyperparam=colorlinks,linkcolor=blue myfile.xml
```

### 5.3 Using Processing Instructions

Dblatex has Processing Instructions (PI) which can modify the default document formatting. Usually these instructions alter the output formatting of specific DocBook elements, like table cells.

To alter formatting globally it is better to set an appropriate [stylesheet parameter](#).

Processing instructions are written `<?name content ?>`. Most often *content* will have the form of one or more XML attributes with a value, as follows: `<?name attribute="value" ?>`.

---

The list of the available Processing Instructions are given in Appendix B.

Here is an example of a PI used in a table:

---

**Example 5.1** Table width specified with a Processing Instruction
 

---

```
<informaltable><?dblatex table-width="autowidth.column: 1 3"?>
  <tgroup cols="4" colsep="1" rowsep="1" align="left">
    <colspec colname="c1"/>          <!-- automatic width is applied to column #1 -->
    <colspec align="left" colwidth="*/>
    <colspec align="right" colwidth="5cm"/> <!-- automatic width is applied to column #3 -->
    <colspec align="center" colwidth="3cm"/>
    ...
  </tgroup>
</informaltable>
```

---

## 5.4 XSL User Stylesheet

You can provide your own XSL stylesheet to set some of the XSL parameters, and/or to override some of the dblatex XSL templates. The user stylesheet is specified by using the option `-p custom.xml`.

### 5.4.1 Changing the XSL parameter values

The parameters can be stored in a user defined XSL stylesheet. An example of configuration stylesheet is given with this manual:

```
<?xml version='1.0' encoding="iso-8859-1"?>
<xsl:stylesheet xmlns:xsl="http://www.w3.org/1999/XSL/Transform" version='1.0'>

<!-- Target Database set by the command line -->

<xsl:param name="target.database.document">olinkdb.xml</xsl:param>
-->

<!-- Use the Bob Stayton's Tip related to olinking -->
<xsl:param name="current.docid" select="/*/@id"/>

<!-- Use the literal scaling feature -->
<xsl:param name="literal.extensions">scale.by.width</xsl:param>

<!-- We want the TOC links in the titles, and in blue. -->
<xsl:param name="latex.hyperparam">colorlinks,linkcolor=blue,pdfstartview=FitH</xsl:param>

<!-- Put the dblatex logo -->
<xsl:param name="doc.publisher.show">1</xsl:param>

<!-- Show the list of examples too -->
<xsl:param name="doc.lot.show">figure,table,example</xsl:param>

<!-- DocBook like description -->
<xsl:param name="term.breakline">1</xsl:param>

<!-- Manpage titles not numbered -->
<xsl:param name="refentry.numbered">0</xsl:param>

<xsl:template match="parameter">
  <xsl:variable name="name" select="."/>
  <xsl:variable name="target" select="key('id',$name)[1]"/>

  <xsl:choose>
```

---

```

<xsl:when test="count($target) > 0">
  <!-- Hot link to the parameter refentry -->
  <xsl:call-template name="hyperlink.markup">
    <xsl:with-param name="linkend" select="$name"/>
    <xsl:with-param name="text">
      <xsl:apply-imports/>
    </xsl:with-param>
  </xsl:call-template>
  <!-- Index entry for this parameter -->
  <xsl:text>\index{Parameters!}</xsl:text>
  <xsl:value-of select="$name"/>
  <xsl:text>></xsl:text>
</xsl:when>
<xsl:otherwise>
  <!--
  <xsl:message>No reference for parameter: '<xsl:value-of
  select="$name"/>'</xsl:message>
  -->
  <xsl:apply-imports/>
</xsl:otherwise>
</xsl:choose>
</xsl:template>

<xsl:template match="sgmltag[@class='xmlpi']">
  <xsl:variable name="name" select="normalize-space(.)"/>
  <xsl:variable name="nameref" select="concat('pi-',translate($name,' ','_'))"/>
  <xsl:variable name="target" select="key('id',$nameref)[1]"/>

  <xsl:choose>
  <xsl:when test="count($target) > 0">
    <!-- Hot link to the parameter refentry -->
    <xsl:call-template name="hyperlink.markup">
      <xsl:with-param name="linkend" select="$nameref"/>
      <xsl:with-param name="text">
        <xsl:apply-imports/>
      </xsl:with-param>
    </xsl:call-template>
    <!-- Index entry for this parameter -->
    <xsl:text>\index{Processing Instructions!}</xsl:text>
    <xsl:value-of select="$name"/>
    <xsl:text>></xsl:text>
  </xsl:when>
  <xsl:otherwise>
    <!--
    <xsl:message>No reference for parameter: '<xsl:value-of
    select="$name"/>'</xsl:message>
    -->
    <xsl:apply-imports/>
  </xsl:otherwise>
  </xsl:choose>
</xsl:template>

</xsl:stylesheet>

```

### 5.4.2 Overriding some templates

You can directly put the overriding templates in your XSL stylesheet, but do not try to import the default dblatex stylesheets in it: it is automatically done by the tool. So, just focus on the template to override and dblatex will ensure that your definitions will get precedence over the dblatex ones.

You can of course split your templates in several files, and import each of them in the main user stylesheet by calling `xsl:import`.

---

#### Example 5.2 Overriding templates

---

```
<?xml version='1.0' encoding="iso-8859-1"?>
<xsl:stylesheet xmlns:xsl="http://www.w3.org/1999/XSL/Transform" version='1.0'>

<!-- Let's import our own XSL to override the default behaviour. -->
<xsl:import href="mystyle.xsl"/>

<!-- Let's patch directly a template here -->
<xsl:template match="article" mode="docinfo">
  <xsl:apply-imports/>
  <xsl:text>\let\mymacro=\DBKrelease</xsl:text>
</xsl:template>

</xsl:stylesheet>
```

---

## 5.5 Customized LaTeX style

The actual output rendering is done by the latex style package used, and not by the XSL stylesheets whose role is only to translate to latex. Users can provide their own LaTeX style file, in respect of some rules:

- The LaTeX style package preamble must support all the options that the XSL stylesheets can pass to the package.
- Some packages must be used to make all the thing work.
- The docbook interface must be defined: the XSL stylesheets register some elements information in LaTeX commands. These commands or macro are the only ones specific to DocBook that are explicitly used by the XSL stylesheets. Other specific macros are used but are not intended to be changed by the user. These hidden macros are defined in the `dbk_core` latex package.

The latex style file to use is specified by using the option `--texstyle latex_style`. An example of a simple LaTeX DocBook style is provided in the package.

The `--texstyle latex_style` option accepts a package name (no path and no `.sty` extension) or a full style file path. If a full path is used, the filename must ends with `.sty`.

```
# Give a package name and assume its path is already in TEXINPUTS
dblet --texstyle=mystyle file.xml

# Give the full package path. The TEXINPUTS is then updated by dblet
dblet --texstyle=./mystyle.sty file.xml
```

### 5.5.1 Reusing an existing LaTeX style

You can either create your latex style from scratch, in respect of the interfaces described in the following sections, or you can simply reuse an already existing style and override what you want. The latter method is easier for small things to change.

Here is an example of a style package reusing the default docbook style:

---

**Example 5.3** Reused LaTeX style

```

%%
%% This style is derivated from the docbook one
%%
\NeedsTeXFormat{LaTeX2e}
\ProvidesPackage{mystyle}[2007/04/04 My DocBook Style]

%% Just use the original package and pass the options
\RequirePackageWithOptions{docbook}

%% Redefine the paragraph layout
\setlength\parskip{\medskipamount}
\setlength\parindent{5pt}

%% Redefine some french settings
\babelsetup{fr}{%
  \catcode'\Tl\guillemotleft =\active
  \catcode'\Tl\guillemotright =\active
  \def\Tl\guillemotleft {u\og\ignorespaces}
  \def\Tl\guillemotright {v\unskip\fg}
}

```

**5.5.2 Package options**

A compliant LaTeX style package supports the following options. The options are provided by the XSL stylesheets according to the document attributes.

| Option                 | Role   |
|------------------------|--|
| hyperlink, nohyperlink | Indicates if links in the document are provided or not |
| article, book          | The document is an article or a book                   |

**5.5.3 Needed packages**

A LaTeX style package must at least include the following packages.

| Package  | Description  |
|----------|--|
| dbk_core | Core LaTeX definitions and macros needed for DocBook |

**5.5.4 DocBook interface**

All the latex commands beginning with DBK are related to elements under `bookinfo` or `articleinfo`.

| Command         | Description                        |
|-----------------|------------------------------------|
| \DBKreference   | mapped to <code>pubsnumber</code>  |
| \DBKsite        | mapped to <code>address</code>     |
| \DBKcopyright   | mapped to <code>copyright</code>   |
| \DBKdate        | mapped to <code>date</code>        |
| \DBKedition     | mapped to <code>edition</code>     |
| \DBKpubdate     | mapped to <code>pubdate</code>     |
| \DBKsubtitle    | mapped to <code>subtitle</code>    |
| \DBKreleaseinfo | mapped to <code>releaseinfo</code> |



| Command                      | Description   |
|------------------------------|---|
| <code>\DBKlegalnotice</code> | environment mapped to a <code>legalnotice</code> . The legal notices are all put into the <code>\DBKlegalblock</code> command. It is up to the latex stylesheet to decide where to put it in the document.  |
| <code>\DBKlegalblock</code>  | wrapper command for the <code>\DBKlegalnotice</code> environments, used by the latex stylesheet to decide where to put the legal notices in the document.   |
| <code>\DBKindexation</code>  | This command contains the <code>othercredit</code> information translated to latex by the XSL. This command must be placed where the <code>othercredit</code> shall appear in the document.   |
| <code>\DBKindtable</code>    | This environment must be defined by the user to render the <code>othercredit</code> list. It can be displayed as a table, listitem, description list, or anything that suits your need.   |
| <code>\DBKinditem</code>     | This is an <code>othercredit</code> item.   |
| <code>\DBKrevtable</code>    | This environment must be defined by the user to render the <code>revhistory</code> table. Untill now it is not really possible to customize it, since it must be a table with four columns, each column for a <code>revhistory</code> piece of information. |
| float example                | This float is expected to be defined, and is mapped to <code>example</code> . It is not defined by default by the <code>dbk_core</code> package to allow the user to define its rendering (ruled or not, etc.)  |
| float dbequation             | This float is expected to be defined, and is mapped to <code>equation</code> . It is not defined by default by the <code>dbk_core</code> package to allow the user to define its rendering (ruled or not, etc.)   |

### 5.5.5 Debugging your Style

It is not surprising if your first `dblatex` compilation fails with a fresh LaTeX style. So, how to debug it when used with `dblatex`?

The following steps can help you:

1. Compile your file in the debug mode (option `-d`). When the compilation is done, the temporary working directory will not be removed.

```
$ dblatex --texstyle=./mystyle.sty -d file.xml
...
/tmp/tpub-ben-99629 is not removed
```

2. Go under the building temporary directory, and set the environment with the file `env_tex`.

```
$ cd /tmp/tpub-ben-99629
$ . env_tex
```

3. Compile the temporary latex file produced by the XSL stylesheets. Its name has the suffix `"_tmp.tex"`.

```
$ pdflatex file_tmp.tex
$ [ many outputs here ]
```

4. Now latex stops when it encounters an error so that you can debug your stylesheet.

## 5.6 Latex post process script

Extra user actions can be processed on the latex file produced by the XSL stylesheets or on its temporary working files produced by the latex compilation.

For instance, in the documents I write the cover page must display the number of pages of the document, but written in full letters (e.g. 23 is written “twenty three”). The latex post process script is then helpfull, and in this particular case it patches the .aux file.

The post process script is called just before the last latex compilation, and takes one parameter, the latex file compiled by the tool.

### 5.6.1 Post latex compilations

The latex compilations done once the script is called depend on the return code of the script:

- When the return code is 0, **dblatex** continues the compilation as many times as necessary.
- When the return code is 1, no more compilation is done by dblatex. This case is useful if the script needs to control precisely the number of compilation to apply. It is up to the script to perform the expected compilations.

To do so, the script can retrieve in the LATEX environment variable the actual compiler used by **dblatex**.

- When the return code is another value, an error is raised to signal a failed post process script execution.

### 5.6.2 Post processing with a Python Plugin

You can use a python plugin instead of a script by prefixing the plugin name with the string "plugin:". When using a plugin you must not put the python suffix in the plugin name. If the plugin is in one of the Python system directories, or in the current directory where you call dblatex, or in one of the directories of the PYTHONPATH environment variable, you don't need to specify a directory location. Otherwise put the plugin directory path before the plugin name.

Here are several plugin call examples:

```
# The texpost.py module is in one of the python paths
dblatex -r plugin:texpost file.xml

# The texpost.py module location is specified with an absolute path
dblatex -r plugin:/path/to/texpost file.xml

# The texpost.py module is specified through a relative path from current dir
dblatex -r plugin:relative/path/from/current/dir/texpost file.xml
```

The plugin must contain a main entry point. **Dblatex** will pass the following parameters to the entry point: *latex\_file* to specify the latex file to post process, and *stdout* to specify the output stream to use to be consistent with the dblatex verbosity.

---

#### Example 5.4 Texpost Python Plugin Example

---

```
import sys
import os

def main(latex_file, stdout):
    """
    Texpost Plugin Entry point
    """
    # Let's find out the backend used
    tex_engine = os.environ["LATEX"]

    # Let's log something
    print >>stdout, "Plugin called on '%s' file" % (latex_file)
```

---

```
# Open the latex file and parse it
texfile = open(latex_file)
...

# Now decide if a new compilation must occur
if has_changed:
    sys.exit(0)
else:
    sys.exit(1)
```

## 5.7 Dblatex Configuration File

A master configuration file, also called a specification file, can be used to list all the customizations and options to apply. Such a file is passed by using the option `-S config_file`.

### 5.7.1 XML Configuration File Format

You should use the XML format to configure dblatex. It contains more features than the text format used up to the 0.3.7 release that is now deprecated. The principle remains the same, that is, most of the configuration parameters correspond to a command line option.

Here is a full example of a configuration file. In the next sections the meaning and use of the configuration tags are detailed.

```
<?xml version="1.0" encoding="utf-8"?>
<!-- ===== -->
<!-- Dblatex Configuration example for building a book -->
<!-- ===== -->
<config xmlns="http://dblatex.sourceforge.net/config" version="1.0">
  <latex>
    <backend use="xetex"/>
    <texstyle use="dbsimple"/>
    <texpost fileref="dblatex-postprocess"/>
    <indexstyle fileref="../myindexstyle.ist"/>
    <texinputs>../mystyledir:/etc/texmf/userfont</texinputs>
  </latex>
  <xslt>
    <stylesheet fileref="user_param.xsl"/>
    <stylesheet fileref="xetex_param.xsl"/>
    <stylesheet fileref="pdf.xsl"/>
  </xslt>
  <imagedata>
    <converter src="svg" dst="*" docformat="pdf">
      <command>
        inkscape -z -D --export-dpi=600 --export-%(dst)s=%(output)s %(input)s
      </command>
    </converter>
  </imagedata>
  <options>-X -V</options>
</config>
```

Another example, much simpler, is the configuration file used for this manual.

---

#### Example 5.5 User Manual Configuration File

---

```
<?xml version="1.0" ?>
<!--
=====
```

---

```

Configuration file for dblatex documentation (manual, release notes)
=====
-->
<config xmlns="http://dblatex.sourceforge.net/config">
  <latex>
    <texinputs>../latex//</texinputs>
    <texstyle use="docbook"/>
    <backend use="pdftex"/>
  </latex>
  <xslt>
    <stylesheet fileref="manual.xsl"/>
  </xslt>
</config>

```

The following sections detail the meaning of each tag. Note that dblatex provides some schema that you can use to validate your configuration file.

#### 5.7.1.1 <config>

It is the root element of a configuration file. A valid configuration file must have a `config` root element.

Attributes:

##### **xmlns**

The namespace to use for a dblatex configuration file is: `http://dblatex.sourceforge.net/config`.

The following elements occur in `config`: [latex](#), [xslt](#), [imagedata](#), [options](#).

#### 5.7.1.2 <latex>

The `latex` element contains the configuration data related to the latex processing.

Attributes: none

The following elements occur in `latex`:

##### **backend**

It defines the latex engine to use, like the option `--backend` does. The backend name is specified through the `use` attribute.

##### **texstyle**

It defines the docbook latex style to use, like the option `--texstyle` does. The latex package is specified through the `use` attribute.

##### **texpost**

It defines the latex post-processing script to use, like the option `--texpost` does. The script name is specified through the `use` attribute or the `fileref` attribute.

##### **indexstyle**

It defines index style file (.ist) to use, like the option `--indexstyle` does. The filename is specified through the `fileref` attribute.

##### **texinputs**

The element text defines the extra paths to add to TEXINPUTS, like the option `--texinputs` does.

##### **bibinputs**

The element text defines the lookup paths of BIBINPUTS, like you would do by successive use of the option `--bib-path`.

##### **bstinputs**

The element text defines the lookup paths of BSTINPUTS, like you would do by successive use of the option `--bst-path`.

### 5.7.1.3 <xslt>

The xslt element contains the configuration data related to the XSL processing.

Attributes: none

The following elements occur in xslt:

#### stylesheet

It defines a user stylesheet to use, like the option `--xsl-user` does. The stylesheet name is specified through the `fileref` attribute. If several `stylesheet` elements are set, the precedence is the same like using the option `--xsl-user` several times.

#### engine

It defines the XSLT processor to use, like the option `--xslt` does. The engine name is specified through the `use` attribute.

### 5.7.1.4 <imagedata>

The imagedata element contains the rules and commands to convert on the fly the images included in the docbook document.

Attributes: none

The following elements occur in imagedata:

#### figpath

It defines a path where to find the images, like the option `--fig-path` does.

#### converter

It defines an image transformation rule. See [converter](#) for more details.

### 5.7.1.5 <converter>

The converter element defines a rule about how to convert on the fly an image in a docbook document to the corresponding image used in the built latex file. The goal is to have an image format compatible with the latex engine, whatever the original format is. **Dblatex** has a default set of rules, but one can overwrite or add some rules.

Attributes:

#### src

Format of the original image referenced in the XML document. The converter only applies to the images matching this format.

#### dst

Target format once converted. The converter only applies to the original images having the format `src` and that need to be converted to the format `dst`. `dst` can take the special value `"*"` meaning that the rule applies for all the possible target formats (e.g. `eps`, `pdf`, `png`).

#### docformat

Specify for which document output format the converter applies. For example, if `docformat` is set to `"pdf"`, it means that the converter applies only if the document output format is PDF. The converter will not apply if you want to build a PostScript or DVI document.

#### backend

The converter applies only if it is this latex engine that is used. For example, it is usefull if you want to convert an image in a specific way only when `xetex` is used.

The following elements occur in `converter`:

#### commandchain

List of the commands to run. A `commandchain` contains one or more `command` elements.

#### command

command to execute to perform the conversion, or a part of the conversion if several commands are chained. See [command](#).

### 5.7.1.6 <command>

The command element contains the arguments of the command to run. The arguments can contain some predefined keywords that are replaced by the actual values when the command is executed. The known keywords are:

**% (src) s**

Replaced by the `src` value (original image format).

**% (dst) s**

Replaced by the `dst` value (target image format).

**% (input) s**

Replaced by the input file required by the command. In the case of an image conversion, it is the filename of the original image to convert.

**% (output) s**

Replaced by the name of the output file required by the command. In the case of an image conversion, it is the filename of the output image once converted.

Attributes:

**input**

Standard input of the command to run. It can specify a file or it can specify to use the output of the preceding command if the keyword "PIPE" is used.

**output**

Standard output of the command to run. It can specify a file or it can specify that the output shall be redirected to the next command if the keyword "PIPE" is used.

**shell**

When set to "1" or "true", the command is run in a shell environment.

### 5.7.1.7 <options>

The options element lists the extra arguments to pass to **dblatex**.

## 5.7.2 Deprecated Text Configuration File Format

The format of the file is the following:

- Every comment starts with a "#", and is ignored.
- The file must contain one parameter by line.
- The format of a parameter is the following:

```
<keyword>: <value>
```

- Every parameter is mapped to an option that can be passed to **dblatex**.
- An unknown parameter is silently ignored (the whole line is dropped).
- The parameters defining a path (a file or a directory) can take absolute or relative paths. A relative path must be defined from the specification file itself. For instance, a specification file under `/the/spec/directory/` with a parameter describing the file `../where/this/file/is/myfile` points to `/the/spec/where/this/file/is/myfile`.

The following table lists the supported parameters and the corresponding command line option.

| Keyword   | Value                | Corresponding option | Description   |
|-----------|----------------------|----------------------|---|
| TexInputs | Directories          | --texinputs          | Defines extra path to add to TEXINPUTS  |
| TexStyle  | Latex package name   | --texstyle           | Defines the LaTeX style package to use.   |
| TexPost   | Script file name     | --texpost            | Defines the LaTeX post process script to use.   |
| XslParam  | Parameter file name  | -p                   | Defines the parameter file to use.  |
| FigInputs | Directories          | -I                   | Defines the extra figures path.   |
| Options   | Command line options | None                 | Lists command options to use by default when using the tool. The options specified by the parameter are directly passed to <b>dblatex</b> |

### 5.7.3 Configuration Paths

By default **dblatex** tries to find the configuration files in the following paths, in respect of the order:

1. The current directory
2. \$HOME/.dblatex
3. /etc/dblatex
4. The dblatex package configuration directories.

You can add some extra paths where to look for by setting the `DBLATEX_CONFIG_FILES` environment variable. The paths are separated by ":" in Unix like systems, and by ";" on Windows. These paths are used only when nothing is found in the default paths.

## 5.8 Customization Precedence

All the customization queries are translated to the corresponding command line options. Thus, using several customization methods can be inconsistent because each of them override the same option with another value.

For instance, you can specify the use of a specification file in which it is said to use a latex style (parameter `TexStyle`) and explicitly use the `--texstyle` command line option. So, what is the behaviour?

The options order is the following:

- If a specification file is used (`-S` option), the options are set to the specification file parameters.
- The options explicitly passed override the specification file setting, whatever is the position of the options (i.e. before or after the `-S` option).
- If an option is passed several times, this is the last occurrence that is used.

---

**Example 5.6** Customization Precedence

---

Let's consider the specification file containing the following parameters:

```
XslParam: file3.xsl  
Options: -b pdftex  
TexStyle: mystyle1
```

And now the command line:

```
dblatex -b dvips -p file1.xsl -p file2.xsl -S file.specs -s mystyle2 mydoc.xml
```

The setting used is the following:

- “-b dvips” overrides “-b pdftex” set by the spec file.
  - “-p file2.xsl” overrides “-p file1.xsl” since it is defined after, and overrides “file3.xsl” set by the spec file.
  - “-s mystyle2” override “mystyle1” set by the spec file.
-



## Chapter 6

# FAQ

The purpose of this mini FAQ is to give some tips about how customizing or tweaking the PDF output.

### 6.1 My images are too big. What can I do?

When an image is included via `imagedata` with no scaling attributes (e.g. `width`, `height`, `contentwidth`) it is its natural size that is used.

One can change individually the size of an `imagedata` by defining its attributes (see [\[TDG\]](#) for more details). One can also use the parameter `imagedata.default.scale` to apply a systematic scaling rule on every image that has no explicit attribute.

The parameter `imagedata.default.scale` can take:

- The default predefined value "pagebound": the image natural size is used, up to the page boundaries. That is, if an image natural width is greater than the page width its size is proportionally reduced so that it is contained in the page. The same control is done for height.
- Any combination of valid `\includegraphics` options. For example

**`imagedata.default.scale=scale=40%`**

The scale 40% is applied on the images.

**`imagedata.default.scale=width=40%,height=3in`**

This example is weird but shows that several options can be used. In this case the image width is 40% of the page width, and the height is fixed to 3 inches. The risk to have an anamorphous result is very high here.

### 6.2 How can I have the PDF fit to height by default?

The behaviour of the PDF file when opened by a reader like Acrobat Reader can be customized with the parameter `latex.hyperparam`. See the section called "[Description](#)" for more details about this parameter.

To answer precisely to the question, set the parameter with the option "`pdfstartview=FitV`".

### 6.3 How can I have all the PDF hyperlinks in blue color?

Same answer than for the previous question.

For this particular case, set the parameter with the options "`linktocpage,colorlinks,linkcolor=blue,citecolor=blue,urlcolor=blue`".

---

## 6.4 How can I remove that stupid float rules?

If you wonder about this, you probably use the `db2latex` style. To remove the rules, you need to patch the `db2latex.sty`. You can:

- Simply remove the floatstyle definition for the floats for which you don't want the rules.
- Explicitly use the plain floatstyle. Note that using this explicit style does not allow to change the float title position anymore. The plain style always puts the title at the bottom of the float.

## 6.5 My long tables don't split in several pages. Why?

A formal table (`table` element) is put in a float, so that it can have a numbered caption and be placed by `tex` at the best place. The limitation is that a float cannot split over several pages.

For long tables that need to split, use `informaltable` instead.

## 6.6 I cannot put a table in an example.

A formal table (`table` element) is put in a float, and cannot be put in another float like an example. You can use an `informaltable` instead.

## 6.7 I cannot compile my cyrillic document. Why?

A document using some characters different from the roman alphabet may face some troubles, because `latex` natively handles only `latin1` encoding.

Try the different unicode supports provided by `dblatex`:

- Use the XeTeX backend, a new `tex` engine that natively supports Unicode characters: `dblatex -b xetex file.xml`.
- Ask for using the `latex` unicode support by setting the `latex.encoding=utf8` parameter: `dblatex -P latex.encoding=utf8 file.xml`.
- Use the Passivetex extensions by setting the `latex.unicode.use=1` parameter: `dblatex -P latex.unicode.use=1 file.xml`.



See Section [4.14.1](#) for more details.

---

## Chapter 7

# Thanks

### 7.1 Sponsors

Thanks to the companies that sponsored dblatex at a time or another:  <sup>1</sup>, and the Raphael Hertzog's company  <sup>2</sup>.

### 7.2 Contributors

Thanks to Andreas Hoenen who packages and maintains dblatex for Debian, provides patches and so on.

Thanks also to other contributors: David Hedley (newtbl implementor), and Nicolas Pernetty (Windows port).

### 7.3 Pioners

Thanks to the people who contributed to the project at its early age: Jean-Yves Le Ruyet, precursory and hard-working user, Julien Ducourthial for his precious help, Vincent Hottier who asked for the embedded LaTeX equations support.

Special thanks to the KDE documentation team (especially Philip Rodrigues), Michael Smith (from the DocBook Project), and Kai Bormmann, for their feedbacks, encouragements, and advice. They were the first people who believed in this project and boosted dblatex.

---

<sup>1</sup><http://www.froglogic.com/>

<sup>2</sup><http://www.freexian.com/>

---

## Appendix A

# Dblatex XSL Parameter Reference

This is reference documentation for all user-configurable parameters in the dblatex XSL stylesheets.

The organization of the reference entries mimics the [FO Parameter Reference](#) for people familiar with the DocBook Project documentation.

### A.1 Admonitions

#### **figure.caution**

*figure.caution* — Figure to use to render a `caution` block.

##### **Synopsis**

```
<xsl:param name="figure.caution">warning</xsl:param>
```

##### **Description**

Figure to use to render a `caution` block. This parameter is added to allow new latex styles to use their own figures in admonitions.

#### **figure.important**

*figure.important* — Figure to use to render a `important` block

##### **Synopsis**

```
<xsl:param name="figure.important">warning</xsl:param>
```

##### **Description**

Figure to use to render a `important` block. This parameter is added to allow new latex styles to use their own figures in admonitions.

---

## figure.note

*figure.note* — Figure to use to render a `note` block

### Synopsis

```
<xsl:param name="figure.note"/>
```

### Description

Figure to use to render a `note` block. This parameter is added to allow new latex styles to use their own figures in admonitions.

## figure.tip

*figure.tip* — Figure to use to render a `tip` block

### Synopsis

```
<xsl:param name="figure.tip"/>
```

### Description

Figure to use to render a `tip` block. This parameter is added to allow new latex styles to use their own figures in admonitions.

## figure.warning

*figure.warning* — Figure to use to render a `warning` block

### Synopsis

```
<xsl:param name="figure.warning">warning</xsl:param>
```

### Description

Figure to use to render a `warning` block. This parameter is added to allow new latex styles to use their own figures in admonitions.

## A.2 Callouts

### callout.linkends.hot

*callout.linkends.hot* — Hot links callout items

### Synopsis

```
<xsl:param name="callout.linkends.hot" select="'1'"/>
```

---

**Description**

The callouts referenced in a callout list are hot links if the parameter is set to 1. Then, the references are in red such like any other cross-reference link in the document.

**calloutlist.style**

*calloutlist.style* — Callout list style to apply

**Synopsis**

```
<xsl:param name="calloutlist.style" select="'leftmargin=1cm,style=sameline'"/>
```

**Description**

Defines how the callout list items are displayed. The value must be some valid enumitem description list options.

**callout.markup.circled**

*callout.markup.circled* — Use black circles for numbering the callout items?

**Synopsis**

```
<xsl:param name="callout.markup.circled" select="'1'"/>
```

**Description**

Set to 1 the callouts references in a `calloutlist` are white numbers in black circles, like the markups in the listing (or graphic). Set to 0 the references are simple numbers.

**co.linkends.show**

*co.linkends.show* — Show the references to calloutlist items next to the markup

**Synopsis**

```
<xsl:param name="co.linkends.show" select="'1'"/>
```

**Description**

Next to a callout markup the links to the corresponding calloutlist items are shown when the parameter is set to 1. Set to 0 the links are not shown.

**imageobjectco.hide**

*imageobjectco.hide* — Hide the callout markups on the image

---

## Synopsis

```
<xsl:param name="imageobjectco.hide" select="0"/>
```

## Description

When set to 1 the callout numbered circles are not drawn on the image. Only the anchors are put, allowing callout list items to jump at the referenced position on the image. The purpose of this parameter is to allow the use of images that already contain the callout numbers (like for GIMP manual).

## A.3 ToC/LoT/Index Generation

### doc.lot.show

*doc.lot.show* — Specifies the Lists of Titles to display

## Synopsis

```
<xsl:param name="doc.lot.show">figure,table</xsl:param>
```

## Description

Specifies which Lists of Titles should be printed after the Table of Content. The value is a comma separated list of the LoTs to show. The supported LoTs are "figure", "table", "equation", and "example". The list order represents the LoTs order in the output document.

### doc.toc.show

*doc.toc.show* — Print the Table Of Contents

## Synopsis

```
<xsl:param name="doc.toc.show">1</xsl:param>
```

## Description

Print the table of contents when set to 1.

### titleabbrev.in.toc

*titleabbrev.in.toc* — Should titleabbrev be put in the TOC instead of title?

## Synopsis

```
<xsl:param name="titleabbrev.in.toc">1</xsl:param>
```

---

**Description**

Set to 1 the titleabbrev content is put in the TOC instead of the title.

**toc.section.depth**

*toc.section.depth* — How deep should recursive sections appear in the TOC?

**Synopsis**

```
<xsl:param name="toc.section.depth">5</xsl:param>
```

**Description**

Depth of the TOC. Used to set the latex `tocdepth` counter.

**bibliography.tocdepth**

*bibliography.tocdepth* — How bibliography section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="bibliography.tocdepth">5</xsl:param>
```

**Description**

Same than *preface.tocdepth* for bibliography sections. Meaningful only when *bibliography.numbered* is set to 0.

**See Also**

*bibliography.numbered*.

*refentry.numbered*, *refentry.tocdepth*.

*glossary.numbered*, *glossary.tocdepth*.

*index.numbered*, *index.tocdepth*.

**colophon.tocdepth**

*colophon.tocdepth* — How colophon section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="colophon.tocdepth">0</xsl:param>
```



**Description**

Same than [preface.tocdepth](#) for colophon sections.

**dedication.tocdepth**

[dedication.tocdepth](#) — How dedication section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="dedication.tocdepth">0</xsl:param>
```

**Description**

Same than [preface.tocdepth](#) for dedication sections.

**preface.tocdepth**

[preface.tocdepth](#) — How preface section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="preface.tocdepth">0</xsl:param>
```

**Description**

When greater than 0, the preface headings appear in the TOC. The parameter value define the preface section depth appearing in the TOC and in the bookmarks. If set to 0, none of the sections are put in the TOC. If set to 1, only the chapter level appears in the TOC and bookmarks, and so on. When the parameter is negative, it behaves like with 0, but it uses the previous implementation (use of unnumbered sections, that is, with latex heading commands ending with '\*').

**glossary.tocdepth**

[glossary.tocdepth](#) — How glossary section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="glossary.tocdepth">5</xsl:param>
```

**Description**

Same than [preface.tocdepth](#) for glossary sections. Meaningful only when [glossary.numbered](#) is set to 0.

---

**See Also**

[glossary.numbered](#).

[refentry.numbered](#), [refentry.tocdepth](#).

[bibliography.numbered](#), [bibliography.tocdepth](#).

[index.numbered](#), [index.tocdepth](#).

**index.tocdepth**

[index.tocdepth](#) — How index section and subsections appear in TOC

**Synopsis**

```
<xsl:param name="index.tocdepth">5</xsl:param>
```

**Description**

Same than [preface.tocdepth](#) for index sections. Meaningful only when [index.numbered](#) is set to 0.

**See Also**

[index.numbered](#).

[refentry.numbered](#), [refentry.tocdepth](#).

[bibliography.numbered](#), [bibliography.tocdepth](#).

[glossary.numbered](#), [glossary.tocdepth](#).

**latex.index.tool**

[latex.index.tool](#) — Define the tool to use to build an index

**Synopsis**

```
<xsl:param name="latex.index.tool"/>
```

**Description**

This parameter defines the LaTeX compatible index tool to use to build the document index. When empty the default tool used is **makeindex**. Currently **xindy** is the only other tool supported by dblatex. Read Section [4.11](#) for more information about index building.

**See Also**

[latex.index.language](#).

---

## latex.index.language

*latex.index.language* — Force the language to use for index sorting

### Synopsis

```
<xsl:param name="latex.index.language"/>
```

### Description

This parameter forces the use of the specified index language whatever the document language is. The index language is used by some index tools like **xindy** that builds and sorts the index list. Read Section 4.11 for more information about index building.

### See Also

*latex.index.tool*.

## refentry.tocdepth

*refentry.tocdepth* — How refentry section and subsections appear in TOC

### Synopsis

```
<xsl:param name="refentry.tocdepth">5</xsl:param>
```

### Description

Same than *preface.tocdepth* for refentry sections. Meaningful only when *refentry.numbered* is set to 0.

## A.4 Processor Extensions

### alt.use

*alt.use* — Always use alt to display equations

### Synopsis

```
<xsl:param name="alt.use" select="0"/>
```

### Description

When an (informal) equation contains both alt and another element (graphic, etc.), and when *tex.math.in.alt* is not set to 'latex', the alt element is not used to display the equation since it is considered as a fallback element. Set *alt.use* to force the use of alt as default rendering element even when *tex.math.in.alt* is not set to 'latex'.

---

## tex.math.in.alt

*tex.math.in.alt* — TeX notation used for equations

### Synopsis

```
<xsl:param name="tex.math.in.alt" select="'latex'"/>
```

### Description

Specifies if the `alt` element in an (informal) equation contains some tex equation. If so, and if the tex equation is in 'latex' format, the content is directly used by dblatex.

## A.5 Automatic labelling

### bibliography.numbered

*bibliography.numbered* — Should bibliography headings be numbered?

### Synopsis

```
<xsl:param name="bibliography.numbered">1</xsl:param>
```

### Description

Defines either the bibliography titles are numbered or not. When numbered, it is displayed as any other numbered section.

### See Also

*bibliography.tocdepth.*

*glossary.numbered*, *glossary.tocdepth.*

*refentry.numbered*, *refentry.tocdepth.*

*index.numbered*, *index.tocdepth.*

### glossary.numbered

*glossary.numbered* — Should glossary headings be numbered?

### Synopsis

```
<xsl:param name="glossary.numbered">1</xsl:param>
```

---

**Description**

Defines either the glossary titles are numbered or not. When numbered, it is displayed as any other numbered section.

**See Also**

[\*glossary.tocdepth\*](#).

[\*refentry.numbered\*](#), [\*refentry.tocdepth\*](#).

[\*bibliography.numbered\*](#), [\*bibliography.tocdepth\*](#).

[\*index.numbered\*](#), [\*index.tocdepth\*](#).

**index.numbered**

[\*index.numbered\*](#) — Should index headings be numbered?

**Synopsis**

```
<xsl:param name="index.numbered">1</xsl:param>
```

**Description**

Defines either the index titles are numbered or not. When numbered, it is displayed as any other numbered section.

**See Also**

[\*index.tocdepth\*](#).

[\*refentry.numbered\*](#), [\*refentry.tocdepth\*](#).

[\*bibliography.numbered\*](#), [\*bibliography.tocdepth\*](#).

[\*glossary.numbered\*](#), [\*glossary.tocdepth\*](#).

**refentry.numbered**

[\*refentry.numbered\*](#) — Should refentry headings be numbered?

**Synopsis**

```
<xsl:param name="refentry.numbered">1</xsl:param>
```

**Description**

Defines either the refentry titles are numbered or not. When numbered, it is displayed as any other numbered section.

---

**See Also**

[refentry.tocdepth](#).

[glossary.numbered](#), [glossary.tocdepth](#).

[bibliography.numbered](#), [bibliography.tocdepth](#).

[index.numbered](#), [index.tocdepth](#).

## A.6 Meta/\*Info

**doc.pdfcreator.show**

[doc.pdfcreator.show](#) — Set the PDF metadata Creator field

**Synopsis**

```
<xsl:param name="doc.pdfcreator.show">1</xsl:param>
```

**Description**

Fill the Creator field of the PDF document information section with "DBLaTeX-<version>" if the parameter is set to 1. Set to 0 this field is keep untouched.

**make.single.year.ranges**

[make.single.year.ranges](#) — Print single-year ranges (e.g., 1998-1999)

**Synopsis**

```
<xsl:param name="make.single.year.ranges" select="0"/>
```

**Description**

If non-zero, year ranges that span a single year will be printed in range notation (1998-1999) instead of discrete notation (1998, 1999). Parameter taken from the DocBook XSL stylesheets.

**make.year.ranges**

[make.year.ranges](#) — Collate copyright years into ranges?

**Synopsis**

```
<xsl:param name="make.year.ranges" select="0"/>
```

**Description**

If non-zero, copyright years will be collated into ranges. Parameter taken from the DocBook XSL stylesheets.

---

## A.7 Reference Pages

### funcsynopsis.decoration

*funcsynopsis.decoration* — Decorate elements of a *funcsynopsis*?

#### Synopsis

```
<xsl:param name="funcsynopsis.decoration" select="1"/>
```

#### Description

If non-zero, elements of the *funcsynopsis* will be decorated (e.g. rendered as bold or italic text). The decoration is controlled by templates that can be redefined in a customization layer.

This parameter is taken from the DocBook Project XSL parameters.

### funcsynopsis.style

*funcsynopsis.style* — What style of *funcsynopsis* should be generated?

#### Synopsis

```
<xsl:param name="funcsynopsis.style">ansi</xsl:param>
```

#### Description

If *funcsynopsis.style* is *ansi*, ANSI-style function synopses are generated for a *funcsynopsis*, otherwise K&R-style function synopses are generated.

This parameter is taken from the DocBook Project XSL parameters.

### function.parens

*function.parens* — Generate parens after a function?

#### Synopsis

```
<xsl:param name="function.parens">0</xsl:param>
```

#### Description

If non-zero, the formatting of a *function* element will include generated parentheses.

This parameter is taken from the DocBook Project XSL parameters.

### refclass.suppress

*refclass.suppress* — Suppress display of *refclass* contents?

**Synopsis**

```
<xsl:param name="refclass.suppress" select="0"/>
```

**Description**

Parameter taken from the DocBook Project.

See [refclass.suppress](#).

**refentry.generate.name**

*refentry.generate.name* — Output NAME header before refnames?

**Synopsis**

```
<xsl:param name="refentry.generate.name" select="0"/>
```

**Description**

If non-zero, a "NAME" section title is output before the list of refnames.

**refentry.xref.manvolnum**

*refentry.xref.manvolnum* — Output manvolnum as part of refentry cross-reference?

**Synopsis**

```
<xsl:param name="refentry.xref.manvolnum" select="'1'"/>
```

**Description**

if non-zero, the manvolnum is used when cross-referencing refentrys, either with xref or citerefentry.

## A.8 Tables

**newtbl.autowidth**

*newtbl.autowidth* — Table column widths sized by latex

**Synopsis**

```
<xsl:param name="newtbl.autowidth"/>
```



**Description**

Defines if the table column widths must be automatically sized by latex. The allowed values are:

**default**

The automatic width (that is, latex is in charge to size the column width) is applied only to columns not having a specified `colspec colwidth`. It includes both undefined `colspec`, and `colspec` without the `colwidth` attribute.

**all**

the automatic width is applied to any column, whether a `colspec` is provided or not.

The default value is empty. This is the same as `none`.

The values `all` and `default` have identical effect in the tabular presentation of `segmentedlists`. (`segmentedlist` elements have no `colwidth` attribute.)

**See Also**

- Section [4.7.7.1](#)
- Section [4.7.7](#)
- [default.table.width](#)

**newtbl.bgcolor.thead**

[newtbl.bgcolor.thead](#) — Background color of the `thead` rows

**Synopsis**

```
<xsl:param name="newtbl.bgcolor.thead"/>
```

**Description**

Background color of the `thead` rows.

**newtbl.default.colsep**

[newtbl.default.colsep](#) — By default draw a vertical line between columns

**Synopsis**

```
<xsl:param name="newtbl.default.colsep" select="'1'"/>
```

**Description**

Set to 1, print the column separators when no `colspec` attribute is specified.

## newtbl.default.rowsep

*newtbl.default.rowsep* — By default draw a horizontal line between rows

### Synopsis

```
<xsl:param name="newtbl.default.rowsep" select="'1'"/>
```

### Description

Set to 1, print the row separators when no `rowspec` attribute is specified.

## newtbl.format.tbody

*newtbl.format.tbody* — LaTeX formatting for body table cells

### Synopsis

```
<xsl:param name="newtbl.format.tbody"/>
```

### Description

LaTeX formatting for body table cells.

## newtbl.format.tfoot

*newtbl.format.tfoot* — LaTeX formatting for foot table cells

### Synopsis

```
<xsl:param name="newtbl.format.tfoot"/>
```

### Description

LaTeX formatting for foot table cells.

## newtbl.format.thead

*newtbl.format.thead* — LaTeX formatting for head table cells

### Synopsis

```
<xsl:param name="newtbl.format.thead">\bfseries%  
</xsl:param>
```

**Description**

LaTeX formatting for head table cells.

**newtbl.use.hhline**

*newtbl.use.hhline* — Draw the horizontal lines with the `hhline` package

**Synopsis**

```
<xsl:param name="newtbl.use.hhline" select="'0'"/>
```

**Description**

Set to 1, use the `hhline` package to draw the table row separators instead of `cline`. Using `hhline` seems more suited for colored tables.

**table.continue.caption**

*table.continue.caption* — Caption text for continued table titles

**Synopsis**

```
<xsl:param name="table.continue.caption" select="'(continued)'/>
```

**Description**

Text to display in the second (and following) captions of long tables expanding over more than one page. The default parameter value is `'(continued)'` (including the parentheses).

**table.default.position**

*table.default.position* — Default table float placement policy

**Synopsis**

```
<xsl:param name="table.default.position" select="'[htbp]'/>
```

**Description**

Default table float placement algorithm to apply. The default parameter value is `[htbp]` meaning that latex tries to place the table where it occurs first (h, here), then at the top of the page (t), at the bottom of the page (b), and finally on the next page (p).

**table.default.tabstyle**

*table.default.tabstyle* — Default table style to apply

**Synopsis**

```
<xsl:param name="table.default.tabstyle"/>
```

**Description**

The parameter applies only for `informaltables` that do not have a `tabstyle` attribute. With `dblatex` its role is to specify the latex table environment to use, so the set value must be a valid latex environment. The supported values are:

**longtable**

The default table type used by `dblatex`, in order to be able to split over several pages. When the parameter is empty and no `tabstyle` attribute is defined, it is the applied value.

**tabular**

The most usual table type. Such table can only be on a single page.

**tabularx**

An advanced table type that allows to stretch column widths to the available remained page width. Such table can only be on a single page.

**table.in.float**

*table.in.float* — Use or emulate a float to display a formal table?

**Synopsis**

```
<xsl:param name="table.in.float" select="'1'"/>
```

**Description**

Set to 0 the formal tables are no more put in table floats. They are displayed with the `longtable` package, allowing to have formal tables covering several pages (which is not possible with floats). The limitation is that the title must necessarily be on the top of the table.

**table.title.top**

*table.title.top* — Title on top of the `table` float

**Synopsis**

```
<xsl:param name="table.title.top" select="'0'"/>
```

**Description**

Set to 1 the `table` float title position is above the table. Set to 0 the title is under the table. Meaningless when the table is not in a float (see *table.in.float*).

---

## default.table.rules

*default.table.rules* — The default column and row rules for tables using HTML markup

### Synopsis

```
<xsl:param name="default.table.rules">none</xsl:param>
```

### Description

Tables using HTML markup elements can use an attribute named `rules` on the `table` or `informaltable` element to specify whether column and row border rules should be displayed. This parameter lets you specify a global default style for all HTML tables that don't otherwise have that attribute.

These are the supported values:

#### **all**

Rules will appear between all rows and columns.

#### **rows**

Rules will appear between rows only.

#### **cols**

Rules will appear between columns only.

#### **groups**

Rules will appear between row groups (thead, tfoot, tbody). No support for rules between column groups yet.

#### **none**

No rules. This is the default value.

The border after the last row and the border after the last column are not affected by this setting. Those borders are controlled by the `frame` attribute on the `table` element.

## default.table.width

*default.table.width* — The default width of tables

### Synopsis

```
<xsl:param name="default.table.width"/>
```

### Description

If non-empty, this value controls table width. It is used for the `width` attribute on tables that do not specify an alternate width (with the `<?dblatex table-width?>` processing instruction, or with the *newtbl.autowidth* parameter).

The parameter takes one of the following values:

- A valid length (e.g. 15cm),
  - A percentage of the page width (e.g. 75%),
  - A keyword telling to apply an automatic column width (e.g. autowidth.all).
-

**See Also**

- Section [4.7.2](#)
- Section [4.7.7](#)
- [newtbl.autowidth](#)

## A.9 Linking

**latex.hyperparam**

*latex.hyperparam* — Options/parameters passed to hyperref

**Synopsis**

```
<xsl:param name="latex.hyperparam"/>
```

**Description**

This parameter gives the options to pass to the LaTeX hyperref package. No validity check is done.

For instance, the Table of Content rendering (link color, etc.) can be changed. Look at the hyperref.sty documentation to know all the hyperref options available.

**Example A.1** Configuring with latex.hyperparam

```
<?xml version='1.0' encoding="iso-8859-1"?>
<xsl:stylesheet xmlns:xsl="http://www.w3.org/1999/XSL/Transform" version='1.0'>

<!-- We want TOC links in the titles (not in the page numbers), and blue.
-->
<xsl:param name="latex.hyperparam">colorlinks,linkcolor=blue</xsl:param>

</xsl:stylesheet>
```

**Olink Parameters**

*current.docid*, *insert.olink.page.number*, *insert.olink.pdf.frag*, *olink.base.uri*, *olink.debug*, *olink.doctitle*, *olink.lang.fallback.sequence*, *prefer.internal.olink*, *target.database.document*, *targets.filename*, *use.local.olink.style* — Parameters to configure Olinks

**Synopsis**

```
<xsl:param name="current.docid"/>

<xsl:param name="insert.olink.page.number">yes</xsl:param>

<xsl:param name="insert.olink.pdf.frag" select="1"/>

<xsl:param name="olink.base.uri" select="''"/>
```

```
<xsl:param name="olink.debug" select="0"/>
<xsl:param name="olink.doctype" select="'yes'"/>
<xsl:param name="olink.lang.fallback.sequence" select="''"/>
<xsl:param name="prefer.internal.olink" select="0"/>
<xsl:param name="target.database.document" select="''"/>
<xsl:param name="targets.filename" select="'target.db'"/>
<xsl:param name="use.local.olink.style" select="0"/>
```

## Description

These parameters are taken from the DocBook Project XSL parameters and must be used as described in the original reference:

- [current.docid](#),
- [insert.olink.page.number](#),
- [insert.olink.pdf.frag](#),
- [olink.base.uri](#),
- [olink.debug](#),
- [olink.doctype](#),
- [olink.lang.fallback.sequence](#),
- [prefer.internal.olink](#),
- [target.database.document](#),
- [targets.filename](#),
- [use.local.olink.style](#),

## A.10 Cross References

### **insert.xref.page.number**

[insert.xref.page.number](#) — Turns page numbers in xrefs on and off

#### **Synopsis**

```
<xsl:param name="insert.xref.page.number">no</xsl:param>
```

**Description**

The value of this parameter determines if cross references (`xrefs`) in printed output will include page number citations. It has three possible values.

**no**

No page number references will be generated.

**yes**

Page number references will be generated for all `xref` elements. The style of page reference may be changed if an `xrefstyle` attribute is used.

**maybe**

Page number references will not be generated for an `xref` element unless it has an `xrefstyle` attribute whose value specifies a page reference.

**xref.hypermarkup**

*xref.hypermarkup* — Wrap the entire the `xref` markups with an hyperlink?

**Synopsis**

```
<xsl:param name="xref.hypermarkup" select="0"/>
```

**Description**

When set to 1, the whole cross reference markup produced for an `xref` is converted to an hyperlink.

When not set, the default latex hyperlinking is done, that usually means that only the reference numbers are hot.

**A.11 Lists****term.breakline**

*term.breakline* — Put the term description on the next line?

**Synopsis**

```
<xsl:param name="term.breakline">0</xsl:param>
```

**Description**

Set to 1 the item following a term in a variable list is put on the next line.

**variablelist.term.separator**

*variablelist.term.separator* — Text to separate terms within a multi-term varlistentry



**Synopsis**

```
<xsl:param name="variablelist.term.separator">, </xsl:param>
```

**Description**

When a `varlistentry` contains multiple `term` elements, the string specified in the value of the `variablelist.term.separator` parameter is placed after each `term` except the last.

**A.12 QAndASet****qanda.defaultlabel**

`qanda.defaultlabel` — Sets the default for defaultlabel on QandASet.

**Synopsis**

```
<xsl:param name="qanda.defaultlabel">number</xsl:param>
```

**Description**

If no `defaultlabel` attribute is specified on a `qandaset`, this value is used. It must be one of the legal values for the `defaultlabel` attribute, one from `none`, `number` or `qanda`. The default value is 'number'.

**Meaning**

`qanda` - questions are labeled "Q:" and answers are labeled "A:".

`number` - The entries are enumerated.

`none` - No distinguishing label precedes Questions or Answers.

**A.13 Bibliography****biblioentry.item.separator**

`biblioentry.item.separator` — Text to separate bibliography entries

**Synopsis**

```
<xsl:param name="biblioentry.item.separator">, </xsl:param>
```

**Description**

Text to separate bibliography entries.

**biblioentry.numbered**

`biblioentry.numbered` — Should `biblioentry` item labels be numbered?

## Synopsis

```
<xsl:param name="biblioentry.numbered" select="0"/>
```

## Description

When non-zero, the reference labels of the bibliography entries are numbers instead of label strings, even if explicit labels are set through an `xreflabel` attribute or an `abbrev` tag.

## **citation.default.style**

*citation.default.style* — Default natbib citation style to apply

## Synopsis

```
<xsl:param name="citation.default.style"/>
```

## Description

Default natbib citation style to apply when natbib is used.

## See Also

- Section [4.12.3](#)
- [dblatex citestyle](#)

## **citation.natbib.options**

*citation.natbib.options* — Specifies the natbib package options

## Synopsis

```
<xsl:param name="citation.natbib.options"/>
```

## Description

Options to pass to the natbib package when it is loaded. See also Section [4.12.3](#).

## **citation.natbib.use**

*citation.natbib.use* — Use natbib to display citations

## Synopsis

```
<xsl:param name="citation.natbib.use" select="'0'"/>
```

---

### Description

Load the natbib package, and allows the use of natbib citation styles. The package is loaded if the parameter is set to 1. See Section [4.12.3](#).

### latex.bibfiles

*latex.bibfiles* — Defines the default BibTeX database to use

### Synopsis

```
<xsl:param name="latex.bibfiles">'</xsl:param>
```

### Description

Defines the default BibTeX database to use. Used when the bibtex PI does not have a "bibfiles" attribute. See Section [4.12.2](#) for more details.

### latex.biblio.output

*latex.biblio.output* — Defines how the BibTeX bibliographic entries are printed out

### Synopsis

```
<xsl:param name="latex.biblio.output">all</xsl:param>
```

### Description

The available print mode values are:

#### all

Print all the entries contained in the databases.

#### cited

Print only the entries cited in the document.

#### notcited

Print only the entries *not* cited in the document.

The default print mode is 'all'.

### See Also

- Section [4.12.2](#)
- [bibtex](#)

### latex.biblio.style

*latex.biblio.style* — Default BibTeX style to apply

---

**Synopsis**

```
<xsl:param name="latex.biblio.style"/>
```

**Description**

Defines the default BibTeX style to apply. Meaningful when not empty, only for the used bibtex databases.

**See Also**

- Section [4.12.2](#)
- [bibtex](#)

**latex.bibwidelabel**

[latex.bibwidelabel](#) — Template of the widest bibliography label

**Synopsis**

```
<xsl:param name="latex.bibwidelabel">WIDELABEL</xsl:param>
```

**Description**

The environment bibliography accepts a parameter that indicates the widest label, which is used to correctly format the bibliography output. The value of this parameter is output inside the `\begin{thebibliography}[]` LaTeX command.

## A.14 Glossary

**glossterm.auto.link**

[glossterm.auto.link](#) — Generate links from glossterm to glossentry automatically?

**Synopsis**

```
<xsl:param name="glossterm.auto.link" select="0"/>
```

**Description**

When set to 1, the glossterms in the document are linked to their definition in the glossary.

## A.15 Miscellaneous

**annotation.support**

[annotation.support](#) — Enable the annotation support

### Synopsis

```
<xsl:param name="annotation.support" select="'0'"/>
```

### Description

Set to 1 the experimental DocBook 5 `annotation support` is enabled.

### **beginpage.as.pagebreak**

*beginpage.as.pagebreak* — Force a page break when set to 1. Otherwise `beginpage` does nothing.

### Synopsis

```
<xsl:param name="beginpage.as.pagebreak" select="1"/>
```

### Description

The legacy behaviour of `dblatex` is that it inserts a page break when `beginpage` appears. You can keep this behaviour by setting this parameter to 1 (default value) or inhibit it by setting to 0.

### **doc.section.depth**

*doc.section.depth* — Depth of the section numbering

### Synopsis

```
<xsl:param name="doc.section.depth">5</xsl:param>
```

### Description

Depth of the section numbering. Used to set the latex `secnumdepth` counter.

### **endnotes.heading.command**

*endnotes.heading.command* — LaTeX command of the endnotes headings

### Synopsis

```
<xsl:param name="endnotes.heading.command"/>
```

### Description

With this parameter you can provide your own latex macro to make the endnotes headings. If not set, **dblatex** uses the default sectioning commands like `\section*`, `\subsection*`, and so on. The command takes one parameter that is the title markup of the heading. For more details see Section 4.16.2.4.

---

**See Also**

[\*endnotes.heading.groups\*](#)

[\*endnotes.heading.command\*](#)

**endnotes.heading.groups**

[\*endnotes.heading.groups\*](#) — Display the endnotes by groups

**Synopsis**

```
<xsl:param name="endnotes.heading.groups"/>
```

**Description**

In the endnote section, the notes are grouped according to the level defined by the elements listed in this parameter. Each group has a heading that references the element that contains these notes. By default, dblatex can group per chapter or per part. For more details see Section 4.16.2.4.

**See Also**

[\*endnotes.heading.style\*](#)

[\*endnotes.heading.command\*](#)

**endnotes.heading.style**

[\*endnotes.heading.style\*](#) — Style of the heading of endnotes groups

**Synopsis**

```
<xsl:param name="endnotes.heading.style" select="'select:title'"/>
```

**Description**

This parameter is provided to format the heading of an endnote group. It uses the `xrefstyle` syntax, and therefore one can specify directly a template, or select some keywords to substitute. For more details see Section 4.16.2.4.

**See Also**

[\*endnotes.heading.groups\*](#)

[\*endnotes.heading.command\*](#)

**endnotes.properties**

[\*endnotes.properties\*](#) — Properties of the latex package `endnotes` setup

---

**Synopsis**

```
<xsl:attribute-set name="endnotes.properties.default">
  <xsl:attribute name="package">endnotes</xsl:attribute>

  <!-- No header: endnotes are embedded in another section -->
  <xsl:attribute name="heading">\mbox{}\par</xsl:attribute>

  <!-- Show end notes as a numbered list -->
  <xsl:attribute name="font-size">\normalsize</xsl:attribute>
  <xsl:attribute name="note-format">%
    \leftskip=1.8em\noindent
    \makebox[0pt][r]{\theenmark.~~\rule{0pt}{\baselineskip}}\ignorespaces
  </xsl:attribute>
</xsl:attribute-set>

<xsl:attribute-set name="endnotes.properties"
  use-attribute-sets="endnotes.properties.default"/>
```

**Description**

These properties are used to configure the `endnotes` package when the footnotes are printed as endnotes. Each attribute defines the content of the setup macros of the package. The user should always override the attributes of `endnotes.properties` and leave `endnotes.properties.default` untouched. See Section 4.16.2 for more details.

**See Also**

[\*footnote.as.endnote\*](#)

**equation.default.position**

[\*equation.default.position\*](#) — Default equation float placement to apply

**Synopsis**

```
<xsl:param name="equation.default.position">[H]</xsl:param>
```

**Description**

Default equation float placement algorithm to apply. See `figure.default.position` for more details about how to use latex float specifications.

**example.default.position**

[\*example.default.position\*](#) — Default example float placement to apply

**Synopsis**

```
<xsl:param name="example.default.position">[H]</xsl:param>
```

**Description**

Default example float placement algorithm to apply. See `figure.default.position` for more details about how to use latex float specifications.

**example.float.type**

`example.float.type` — Select the type of float for example elements

**Synopsis**

```
<xsl:param name="example.float.type">none</xsl:param>
```

**Description**

Selects the type of float for example elements.

- If `example.float.type` is “none”, then no float is used. It may be usefull when the example must be displayed exactly where it is defined or when it must cover several pages.
- If `example.float.type` is "float", then the float environment is used. The actual float placement is computed by latex according to the `floatstyle` attribute if specified, or according to the `example.default.position` parameter.

**See Also**

`example.default.position`.

`figure.default.position`.

**figure.anchor.top**

`figure.anchor.top` — Cross reference anchor on top of the figure float

**Synopsis**

```
<xsl:param name="figure.anchor.top" select="$figure.title.top"/>
```

**Description**

By default the anchor of a formal figure is where the figure title appears. It means that a link to the figure points after the image when the title is below the image, and at the top of the image when the title is on the top. This parameter allows to put the anchor at the top of the image even if the title is below the figure.

Note that it is not possible to have the anchor below the image if the title is on the top.

**See Also**

`figure.title.top`



## figure.default.position

*figure.default.position* — Figure float placement policy

### Synopsis

```
<xsl:param name="figure.default.position">[htbp]</xsl:param>
```

### Description

Default figure float placement algorithm to apply. The default parameter value is [htbp] meaning that latex tries to place the figure where it occurs first (h, here), then at the top of the page (t), at the bottom of the page (b), and finally on the next page (p).

## figure.title.top

*figure.title.top* — Title on top of the figure float

### Synopsis

```
<xsl:param name="figure.title.top">0</xsl:param>
```

### Description

Set to 1 the *figure* float title position is above the image. Set to 0 the title is under the image.

## filename.as.url

*filename.as.url* — Hyphenate a filename like if it was an URL

### Synopsis

```
<xsl:param name="filename.as.url">1</xsl:param>
```

### Description

Set to 1 the *filenames* are handled as URLs, with the same hyphenation rules. Set to 0 the *filename* hyphenation is forced for each character.

## footnote.as.endnote

*footnote.as.endnote* — Use footnotes as endnotes

### Synopsis

```
<xsl:param name="footnote.as.endnote" select="0"/>
```

---

**Description**

When set to 1, the footnotes are displayed as endnotes, that is, all the notes appear in a section at the end of the document. See Section 4.16.2 for more details.

**See Also**

[\*endnotes.properties\*](#)

**hyphenation.format**

[\*hyphenation.format\*](#) — Predefined formats to hyphenate

**Synopsis**

```
<xsl:param name="hyphenation.format">monoseq,sansseq</xsl:param>
```

**Description**

This parameter replaces the parameter [\*monoseq.hyphenation\*](#) and its role is more general. It contains a comma separated list of the predefined inline formats that must be aggressively hyphenated. It means that all the elements rendered with these formats are then hyphenated.

The predefined formats that can be hyphenated when contained in the list are:

**monoseq**

Monospaced font.

**sansseq**

Sans serif like font.

**boldmonoseq**

Bold monospaced font.

**italicmonoseq**

Italic monospaced font.

If one wants no hyphenation at all, he must set the parameter to "nohyphen". In this case dlatex tries to avoid overfull boxes (words in the margins) but keeps the words splittable only on their natural hyphenation points which can end up to no hyphenation at all for literal words like URLs or technical terms.

**See Also**

[\*monoseq.hyphenation\*](#)

**linenumbering.scope**

[\*linenumbering.scope\*](#) — Templates on which the global linenumbering setup applies

**Synopsis**

```
<xsl:param name="linenumbering.scope"/>
```

### Description

List of the templates for which the `linenumbering.default` parameter applies. The list separator is a space. For example, when the parameter is set to "screen programlisting", the two other linenumbering parameters will have effects only on `screen` and `programlisting` templates.

### See Also

`linenumbering.default`, `linenumbering.everyNth`.

## linenumbering.default

`linenumbering.default` — Default linenumbering setup for literal environments

### Synopsis

```
<xsl:param name="linenumbering.default"/>
```

### Description

This parameter defines the default linenumbering setup to apply to the templates listed in `linenumbering.scope` that do not have a `linenumbering` attribute.

The parameter value must be consistent and therefore compliant to the values allowed for the `linenumbering` attribute.

### See Also

`linenumbering.scope`, `linenumbering.everyNth`.

## linenumbering.everyNth

`linenumbering.everyNth` — Indicate which lines should be numbered

### Synopsis

```
<xsl:param name="linenumbering.everyNth"/>
```

### Description

If line numbering is enabled, everyNth line will be numbered. Note that numbering is one based, not zero based.

## literal.layout.options

`literal.layout.options` — Override the options passed to the `listing` package

### Synopsis

```
<xsl:param name="literal.layout.options"/>
```

---

**Description**

Overwrite the default options passed to the `\lstset` command.

**literal.lines.showall**

*literal.lines.showall* — Show the last empty lines in the literal environments?

**Synopsis**

```
<xsl:param name="literal.lines.showall">1</xsl:param>
```

**Description**

Set to 1, all the lines in a verbatim environment like `programlisting` or `screen` are printed, even if they are empty. Set to 0, the last empty lines are not printed. It is set to 1 by default.

**literal.width.ignore**

*literal.width.ignore* — Ignore the literal environment width attribute

**Synopsis**

```
<xsl:param name="literal.width.ignore">0</xsl:param>
```

**Description**

When set to 1 the `programlisting` and `screen` width attribute is ignored. In this case all the verbatim environment widths are equal to the enclosing environment width.

**literal.class**

*literal.class* — Default class to apply to `literallayout` blocks

**Synopsis**

```
<xsl:param name="literal.class">monospaced</xsl:param>
```

**Description**

Default class to apply when no `class` attribute is set, to render `literallayout` environments.

**literal.role**

*literal.role* — Default role to apply to verbatim blocks

---

## Synopsis

```
<xsl:param name="literal.role"/>
```

## Description

When not empty and when no `role` attribute is specified for a block verbatim block to render, this parameter is applied as formatting role.

The allowed values are specified in Section 4.10.1. If the value is not one of the allowed value, the role is then ignored.

## literal.environment

*literal.environment* — Latex environment used to format verbatim blocks

## Synopsis

```
<xsl:param name="literal.environment">
<xsl:choose>
<xsl:when test="contains($literal.extensions,'scale')">
  <xsl:text>lstcode</xsl:text>
</xsl:when>
<xsl:otherwise>
  <xsl:text>lstlisting</xsl:text>
</xsl:otherwise>
</xsl:choose>
</xsl:param>
```

## Description

It specifies the Latex environment to use to render a verbatim block.

Since **dblatex** uses the listings package capabilities to handle the DocBook attributes, the specified environment must have the same capabilities if written from scratch, but it is recommended to just extend the listings environment with you own listings extension. See Section 4.10.4 for more details.

The specified environment name must starts with "lst". Otherwise **dblatex** raises an error and exits.

## See Also

*literal.extensions*.

## literal.extensions

*literal.extensions* — Enable extended verbatim features

## Synopsis

```
<xsl:param name="literal.extensions">0</xsl:param>
```

### Description

When this parameter is empty, **dblatex** only uses options supported by the listings package, in order to ensure that any verbatim environment built upon this standard package will work.

When this parameter contains "scale", **dblatex** uses additional options handled only by the dblatex version of the verbatim environment to provide scaling capabilities (see Section 4.10.2).

### See Also

[literal.environment](#).

## mediaobject.caption.style

[mediaobject.caption.style](#) — Font style of the mediaobject caption text

### Synopsis

```
<xsl:param name="mediaobject.caption.style">\slshape</xsl:param>
```

### Description

Font style of the mediaobject caption text. Its value can be any valid latex font style command combinations. By default this parameter put the caption text to italics.

## monoseq.hyphenation

[monoseq.hyphenation](#) — Specifies one of the supported monoseq hyphenation policy

### Synopsis

```
<xsl:param name="monoseq.hyphenation">1</xsl:param>
```

### Description

This parameter is obsoleted in version 0.3.4 and has no more effect. It has been replaced by the [hyphenation.format](#).

Its role was: when set to 1, aggressively hyphenates the inlined element rendered with monoseq fonts. When set to 0, let latex do as default. When set to 'nohyphen', dblatex tries to avoid overfull boxes (words in the margins) but keeps the monoseq words not splittable.

### See Also

[hyphenation.format](#)

## monoseq.small

[monoseq.small](#) — Use a smaller font to render monoseq portions of text

---

## Synopsis

```
<xsl:param name="monoseq.small">0</xsl:param>
```

## Description

When set to 1, choose a smaller font to the element rendered with monoseq fonts.

### Tip

If you use the XeTeX backend you do not need to use this parameter. Instead, you can configure the monospaced font used with a scale option as follow, through the parameter *xetex.font* or via a user latex style:

```
\setmonofont[Scale=MatchLowercase]{DejaVu Sans Mono}
```

## pdf.annot.options

*pdf.annot.options* — PDF text annotations rendering options

## Synopsis

```
<xsl:param name="pdf.annot.options"/>
```

## Description

Options to change how the PDF text annotations should look. The supported options are width, height, depth. The options must be comma separated like: width=5cm, depth=10cm.

## segmentedlist.as.table

*segmentedlist.as.table* — Format segmented lists as tables?

## Synopsis

```
<xsl:param name="segmentedlist.as.table" select="0"/>
```

## Description

If non-zero, segmentedlists will be formatted as tables. If you want a local setup for a specific segmentedlist you can use the list-presentation Processing Instruction instead.

When formatted as table, some table Processing Instructions can be used to customize the rendering.

**See Also**

- [dblatex list-presentation](#)
- Inline presentation:
  - [seg.item.separator](#)
- Table presentation:
  - Section [4.7.2](#)
  - [newtbl.autowidth](#)
  - [default.table.width](#)
  - [dblatex colwidth](#)
  - [dblatex autowidth](#)
  - [dblatex table-width](#)

**seg.item.separator**

*seg.item.separator* — Separator to use between several segs

**Synopsis**

```
<xsl:param name="seg.item.separator">, </xsl:param>
```

**Description**

Defines the separator to use between several segs.

**show.comments**

*show.comments* — Display remark elements?

**Synopsis**

```
<xsl:param name="show.comments" select="1"/>
```

**Description**

If non-zero, comments will be displayed, otherwise they are suppressed. Comments here refers to the `remark` element (which was called `comment` prior to DocBook 4.0), not XML comments (`<--` like this `-->`) which are unavailable.

**Note**

Dblatex uses the PDF Text Annotations capabilities to handle comments and remarks.

**texlive.version**

*texlive.version* — Version of the installed Tex Live Distribution



## Synopsis

```
<xsl:param name="texlive.version">2007-10</xsl:param>
```

## Description

The version number is used to adapt the tex output. For instance the URL output depends on the url package behaviour that differs from one release to another.

## ulink.footnotes

*ulink.footnotes* — Generate footnotes for ulinks?

## Synopsis

```
<xsl:param name="ulink.footnotes" select="0"/>
```

## Description

If non-zero, and if *ulink.show* also is non-zero, the URL of each ulink will appear as a footnote.

---

### Dblatex Limitation

The URL cannot be shown in a footnote if the ulinks are in list terms or heading titles.

---

## ulink.show

*ulink.show* — Display URLs after ulinks?

## Synopsis

```
<xsl:param name="ulink.show" select="0"/>
```

## Description

If non-zero, the URL of each ulink will appear after the text of the link. If the text of the link and the URL are identical, the URL is suppressed.

See also *ulink.footnotes*.

The global *ulink.show* and *ulink.footnotes* setting can be overridden for each ulink that uses an xrefstyle like the following examples:

```
<!-- show 'Hot Text [URL]' or 'Hot Text (foot)' even if $ulink.show=0 -->
<ulink xrefstyle="url.show" url="http://www.a.site.org/path">Hot Text</ulink>

<!-- show 'Hot Text' even if $ulink.show=1 -->
<ulink xrefstyle="url.hide" url="http://us3.a.site.org/path">Hot Text</ulink>

<!-- show 'Hot Text [URL]' even if $ulink.show=0 and $ulink.footnotes=1 -->
<ulink xrefstyle="url.show.after" url="http://www.a.site.org/path">Hot Text</ulink>
```

---

```
<!-- show 'Hot Text (foot)' even if $ulink.show=0 and $ulink.footnotes=0 -->
<ulink xrefstyle="url.show.infofoot" url="http://www.a.site.org/path">Hot Text</ulink>

<!-- show 'Hot Text (foot)' if $ulink.show=1 and even if $ulink.footnotes=0 -->
<ulink xrefstyle="url.infofoot" url="http://www.a.site.org/path">Hot Text</ulink>

<!-- show 'Hot Text [URL]' if $ulink.show=1 and even if $ulink.footnotes=1 -->
<ulink xrefstyle="url.after" url="http://www.a.site.org/path">Hot Text</ulink>
```

### xref.with.number.and.title

*xref.with.number.and.title* — Use number and title in cross references

#### Synopsis

```
<xsl:param name="xref.with.number.and.title" select="0"/>
```

#### Description

A cross reference may include the number (for example, the number of an example or figure) and the `title` which is a required child of some targets. This parameter inserts both the relevant number as well as the title into the link.

## A.16 Graphics

### imagedata.boxed

*imagedata.boxed* — Put the images into a framed box

#### Synopsis

```
<xsl:param name="imagedata.boxed">0</xsl:param>
```

#### Description

If set to 1, put the images into a framed box.

### imagedata.default.scale

*imagedata.default.scale* — Specifies the default image scaling properties

#### Synopsis

```
<xsl:param name="imagedata.default.scale">pagebound</xsl:param>
```

**Description**

Default scale to apply to every `imagedata` that does not contain any scaling attribute.

By default this parameter is set to ``pagebound`` so that the included images keep their natural size up to the page boundaries.

Two other special parameters are available: `'maxwidth=width'` and `'maxheight=height'` where *width* and *height* define the maximum image dimensions, i.e. the image keeps its natural size up to the specified maximum dimension. Both `'maxwidth'` and `'maxheight'` settings can be combined in a comma separated list.

Example:

```
dblatex -P imagedata.default.scale=maxwidth=10cm,maxheight=8cm file.xml
```

Except these special reserved values, the expected value of the parameter must be some valid options passed to the `\includegraphics` command.

**imagedata.file.check**

*imagedata.file.check* — Make the latex compilation robust to missing images

**Synopsis**

```
<xsl:param name="imagedata.file.check">1</xsl:param>
```

**Description**

When set to 1 some tex code is added to ensure that latex compilation does not fail when the referenced `imagedata` file does not exist.

**keep.relative.image.uris**

*keep.relative.image.uris* — Should image URIs be resolved against `xml:base`?

**Synopsis**

```
<xsl:param name="keep.relative.image.uris" select="0"/>
```

**Description**

If non-zero, relative URIs (in, for example `fileref` attributes) will be used in the generated output. Otherwise, the URIs will be made absolute with respect to the base URI.

Note that the stylesheets calculate (and use) the absolute form for some purposes, this only applies to the resulting output.

## A.17 Chunning

**set.book.num**

*set.book.num* — Select a single book or all the books to compile from a set

**Synopsis**

```
<xsl:param name="set.book.num">1</xsl:param>
```

**Description**

When the document root element is a `set` this parameter can be used to select the book to print, or to publish all the books contained in the set when the value is "all". **dblatex** can only chunk the set in several books, and is not able to publish several books in a single file.

See Section 4.3.2 for more details.

**use.id.as.filename**

*use.id.as.filename* — Use ID value of chunk elements as the filename?

**Synopsis**

```
<xsl:param name="use.id.as.filename" select="0"/>
```

**Description**

If *use.id.as.filename* is non-zero, the filename of chunk elements that have IDs will be derived from the ID value.

This parameter is used only when chunking occurs, that is, when a set of books is published.

## A.18 Pagination and General Styles

**page.height**

*page.height* — The height of the physical page

**Synopsis**

```
<xsl:param name="page.height"/>
```

**Description**

The page height is generally calculated from the *paper.type* parameter.

**page.margin.bottom**

*page.margin.bottom* — The bottom margin of the page

**Synopsis**

```
<xsl:param name="page.margin.bottom"/>
```

---

**Description**

The bottom page margin is the distance from the bottom of the body including the footer to the physical bottom of the page. When empty the used latex style layout applies.

**page.margin.inner**

*page.margin.inner* — The inner page margin

**Synopsis**

```
<xsl:param name="page.margin.inner"/>
```

**Description**

The inner page margin is the distance from bound edge of the page to the first column of text.

The inner page margin is the distance from bound edge of the page to the outer edge of the first column of text.

In left-to-right text direction, this is the left margin of recto (front side) pages. For single-sided output, it is the left margin of all pages.

In right-to-left text direction, this is the right margin of recto pages. For single-sided output, this is the right margin of all pages.

**page.margin.outer**

*page.margin.outer* — The outer page margin

**Synopsis**

```
<xsl:param name="page.margin.outer"/>
```

**Description**

The outer page margin is the distance from non-bound edge of the page to the outer edge of the last column of text.

In left-to-right text direction, this is the right margin of recto (front side) pages. For single-sided output, it is the right margin of all pages.

In right-to-left text direction, this is the left margin of recto pages. For single-sided output, this is the left margin of all pages.

**page.margin.top**

*page.margin.top* — The top margin of the page

**Synopsis**

```
<xsl:param name="page.margin.top"/>
```

---

**Description**

The top page margin is the distance from the physical top of the page to the top of the body including the header.

**page.width**

*page.width* — The width of the physical page

**Synopsis**

```
<xsl:param name="page.width"/>
```

**Description**

The page width does not need to be specified when *paper.type* is set.

**paper.type**

*paper.type* — Select the paper type

**Synopsis**

```
<xsl:param name="paper.type"/>
```

**Description**

The paper type is a convenient way to specify the paper size. The list of known paper sizes includes USletter and most of the A, B, and C sizes.

When the parameter is empty, the default layout of the latex style used is applied.

When not empty, the value is directly passed to the latex geometry package, and therefore it must be a valid value understood by this package.

**geometry.options**

*geometry.options* — Raw options to pass to the geometry package

**Synopsis**

```
<xsl:param name="geometry.options"/>
```

**Description**

The content of this parameter is directly passed as options to the latex geometry package, when the page layout setup is customized by the user. Page layout customization is done through setting one or more of the pagination parameters (see below). If *geometry.options* is set but none of the other parameters is set, nothing is passed to geometry because the package is loaded only when the layout is not the default one.

---

**See Also**

[\*page.height\*](#), [\*page.margin.bottom\*](#), [\*page.margin.inner\*](#), [\*page.margin.outer\*](#), [\*page.margin.top\*](#), [\*page.width\*](#), [\*paper.type\*](#).

**doc.alignment**

[\*doc.alignment\*](#) — Specifies the text alignment of the document

**Synopsis**

```
<xsl:param name="doc.alignment"/>
```

**Description**

Defines the text alignment for the whole document. The valid values are: "left", "center", "right", "justify". An empty string is equivalent to "justify".

**doc.collab.show**

[\*doc.collab.show\*](#) — Print the document collaborators (authors, etc.) in a table

**Synopsis**

```
<xsl:param name="doc.collab.show">1</xsl:param>
```

**Description**

Show the collaborators (authors, contributors) defined in the document information block.

**doc.layout**

[\*doc.layout\*](#) — Specifies the overall document layout.

**Synopsis**

```
<xsl:param name="doc.layout">coverpage toc frontmatter mainmatter index </xsl:param>
```

**Description**

The parameter configures the overall document layout, i.e. it specifies if the document must contain a coverpage, some TOC/LOTs, a frontmatter layout (for metadata/preface/dedication rendering), an index section, etc.

See also the [\*doc.lot.show\*](#) and [\*doc.toc.show\*](#) parameters to specify the content of the TOC/LOTs.

**doc.publisher.show**

[\*doc.publisher.show\*](#) — Print the dblatex logo on the cover page?

## Synopsis

```
<xsl:param name="doc.publisher.show">0</xsl:param>
```

## Description

Print the dblatex logo on the cover page for the native docbook style if the parameter is set to 1.

## draft.mode

*draft.mode* — Select draft mode

## Synopsis

```
<xsl:param name="draft.mode">maybe</xsl:param>
```

## Description

Print `releaseinfo` in a framed box in the header, when the parameter is set to 'yes'. The `releaseinfo` is ignored if the parameter is set to 'no', or if the `releaseinfo` content is empty. When the parameter is set to 'maybe', the draft mode is deduced from the `status` attribute of the root element if set to 'draft'.

## draft.watermark

*draft.watermark* — Print a Watermak on each page in draft mode?

## Synopsis

```
<xsl:param name="draft.watermark">1</xsl:param>
```

## Description

Print the draft text (that is, "DRAFT") as a watermark on each page, if the document is in draft mode and if the parameter is set to '1'.

## latex.engine.options

*latex.engine.options* — Extra arguments to pass to the TeX engine

## Synopsis

```
<xsl:param name="latex.engine.options"/>
```

---



**Description**

This parameter enables to pass some options or extra arguments to the TeX engine used to compile the latex file built by **dblatex**. This can be usefull to tweak the PDF generation to meet some specific needs that cannot be set through latex commands. The following example asks to **xelatex** to produce PDF version 1.3 and to embed all the fonts in the PDF file:

```
$ dblatex -b xetex -V -P latex.engine.options="-output-driver='xdvipdfmx -V3 -E'" file.xml
[...]
xelatex -output-driver=xdvipdfmx -V3 -E -interaction=batchmode file.tex
[...]
xelatex -output-driver=xdvipdfmx -V3 -E -interaction=batchmode file.tex
[...]
```

**latex.class.article**

*latex.class.article* — LaTeX document class to use for article documents

**Synopsis**

```
<xsl:param name="latex.class.article">article</xsl:param>
```

**Description**

This parameter sets the document class to use for article documents.

**latex.class.book**

*latex.class.book* — LaTeX document class to use for book documents

**Synopsis**

```
<xsl:param name="latex.class.book">report</xsl:param>
```

**Description**

This parameter sets the document class to use for book documents.

**latex.class.options**

*latex.class.options* — Options passed to the `\documentclass` command

**Synopsis**

```
<xsl:param name="latex.class.options"/>
```

**Description**

Options passed to the `\documentclass` command.

---

## latex.encoding

*latex.encoding* — Encoding of the latex document to produce

### Synopsis

```
<xsl:param name="latex.encoding">latin1</xsl:param>
```

### Description

Encoding of the latex document to produce. The supported values are: "latin1" and "utf8". See Section 4.14.1 for more details about how to use it.

## latex.unicode.use

*latex.unicode.use* — Use passivetex unicode support?

### Synopsis

```
<xsl:param name="latex.unicode.use">0</xsl:param>
```

### Description

Set to 1 the passivetex unicode support is included, allowing to handle a wider range of Unicode characters (like cyrillic).

## latex.output.revhistory

*latex.output.revhistory* — Print the revhistory table?

### Synopsis

```
<xsl:param name="latex.output.revhistory">1</xsl:param>
```

### Description

The *revhistory* data are formatted as a table of the revisions if the parameter is non-zero. If the parameter is zero all the *revhistory* data are skipped.

## A.19 Font Families

### body.font.family

*body.font.family* — The default font family for body text

---

## Synopsis

```
<xsl:param name="body.font.family">DejaVu Serif</xsl:param>
```

## Description

The body font family is the default font used for text in the page body.

Currently this parameter is taken into account only when the xetex backend is used, through the [xetex.font](#).

## See Also

[xetex.font](#)

## cjk.font

[cjk.font](#) — Fonts to use in CJK environments

## Synopsis

```
<xsl:param name="cjk.font">cyberbit</xsl:param>
```

## Description

Fonts to use in CJK environments (i.e. for Chinese, Japanese or Korean documents handled by the CJK package).

## monospace.font.family

[monospace.font.family](#) — The default font family for monospace environments

## Synopsis

```
<xsl:param name="monospace.font.family">DejaVu Sans Mono</xsl:param>
```

## Description

The monospace font family is used for verbatim environments (program listings, screens, etc.).

Currently this parameter is taken into account only when the xetex backend is used, through the [xetex.font](#).

## See Also

[xetex.font](#)

## sans.font.family

[sans.font.family](#) — The default sans-serif font family

---

## Synopsis

```
<xsl:param name="sans.font.family">DejaVu Sans</xsl:param>
```

## Description

The default sans-serif font family.

Currently this parameter is taken into account only when the xetex backend is used, through the [xetex.font](#).

## See Also

[xetex.font](#)

## xetex.font

[xetex.font](#) — Specifies the fonts that XeTeX must use

## Synopsis

```
<xsl:param name="xetex.font">
  <xsl:value-of select="concat(' \setmainfont{' , $body.font.family, ' }&#10;' )"/>
  <xsl:value-of select="concat(' \setsansfont{' , $sans.font.family, ' }&#10;' )"/>
  <xsl:value-of
    select="concat(' \setmonofont{' , $monospace.font.family, ' }&#10;' )"/>
</xsl:param>
```

## Description

Font specification for XeTeX. Meaningful only when the xetex backend is used. By default the parameter sets the XeTeX configuration from the parameters [body.font.family](#), [sans.font.family](#), and [monospace.font.family](#) but you can completely override it to define a more complex setup.

## See Also

[body.font.family](#), [sans.font.family](#), [monospace.font.family](#)

## A.20 Localization

### korean.package

[korean.package](#) — Package included when Korean language is used

## Synopsis

```
<xsl:param name="korean.package">CJK</xsl:param>
```

---

**Description**

When lang is set to 'ko' and the parameter is set to 'CJK' the CJK package is included to handle the Korean language.

**latex.babel.language**

*latex.babel.language* — Force the loaded babel language

**Synopsis**

```
<xsl:param name="latex.babel.language"/>
```

**Description**

This parameter forces the use of the specified babel language whatever the document language is.

**latex.babel.use**

*latex.babel.use* — Disable the use of babel, whatever the document language is

**Synopsis**

```
<xsl:param name="latex.babel.use">1</xsl:param>
```

**Description**

Set to 1 the babel package corresponding to the document language is included. Set to 0 no babel package is included whatever the document language is.

## A.21 Prepress

**crop.marks**

*crop.marks* — Output crop marks?

**Synopsis**

```
<xsl:param name="crop.marks" select="0"/>
```

**Description**

If non-zero, crop marks will be added to each page. Crop marks are produced with the latex crop package.

**crop.paper.type**

*crop.paper.type* — Select the paper type for paper with crops

## Synopsis

```
<xsl:param name="crop.paper.type"/>
```

## Description

The paper type is a convenient way to specify the paper size. The list of known paper sizes includes USletter and most of the A, B, and C sizes.

This parameter gives the paper type of the physical page containing crops and the usefull page. The crop paper type is valid only if the overall size actually contains the usefull page whose sizes are defined with the page layout parameters.

The crop paper type is used only if *crop.marks* parameter is not set to zero.

---

### Note

The usefull page is always centered in the crop page, and there is no parameter to change this behaviour.

---

## crop.page.width

*crop.page.width* — The width of the physical crop page

## Synopsis

```
<xsl:param name="crop.page.width"/>
```

## Description

The crop page width does not need to be specified when *crop.paper.type* is set.

The parameter is used only if *crop.marks* parameter is not set to zero.

---

### Note

The usefull page is always centered in the crop page, and there is no parameter to change this behaviour.

---

## crop.page.height

*crop.page.height* — The height of the physical crop page

## Synopsis

```
<xsl:param name="crop.page.height"/>
```

---

### Description

The crop page height is generally calculated from the `crop.paper.type` parameter.

The parameter is used only if `crop.marks` parameter is not set to zero.

---

#### Note

The usefull page is always centered in the crop page, and there is no parameter to change this behaviour.

---

## crop.mode

`crop.mode` — How to display crops

### Synopsis

```
<xsl:param name="crop.mode" select="'cam'"/>
```

### Description

Mode to pass to the crop package defining the form of the crops to display when `crop.marks` is not set to zero.

The allowed values are detailed in the crop package manual.

## crop.options

`crop.options` — Raw options passed to the crop package

### Synopsis

```
<xsl:param name="crop.options"/>
```

### Description

Options directly passed to the crop package when crop marks are asked with the `crop.marks` set to non-zero.

---

## Appendix B

# Dblatex Processing Instruction Reference

This is reference documentation for all processing instructions in the dblatex XSL stylesheets.

### B.1 Bibliography

#### **bibtex**

`<?bibtex?>` — Specify how to fill a Bibliography with BibTeX

#### Synopsis

```
<?bibtex bibfiles="bib/database1,bib/database2"
          bibstyle="plain"
          mode="cited"?>
```

#### Description

This Programming Instruction is usefull to include a bibliography coming from an external bibliography database written in the well known BibTeX format. **Dblatex** will call **bibtex** to process the database.

The attributes supported by the PI are:

#### **bibfiles**

This attribute is mandatory and specifies the databases to use. The databases are separated by commas, and must not contain the file suffix (`.bib`). The bibfiles paths must be absolute or relative to the base directory of the document. You can also add some bibfile paths by using the `-L` option.

#### **bibstyle**

Optional attribute specifying the bibliographic style to apply for rendering the databases. You can also change globally the style to apply with the [latex.biblio.style](#).

The actual style file used by **bibtex** is searched in the default paths, but some extra paths can be added by using the `-l` option.

#### **mode**

Optional print mode. The available values are:

#### **all**

Print all the entries contained in the databases.

---



**cited**

Print only the entries cited in the document.

**notcited**

Print only the entries *not* cited in the document.

When the attribute is not used, the `latex.biblio.output` parameter is used as print mode. By default the print mode is set to 'all'.

**Context**

Recognized in the `bibliomixed` element.

**See Also**

- Section [4.12.2](#)
- [latex.biblio.style](#)
- [latex.biblio.output](#)

**dblatex citestyle**

`<?dblatex citestyle?>` — Sets Natbib Citation Style

**Synopsis**

```
<?dblatex citestyle="\citep[see][chap. #2]"?>
```

**Description**

Applies the given natbib citation command to a citation. As the value of `citestyle` is a LaTeX command, if square brackets “[ ]” are part of the citation text then the text must be enclosed in curly brackets “{ }” to protect them.

**Context**

Recognized in the `citation` element, only when the [citation.natbib.use](#) parameter is set to 1.

**See Also**

[citation.default.style](#)

Section [4.12.3](#)

**B.2 LaTeX**

If you do inject arbitrary LaTeX into the output stream you will probably need to use the techniques found in Section [5.5.5](#).

**latex**

`<?latex?>`, `<?db2latex?>` — Insert Arbitrary text into the LaTeX file

## Synopsis

```
<?latex content ?>
```

## Description

These Processing Instructions are unusual in that they have no “attribute”. Instead, the *content* is put directly into the generated LaTeX document.

The `<?db2latex?>` PI is deprecated and should not be used anymore. It was provided for backward compatibility. Use the `<?latex?>` PI instead.

This can provide the ultimate in customization, but can be very dangerous since it breaks the abstractions provided by dblatex.

### Warning



These Processing Instructions can be used to inject arbitrary LaTeX into the output stream. Please check if a safer customization method can be used instead. See the other [customization methods](#).

While it is pretty clear that insertion of certain sorts of LaTeX text, at some points within the document, will always be expected to work, there is no guarantee that *any* inserted LaTeX will continue to work in the future with newer versions of dblatex or its underlying software stack.

Inserting LaTeX into CDATA, i.e. in places where document text appears, is likely to be more robust than inserting LaTeX elsewhere. But again, no guarantees are made.

The `<?latex?>` Processing Instruction takes special steps to work in verbatim blocks, screen, programlisting, and literallayout elements, while `<?db2latex?>` is directly written as is.

## Context

Recognized in all elements.

## B.3 Miscellaneous

### dblatex angle

`<?dblatex angle?>` — Rotates an imagedata Image

## Synopsis

```
<?dblatex angle="90" ?>
```

## Description

Rotates the designated image by the angle given, expressed in degrees.

The default is no rotation.

## Context

Recognized in the `imagedata` element.

## texmath delimiters

`<?texmath delimiters?>` — Disable The LaTeX Mathematical Delimiters Control

### Synopsis

```
<?texmath delimiters="user" ?>
```

### Description

By default **dblatex** checks that consistent mathematical delimiters or environment are used in `alt` and it inserts the default math mode delimiters if `dblatex` thinks they are missing, but you can ask `dblatex` to write directly the `alt` content without any action. To do this, use the `texmath` Processing Instruction with `delimiters` set to `'user'`.

### Context

Recognized in the `alt` element.

### See Also

Section [4.8.1.3](#).

## B.4 Tables

### dblatex bgcolor

`<?dblatex bgcolor?>` — Sets the Background Color of A Table Element

### Synopsis

```
<?dblatex bgcolor="#00FF00"?>
<?dblatex bgcolor="{blue}"?>
<?dblatex bgcolor="[gray]{0.8}"?>
```

### Description

Set the background color of a table element. The color of a child element is inherited from its parent, with the exception of the color of row cells. These have a color which is inherited from the column in which they appear so long as no color is specified for the row. How the color is set, whether by attribute or by processing instruction, does not matter.

The color can be expressed in hexadecimal notation like for HTML (e.g. `#C0C0C0`) or in a syntax understood by the `colortbl` latex package.

The default is the value of the table's `bgcolor` attribute, or white when not otherwise specified.

## Context

Recognized in the following elements<sup>1</sup>:

- `col`
- `colgroup`
- `entry`
- `entrytbl`
- `row`

## See Also

- See Section [4.7.12](#)

## dblatex table-width

`<?dblatex table-width?>` — Control the Automatic Width of a Table

## Synopsis

```
<?dblatex table-width="12cm" ?>
```

## Description

Set the width of a table. Used only when there is at least one column in the table without a fixed width, the `table-width` has precedence over other determinants of a table's width.

The `table.width` takes the values allowed for the [default.table.width](#) param, plus more. The values shared with [default.table.width](#) are:

- A valid length (e.g. 15cm),
- A percentage of the page width (e.g. 75%),
- A keyword telling to apply an automatic column width (e.g. `autowidth.all`).

## Automatic Column Width

If you want to apply an automatic width only to some specific tables you can put the Processing Instruction `<?dblatex table-width="autowidth.scope" ?>` in the related tables. The PI has precedence over the [newtbl.autowidth](#) parameter.

The `scope` can take the following values, like in the [newtbl.autowidth](#) parameter:

### default

The automatic width (that is, latex is in charge to size the column width) is applied only to columns not having a specified `colspec` `colwidth`. It includes both undefined `colspec`, and `colspec` without the `colwidth` attribute.

### all

the automatic width is applied to any column, whether a `colspec` is provided or not.

In addition to these keywords, `table.width` can also take for its value keywords of the form `autowidth.column:N ...`, where `N` is the number of the column (counting from 1) which is to have its width automatically sized.

There is no default.

---

<sup>1</sup>HTML table elements have attributes which allow color to be specified.

**Context**

Recognized in the `table` element.

**See Also**

- Section [4.7.2](#)
- Section [4.7.7.2](#)
- [default.table.width](#)
- [newtbl.autowidth](#)

## B.5 Lists

**dblatex autowidth**

`<?dblatex autowidth?>` — Column sizing by LaTeX in `segmentedlist` tables

**Synopsis**

```
<?dblatex autowidth="all" ?>
```

**Description**

Defines, when `segmentedlists` are presented in tabular form, whether the column widths are automatically sized by latex. The allowed values are:

**default**

The automatic width (that is, latex is in charge to size the column width) is applied only to columns not having a specified `colspec` colwidth. It includes both undefined `colspec`, and `colspec` without the `colwidth` attribute.

**all**

the automatic width is applied to any column, whether a `colspec` is provided or not.

In addition to these keywords, `autowidth` can also take for its value keywords of the form `column:N ...`, where `N` is the number of the column (counting from 1) which is to have its width automatically sized. Columns with numbers not referenced, and not otherwise sized, will all have widths equally apportioned from available space.

The values `all` and `default` have identical effect in the tabular presentation of `segmentedlists`. (`segmentedlist` elements have no `colwidth` attribute.)

The `<?dblatex autowidth?>` processing instruction supersedes column width sizing specified by the [default.table.width](#) parameter or [dblatex table-width](#) processing instruction.

The default depends on whether the overall table width is specified. When there is no fixed table width columns default to the LaTeX default, the width of the widest cell. This is the default when no parameters or processing instructions are used. When a fixed table width is specified the default is “\*”, proportional spacing.

**Context**

Recognized in the `segmentedlist` element.

### See Also

- Section [4.7.2](#)
- [dblatex table-width](#)
- [dblatex colwidth](#)
- [segmentedlist.as.table](#)
- [dblatex list-presentation](#)
- [newtbl.autowidth](#)
- [default.table.width](#)

### dblatex colwidth

`<?dblatex colwidth?>` — Specifies a column width for `segmentedlists` presented as tables

### Synopsis

```
<?dblatex colwidth="3cm" ?>
```

### Description

Specifies a column width for the columns of a `segmentedlist` when presented as a table. (See [segmentedlist.as.table](#).) This is the width of the cell content and does not include inter-cell spacing.

The `colwidth` attribute may take any of the `colspec`'s `colwidth` attribute's values. These are:

- A valid TeX length (e.g. 4cm).
- A proportional width specification of the form  $N*$ , where  $N$  is a positive integer.
- A combination of the above (e.g.  $3*+1\text{cm}$ ). Spaces are not allowed.
- Any of the keywords allowed the [default.table.width](#) parameter: `autowidth.default`, `autowidth.all`, and `autowidth.none`. The first two, `autowidth.default` and `autowidth.none`, have the same meaning -- LaTeX determines the width of the column based on the width of the widest cell value. `autowidth.none` means the same as “\*”, proportional spacing.

The `<?dblatex colwidth?>` processing instruction supersedes any column width specified by the [default.table.width](#) parameter or [dblatex table-width](#) processing instruction.

The default depends on whether the overall table width is specified. When there is no fixed table width columns default to the LaTeX default, the width of the widest cell. This is the default when no parameters or processing instructions are used. When a fixed table width is specified the default is “\*”, proportional spacing.

### Context

Recognized in the `segtitle` element.

---

**See Also**

- [Section 4.7.2](#)
- [dblatex table-width](#)
- [segmentedlist.as.table](#)
- [dblatex list-presentation](#)
- [newtbl.autowidth](#)
- [default.table.width](#)

**dblatex list-presentation**

`<?dblatex list-presentation?>` — Specifies presentation style for a `segmentedlist`

**Synopsis**

```
<?dblatex list-presentation="list|table" ?>
```

**Description**

Use the `<?dblatex list-presentation?>` PI as a child of a `segmentedlist` to control the presentation style for the list (to cause it, for example, to be displayed as a table).

The value of `list-presentation` must be one of the following:

**list**

Display as a term-by-term list. The `segmentedlist`'s `seg` values are output like `variablelist listitem` values, one per line. The `segtitle` values appear as `variablelist terms` values do. Unlike a `variablelist`, the list is formatted without indentation.

**table**

Display as a table. The `segtitle` values are the column headings.

**Context**

Recognized in the `segmentedlist` element.

**See Also**

- [segmentedlist.as.table](#)
- Inline presentation:
  - [seg.item.separator](#)
- Table presentation:
  - [Section 4.7.2](#)
  - [dblatex colwidth](#)
  - [dblatex table-width](#)
  - [newtbl.autowidth](#)
  - [dblatex autowidth](#)
  - [default.table.width](#)

## Chapter 8

# Index

### P

#### Parameters, 61

- alt.use, 68
- annotation.support, 85
- beginpage.as.pagebreak, 86
- biblioentry.item.separator, 82
- biblioentry.numbered, 82
- bibliography.numbered, 65, 67, 69–71
- bibliography.tocdepth, 65, 67, 69–71
- body.font.family, 107, 109
- callout.linkends.hot, 62
- callout.markup.circled, 63
- calloutlist.style, 63
- citation.default.style, 39, 83
- citation.natbib.options, 39, 83
- citation.natbib.use, 39, 83
- cjk.font, 108
- co.linkends.show, 63
- colophon.tocdepth, 17, 65
- crop.marks, 110–112
- crop.mode, 112
- crop.options, 112
- crop.page.height, 111
- crop.page.width, 111
- crop.paper.type, 110–112
- dedication.tocdepth, 17, 66
- default.table.rules, 29, 78
- default.table.width, 20, 23, 78
- doc.alignment, 104
- doc.collab.show, 104
- doc.layout, 104
- doc.lot.show, 64, 104
- doc.pdfcreator.show, 71
- doc.publisher.show, 104
- doc.section.depth, 17, 86
- doc.toc.show, 64, 104
- draft.mode, 105
- draft.watermark, 105
- endnotes.heading.command, 43, 86, 87
- endnotes.heading.groups, 43, 87
- endnotes.heading.style, 43, 87
- endnotes.properties, 42, 87, 91
- equation.default.position, 88
- example.default.position, 88, 89
- example.float.type, 89
- figure.anchor.top, 89
- figure.caution, 61
- figure.default.position, 89, 90
- figure.important, 61
- figure.note, 62
- figure.tip, 62
- figure.title.top, 89, 90
- figure.warning, 62
- filename.as.url, 90
- footnote.as.endnote, 41, 88, 90
- funcsynopsis.decoration, 72
- funcsynopsis.style, 72
- function.parens, 72
- geometry.options, 103
- glossary.numbered, 65–67, 69–71
- glossary.tocdepth, 65–67, 69–71
- glossterm.auto.link, 85
- hyphenation.format, 91, 95
- imagedata.boxed, 99
- imagedata.default.scale, 99
- imagedata.file.check, 100
- imageobjectco.hide, 63
- index.numbered, 65, 67, 69–71
- index.tocdepth, 65, 67, 69–71
- insert.xref.page.number, 80
- keep.relative.image.uris, 100
- korean.package, 109
- latex.babel.language, 110
- latex.babel.use, 110
- latex.bibfiles, 84
- latex.biblio.output, 38, 84, 114
- latex.biblio.style, 38, 84, 113
- latex.bibwidelabel, 85
- latex.class.article, 106
- latex.class.book, 106
- latex.class.options, 106
- latex.encoding, 40, 59, 107
- latex.engine.options, 105
- latex.hyperparam, 79
- latex.index.language, 37, 67, 68
- latex.index.tool, 36, 67, 68



- latex.output.revhistory, [107](#)
- latex.unicode.use, [40](#), [59](#), [107](#)
- linenumbers.default, [92](#)
- linenumbers.everyNth, [92](#)
- linenumbers.scope, [91](#), [92](#)
- literal.class, [33](#), [93](#)
- literal.environment, [36](#), [94](#), [95](#)
- literal.extensions, [33](#), [94](#)
- literal.layout.options, [35](#), [92](#)
- literal.lines.showall, [93](#)
- literal.role, [33](#), [93](#)
- literal.width.ignore, [93](#)
- make.single.year.ranges, [71](#)
- make.year.ranges, [71](#)
- mediaobject.caption.style, [95](#)
- monoseq.hyphenation, [91](#), [95](#)
- monoseq.small, [95](#)
- monospace.font.family, [108](#), [109](#)
- newtbl.autowidth, [22](#), [23](#), [73](#), [78](#), [117](#)
- newtbl.bgcolor.thead, [74](#)
- newtbl.default.colsep, [74](#)
- newtbl.default.rowsep, [75](#)
- newtbl.format.tbody, [75](#)
- newtbl.format.tfoot, [75](#)
- newtbl.format.thead, [75](#)
- newtbl.use.hhline, [76](#)
- page.height, [101](#), [104](#)
- page.margin.bottom, [101](#), [104](#)
- page.margin.inner, [102](#), [104](#)
- page.margin.outer, [102](#), [104](#)
- page.margin.top, [102](#), [104](#)
- page.width, [103](#), [104](#)
- paper.type, [101](#), [103](#), [104](#)
- pdf.annot.options, [96](#)
- preface.tocdepth, [17](#), [65–68](#)
- qanda.defaultlabel, [82](#)
- refclass.suppress, [72](#)
- refentry.generate.name, [73](#)
- refentry.numbered, [65](#), [67–70](#)
- refentry.tocdepth, [65](#), [67–71](#)
- refentry.xref.manvolnum, [73](#)
- sans.font.family, [108](#), [109](#)
- seg.item.separator, [97](#)
- segmentedlist.as.table, [96](#)
- set.book.num, [14](#), [100](#)
- show.comments, [97](#)
- table.continue.caption, [76](#)
- table.default.position, [76](#)
- table.default.tabstyle, [24](#), [76](#)
- table.in.float, [77](#)
- table.title.top, [77](#)
- term.breakline, [81](#)
- tex.math.in.alt, [68](#), [69](#)
- texlive.version, [97](#)
- titleabbrev.in.toc, [64](#)
- toc.section.depth, [17](#), [65](#)
- ulink.footnotes, [41](#), [98](#)

- ulink.show, [41](#), [98](#)
- use.id.as.filename, [14](#), [101](#)
- variablelist.term.separator, [81](#), [82](#)
- xetex.font, [96](#), [108](#), [109](#)
- xref.hypermarkup, [81](#)
- xref.with.number.and.title, [99](#)

Processing Instructions, [113](#)

- bibtex, [113](#)
- dblatex angle, [115](#)
- dblatex autowidth, [118](#)
- dblatex bgcolor, [116](#)
- dblatex citestyle, [114](#)
- dblatex colwidth, [119](#)
- dblatex list-presentation, [120](#)
- dblatex table-width, [117](#)
- latex, [114](#), [115](#)
- texmath delimiters, [116](#)